BM 127.37 - C. of W. Brass disc in Top Cb N.S. Mt. Vernon @ E.L. Bluff @ 2' and Return

BLUFF

MT. VERNON

Golf Green

Golf Green

Golf Green

Golf Green

SCALE: Hor. 1"=50'
Ver. 1"=5'

Park Maintenance Shop

1-6" House Services

Water Line

Constr. Manhole
Sta. 0+00

Tee Mound

1' Ex. 30" CP

42" RCP SWS

Constr. Manhole
Sta. 3+00
3+99.0

Water Line

Constr. Manhole
Sta. 7+00; ~~23+98.50~~
7+53.0

Constr. Manhole
Sta. 10+00; Δ=51° 10'
10+73.1

Abandon Manholes
Plug Pipes

Plug

Abandon Manholes
Plug Pipes

Creek Bank

Abandon Manhole
Plug Pipes

GENERAL NOTES

1. ALL CLAY PIPE SHALL BE EXTRA STRENGTH.
2. SAND FILL AND FLUSHING WILL NOT BE PAID FOR SEPARATELY AND THESE COSTS ARE TO BE INCLUDED IN THE UNIT PRICE BID FOR SEWER PIPE.
3. CONTRACTOR'S CONSTRUCTION METHODS SHALL BE SUCH THAT WILL PROVIDE CONTINUOUS FLOW OF SEWAGE DURING CONSTRUCTION OF THIS PROJECT. CONTRACTOR'S METHOD OF HANDLING SEWAGE FLOW SHALL MEET WITH THE APPROVAL OF THE ENGINEER.
4. MANHOLES TO BE ABANDONED SHALL HAVE THE TOP FOUR FEET REMOVED WITH THE REMAINING PORTION FILLED WITH SAND.
5. ALL AREAS DISTURBED DURING CONSTRUCTION SHALL BE LEVELED AND GRADED TO MATCH ADJACENT GROUND ELEVATIONS WITHOUT DEPRESSIONS WHICH WOULD POND WATER.
6. CONTRACTOR'S CONSTRUCTION METHODS SHALL BE SUCH THAT WILL PREVENT ANY DAMAGE TO GOLF GREENS. ANY DAMAGE TO GOLF GREENS BY CONTRACTOR'S OPERATIONS SHALL BE REPAIRED BY THE CONTRACTOR TO THE SATISFACTION OF ~~THE~~ PARK DEPARTMENT WITHOUT ANY ADDITIONAL COMPENSATION.

Sta. 0+00 Constr. Type A 5' dia. Manhole
Top 1855.0

Ex. 42" SWS

Sta. 3+00 Constr. Type A 5' dia. Manhole
Top 1854.00

Water Line

Water Line

Sta. 7+45.11
Constr. Type A 5' dia. Manhole

Existing Ground

FIELD CHANGE

Sta. 10+76 Constr. Type A 5' dia. Manhole
Top 1858.50

140
135
130
125
120
115

1114.66
114.66
114.86
115.24
115.24
115.66
115.66
115.86
116.04
116.26
116.46
Ex. 30" CP
Ex. 42" SWS
Ex. 48" SWS
Ex. 54" SWS
Ex. 60" SWS
Ex. 66" SWS
Ex. 72" SWS
Ex. 78" SWS
Ex. 84" SWS
Ex. 90" SWS
Ex. 96" SWS
Ex. 102" SWS
Ex. 108" SWS
Ex. 114" SWS
Ex. 116.11

1075' of 30" CP @ +0.20%

As Built 9-11-75

Rev. 1-24-75

SUPPLEMENT DRY CREEK SUBMAIN 1 & DRY CREEK SUBMAIN 2, SANITARY SEWER 18, ALONG DRY CREEK FROM 230' NORTH OF MT. VERNON TO 500' NORTH OF MEADOWLANE

CITY OF WICHITA, KANSAS

R. W. LINN, CITY ENGINEER

DATE: November 1974

Project No. DSAM 574084 Sheet 1 of 3

DONALD E. SCHNEIDER LICENSED 6311 KANSAS PROFESSIONAL ENGINEER

K&E PLATE 1 PLASTIC FILE SUPER E PRINT CO.

DCD 115

1/3

Constr. Manhole
Sta. ~~10+73.2~~; Δ=51°10'
10+73.2

Constr. Manhole (Outside Drop)
Sta. ~~14+50.5~~; ~~24+57.1~~
14+50.1

Install 8" Outside Drop

Plug

Abandon Manholes
Plug Pipes

Creek Bank

Golf Green

Constr. Manhole
16+86.1

MANHOLE LAYOUT STA 16+63.80

30° C.P.

Remove 21" C.P.

5' dia.

11'

VOID

Plug Pipes Phase 2

Constr. Manhole
Sta. ~~20+65.24~~; Δ=24°12'
20+65.1

Constr. Manhole
Sta. ~~24+57.15~~; Δ=3°08'30"
24+57.1

Sta. 24+65. End Const. and plug pipe.

Golf Green

SCALE: Hor. 1"=50'
Ver. 1"=5'

Creek Bank

Sta. 10+79 Type A 5' dia. Manhole
Top 128.50
Out 116.81
In 116.71

Sta. 14+46.05 Type A 5' dia. Manhole
Top 129.10
Out 117.98
In 117.88
Ex. 18" in 123.26

Water Line

Sta. 16+63.80 Type A 5' dia. Manhole
Top 130.20
30° Cut 118.79
New 21" In 118.24
Ex. 21" In 118.14

Existing Ground

FILLED CHANGE

Sta. 20+43.80
Type A 5' dia. Manhole
Top 137.90
Out 118.89
In 118.79

1390' of 30" C.P. @ +0.20%

Sta. 24+57.15
Type A 5' dia. Manhole
Top 137.80

Sta. 24+65. End Construction and Plug Pipe.
Out 119.72
In 119.62

160
135
130
125
120
115

116.76 11
116.36 12
117.16 15
117.36 14
117.96 13
117.86 16
118.16 17
118.36 18
118.56 19
118.76 20
119.06 21
119.26 22
119.46 23
119.66 24
119.87 +65

Rev. 1-26-75

Sheet 2 of 3

SUPPLEMENT DRY CREEK SUB. 1 & 2, 35th & 18, Project No. DBKM 5740.84

2/3

K&E PLATE 1 PLAN PROFILE

FILMED FROM THE BEST AVAILABLE COPY

B.M. 142.433 City Std on W. and Hkgd. to SCB approx. 150 E. of Oliver on Harry

Constr. Manhole Sta. 24+57.13; Δ=3°08'30"

Constr. Manhole Sta. 28+57.13

Remove Manhole

Water Line

Constr. Manhole Sta. 32+57.13

Flo. 124.5

Flo. 121.34

Plug

Golf Green.

HARRY

OLIVER

Golf Green

Golf Green

SCALE: Hor. 1"=50'
Ver. 1"=5'

NOTE: ALL WORK INDICATED ON THIS SHEET BETWEEN STA. 24+65 AND STA. 32+57.15 IS NOT A PART OF THIS PROJECT. THIS SHEET IS FURNISHED FOR INFORMATION ONLY.

Sta 24+57.15
Type A 5' dia. Manhole
Top 137.20

Sta 28+57.15
Type A 5' dia. Manhole
Top 133.40

Sta 32+57.15
Type A 5' dia. Manhole
Top 130.60

Existing Ground

Water Line

140
135
130
125
120

Out 112.71
In 110.87

120.67

Out 121.47
21" In 121.64
21" In 124.58

792.15' of 30" CP @ +0.20%

24+65	25	26	27	28	29	30	31	32
112.%	120.16	120.86	120.50	120.76	120.76	121.16	121.36	

K&E PLATE PLANIPRINTER KEUFFEL & ESSER CO. MADE IN U.S.A.

Sheet 2 of 3

SUPPLEMENT DRY CREEK SUB. 1 & 2, 59-12, Project No. DBKM 574084

2/3

N S 7 (15)

OCD 115

FILMED FROM THE BEST AVAILABLE COPY