ANNA ST.

REPLAT OF PART OF LOT 31 R.A. MORRIS TRACTS

REPLAT OF LOT 1 AND PART OF LOTS 2 AND 32 R.A. MORRIS TRACTS AND LOT 5 R.A. MORRIS GARDENS

20' TEMP. EASEMENT

Eugene Guldeman Part of Lot 31 R.A. Morris Tracts

STATION 3+00

STATION 6+00

PLUG @ ℄ STATION 6+34

Existing 15" VCP

STATION 0+00

11' TH.

Scale 1"=40'

Note
REPLACE FENCE & CLOTHESLINE POLES.

LOT #17 R.A. MORRIS GARDENS

James Murray 1525 W. 12th

Eugene Guldeman 1231 Baker

Robt. K. Hodges 1237 Baker

Robt. T. Leach 1257 Baker

BAKER ST.

B.M. 131.47 STEPBENCH NS HLP SS 11TH. @ 10' E & BAKER NO.

PLAN SCALE 1"=40'
PROFILE SCALE 1"=40' HOR., 1"=4' VERTICAL

STATION 0+00 EXISTING M.H.

STATION 3+00 STANDARD M.H.

STATION 6+00 STANDARD M.H.

BAKER CURB

NATURAL GROUND

600 LIN. FT. 8" VCP @ 1.0% GRADE

120.00 FLO

17.00 IN

CONST. DROP STACK TO WITHIN 4' OF FLOOR OF M.H.

109.53 BUT

56 LIN. FT. 8" VCP @ 0.60% GRADE

123.00 FLO

123.34 FLO

600 LIN. FT. 8" VCP @ 1.0% GRADE

56 LIN. FT. 8" VCP @ 0.60% GRADE

LATERAL 151. SUB. 5 SAN. SEWER 22
CITY OF WICHITA, KANSAS
B.E. SMITH CITY ENGINEER
PROJ. NO. C20-31 · DATE: June 1961