BM. 126.44 City Std. Disc. 94' East & 94' North of ℄ of West Street and 13th Street.

Plan Scale: 1" = 40'
Profile Scale: 1" = 40' Horz.
1" = 5' Vert.

Sta 0+00
Existing M.H.
Begin Construction
8" Pipe.

1+04.5
Sta 1+05
Const. Std M.H.
Type 'A' or 'C'

3+82.0
Sta 3+75
Const. Std MH
Type 'A' or 'C'

5+82.7
Sta 5+75
End Construction
Plug Pipe

WOMERS 5 6
WEST ② 3
LYNN 2 1
5TH 5 4
ADDITION ① 3 2 1

HARLAN AVENUE

OTT STREET

20' Utility Easement
10' Utility Easement

Note: Block 1 is not in the benefit district.

Field Engineer to make 'ties' to all irons.
Irons disturbed or destroyed are to be replaced.

NOTE: CONTRACTOR SHALL EXERCISE CAUTION SUCH THAT HIS OPERATIONS WILL PREVENT DAMAGE TO EXISTING PAVEMENT ON HARLAN AVENUE. ANY PAVEMENT DAMAGE BY THE CONTRACTOR SHALL BE REPLACED BY THE CONTRACTOR WITHOUT ADDITIONAL COMPENSATION.

Sta 0+00 Begin Const 8" Pipe at Existing M.H.
Sta 1+05 Const Std M.H. Type 'A' or 'C' Rim Elev 1128.57
Sta 3+28 Const Std M.H. Type 'A' or 'C' Rim Elev 1128.79
Sta 5+28 Plug Pipe End Construction

Natural Ground
Well Graded
Top of Curb

130
125
120
115

Flo Elev 116.93
Flo Elev 117.85
Flo Elev 117.55
Flo Elev 118.33
Flo Elev 118.64
Flo Elev 118.72
Flo Elev 118.45
Flo Elev 118.64

573 Lin Ft of 8" Std Pipe at 0.5% Grade
Alt 8" ASB Composite Pipe

0 1 2 3 4 5 6

As built 9-22-77

RONALD E. SCHNEIDER
LICENSED
6311
KANSAS
PROFESSIONAL ENGINEER

LAT 217 MAIN 5 S.S. 22
CITY OF WICHITA, KANSAS
R.W. LINN CITY ENGINEER
DATE: April 1922 PROJECT NUMBER: DBKL574024

PLAN
LOCATED
NOTE BOOK PAGE
No. 0095

PROFILE
SURVEY
NOTE BOOK PAGE
No. 0095

PLATE 1-SINGLE PLAN AND PROFILE-FULL LINE
NICHOLAS STERN & CO. INDIANAPOLIS, INDIANA
ON 75 CENTIMETRICAL TRACING PAPER
PRINTED IN U.S.A.