


DATE	
BY	
REFERENCES NOTED	
REFERENCES CHECKED	

	Quantity	
Paving Items		
AC Pavement 5"	1,542	sy
Concrete Pavement (5")	5,644	sy
Concrete Sidewalk (4")	3,112	sf
Concrete Pavement (8") (Reinforced)	842	sy
Comb. C & G (6" & 1 1/2").	292	lf
Roll C&G (3 5/8")	160	lf
Median C&G (6")	177	lf
Mono Edge Curb (6 5/8" & 1 1/2")	139	lf
Wheelchair Ramp Construction	1,653	sf
Subtotal		
Earth Work Items		
Ditch Grading (Swales)	2214	lf
Subtotal		
General Items		
Sawed Joint	244	lf
MH, Adj. w/ new ring and cover	2	ea
Sidewalk, Drives, Parking Lot Removed	1200	sy
Fence Removed & Re-set	93	lf
Site Clearing and Restoration	1	ls
Mobilization	1	ls
Adjust sanitary sewer manhole	1	ea
Subtotal		
Traffic Items		
Street Signage	1	LS
Pavement Marking	1	LS
Traffic Control	1	LS
Subtotal		
Drainage Items		
SWS Pipe RCP 15"	254	lf
Inlet, Drop 2'x2'	5	ea
8" D.I.P.	248	lf
12" HDPE pipe	267	lf
Driveway Grated Inlet	1	ea
Std. Manhole (4' dia.)	2	ea
Inlet Sediment Barrier	18	ea
Silt Fence	1,092	lf

	Quantity	
Landscaping and Amenities		
Bulk Steel Allowance	1	ls
Entry Columns	4	ea
4" Concrete Pavement	1,815	sf
Bollard Installation	14	ea
6' Black Chain Link	1,162	lf
Concrete Pavers	1,025	sf
Paver edge restraint	13	lf
12" Concrete Band	175	lf
6" Concrete Band	63	lf
Drinking fountain	1	ea
Water meter and service (1")	1	ea
Bench	10	ea
Bike Rack	6	ea
Trash Receptacle	6	ea
Anti-Graffiti Sealer	1	ls
Topsoil	1,142	cy
Raingarden Bed Preparation	1,213	sf
Arkansas Sandstone	14	ton
6" PVC Pond Drain Line	29	lf
12" Drain Basin	1	ea
Overstory Trees	88	ea
Understory Trees	46	ea
Shrubs - 5 gallon	68	ea
Shrubs - 3 gallon	80	ea
Shrubs - 1 gallon	15	ea
Perennials - Plugs	1,551	ea
Seeding	150,000	sf
Mulch	40	cy
Lighting		
Poles, fixtures, bases, controls and service	1	ls
Artist Allowance		
Steel Arch	2	ea
Bollards	1	ls
Construction Subtotal		
Administration 2%		
Publication		
Material from Water & Sewer		
Contingency		
Alternate #1		
Clock Tower	1	ea
Alternate #2		
Ornamental Steel Fence (in lieu of Chain Link)		lf

MIDTOWN SUMMARY OF QUANTITIES WICHITA, KANSAS		DESIGN: TCR DRAWN: EJB REVIEW: [blank] UTILITY: [blank]
 Ruggles & Bohm, P.A. Engineering, Surveying, Land Planning 824 North Main Wichita, Kansas 67203 www.rbkansas.com	(316) 264-8008 (316) 264-4821 fax E-mail: info@rbkansas.com	SHEET: 43 OF: 70
	DRAWING FILE: Quantities PROJECT NUMBER: 472-84008 DATE: May 16, 2008	