



CONTRACTOR SHALL REMOVE COLD MIX PAVEMENT FROM STA. 63+00 TO 64+95 AND REPLACE WITH X PAVEMENT PER PAVING SECTION. SEE SHEET 11 FOR DETAIL.

ABANDON LINE WEST OF MANHOLE WITH 3" CONCRETE PLUG IN MANHOLE.

CONTRACTOR TO COORDINATE WITH SDG CO. ELEC. COOP TO SUPPORT POLES DURING CONSTRUCTION. COST SUBSIDIARY TO PROJECT.

REMOVE AND RESET 72 LF. 18" X 30" HERO P.

CONTRACTOR TO COORDINATE WITH WESTAR TO SUPPORT POLES DURING CONSTRUCTION. COST SUBSIDIARY TO PROJECT.

MH-25 STA. 65+74.18 LINE 1  
R.L. STA. 74+17.51, 22.5' RT.  
CONSTRUCT 5' DIA. LINED MH TYPE P WITH BOLTED AND GASSETEED LD.  
TOP = 1357.6

Scale 1" = 40' (HORIZ)  
1" = 5' (VERT.)



**RUGGLES & BOHM**  
ENGINEERING, SURVEYING & LAND PLANNING  
804 North Main  
Wichita, Kansas 67203  
www.rugglesandbohm.com  
E-mail: info@ruggles.com

MAIN 4 - NORTHWEST INTERCEPTOR  
WICHITA, KANSAS

PROJECT NUMBER 468-83889	DESIGN KWL	DRAWN RA	REVISIONS
DRAWING FILE base [s07]	UTILITY	DATE July 10, 2006	REVIEW