


SUMMARY OF QUANTITIES

FHWA REG NO.	STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
7	KANSAS	87 N-0301-01	2003	16-A	36

Items	Quantity	Unit
Mobilization	1	LS
Mobilization (DBE)	1	LS
Field Office and Lab (Type A)	1	ea
AC Pavement 7" (5" Bit Base)	8,930	sy
AC Pavement 5" (3" Bit Base)	307	sy
8" Reinf. Crushed Rock Base w/Geogrid	12,692	sy
5" Reinf. Crushed Rock Base w/Geogrid	326	sy
Comb. C & G Type 1 (6" & 1 1/2")	4,347	lf
Concrete Header	30	lf
Median Comb C&G	799	lf
Monolithic Edge Curb (6" & 1 1/2")	673	lf
8" RCVG Pavement	1,311	sy
Concrete Sidewalk (4")	21,545	sf
Paving Brick (2 5/8")	112	sy
Wheelchair Ramps, Std.	14	ea
Pavement Removed	8,396	sy
Sidewalk Removed	642	sf
Hedgerow Removed	348	lf
Trees Removed	28	ea
Combined Curb and Gutter Removed	710	lf
Excavation	9,351	cy
Compacted Fill (90% Density)	1,331	cy
Site Clearing	1	LS
Site Restoration	1	LS
Erosion Control	1	LS
Temporary Project Seeding	1	LS
Pavement Marking	1	LS
Signage	1	LS
Traffic Control	1	LS
SWS Pipe RCP 24"	1,993	lf
SWS Pipe RCP 18"	90	lf
SWS Pipe RCP 15"	185	lf
Inlet, Curb 1A (L=5' W=3')	5	ea
Inlet, Curb 1A (L=5' W=4')	4	ea
Inlet, Curb 1A (L=10' W=3')	1	ea
Inlet, Curb 1A (L=10' W=4')	2	ea
Inlet Hookup	12	ea
Inlet Removed	2	ea
MH, Std.	2	ea
Sediment Barrier, Inlet	13	ea
SWS Pipe Removed, 0"-20"	433	lf
SWS Pipe Removed, 21"-48"	35	lf
Lacebark Elm - 2" cal.	6	ea
Amur Maple - 1 1/2" cal.	5	ea
Sugar Caddo Maple - 2" cal.	10	ea
Goldenrain Tree - 2" cal.	10	ea
Chanticleer Pear - 1 1/2" cal.	25	ea
Snowdrift Crabapple - 1 1/2" cal.	20	ea
Chinese Pistache - 2" cal.	27	ea
Red Bud - 1 1/2" cal.	53	ea
Shumard Oak - 2" cal.	12	ea
Imperial Honeylocust - 2" cal.	22	ea
Sawtooth Oak - 2" cal.	16	ea
Bald Cypress - 2" cal.	34	ea
Fescue Sod	450	sy
8" Reinforced Concrete Drive Pavement	2,095	sf
Survey Monument Box	1	ea
Non-Participating Items		
3" PVC	116	lf
Transportation of Salvagable Material	1	ls
Adjustment of Water Valves	11	ea
Relocate / Reconstruct Private Sprinkler System	1	ls
Design-Build Irrigation System	3	ea

 <p>THE CITY OF WICHITA</p> <p>CITY ENGINEER'S OFFICE 425 NORTH MAIN STREET WICHITA, KANSAS 67202 (316) 268-4501 (316) 268-4114 FAX</p>	SUMMARY OF QUANTITIES	
	NEIL D. CABLE, P.E. - CITY ENGINEER	
	PROJECT NUMBER 472-83890	INDEX CODE 706875
	DATE DEC 03	SHEET 16-A OF 36