



Sta. 9+79.68 Wheelchair Ramp, Lt. By Others
W = 5'-0"
See Sh. No. 7

Sta. 9+67.46 8" Reinf. Conc. Valley Gutter, 0.00' Lt. By Others
See Sh. No. 5

Sta. 9+23.43 =
Sta. 48+25.14 on Central N -0.6295
E 4825.1368

Sta. 9+79.67 Wheelchair Ramp, Rt. By Others
W = 5'-0"
See Sh. No. 7

Sta. 10+20.11 Adjust Exist. Manhole, 20.72' Rt. Replace Frame and Lid

Sta. 10+38.54 Adjust Exist. Manhole, 1.90' Rt.

Sta. 11+66.53 Const. full-radius 8" Reinf. Conc. Drive Ent., 15.50' Lt. W = 24.0'
See Sh. No. 6

Sta. 12+16.51, 20.45' Rt. Install 12" Nyloplast Catch Basin (H-25) with Solid lid. Connect to Exist. 6" PVC Pipe (E). Field verify Invert Elevations. Remove Existing line (W). Removal shall be Subsidiary. See Sh. No. 10

Install 33.6 L.F. of 6" PVC Drain Pipe. Connect to Curb Inlet (N) See Sh. No. 10

Sta. 12+76.66 Const. Curb Inlet (Type II), 14.68' Lt. W=3'-4 3/8", L=6'-2 1/2" Inlet Top = 176.77 Install 24"x12.06' RCP (W) \bar{E} Out= 172.58 W/End Section, \bar{E} = 172.52 Install Underdrain See Sh. No. 8, 9

Sta. 12+82.87 Const. Curb Inlet (Type II), 14.68' Lt. W=3'-4 3/8", L=6'-2 1/2" Inlet Top = 176.77 See Sh. No. 8

Sta. 13+34.47 Const. Curb Inlet (Type II), 14.68' Rt. W=3'-4 3/8", L=6'-2 1/2" Inlet Top = 176.77 See Sh. No. 8

Sta. 12+76.66 Const. Curb Inlet (Type II), 14.68' Rt. W=3'-4 3/8", L=6'-2 1/2" Inlet Top = 176.77 Install 24"x27.34' RCP (W) \bar{E} Out= 172.66 Install Underdrain See Sh. No. 8, 9

- UTILITIES**
- COX COMMUNICATIONS (CABLE) 262-0661
 - WESTAR (ELECTRIC) 261-6512
 - KANSAS GAS SERVICE (GAS) 832-3101
 - SBC (TELEPHONE) 800-870-8390
 - CITY OF WICHITA WATER & SEWER 262-6000
 - AQUILA (GAS) 946-0096

- LEGEND**
- 6.46 Elevation at Flowline of Curb
 - 177.01 Elevation at Top of Curb
 - Pavement Removal
 - Trees to be Removed

BM #1: Cut "C" at East End of RCBC, North Side of Central
Sta. 47+56.27, 28.95' Lt. Elev. = 178.45

UTILITY ADJUSTMENTS			
DESCRIPTION	STATION/OFFSET	EXIST. TOP	PROP. TOP
Sanitary Sewer Manhole	10+20.11, 20.72' Rt.	179.52	179.90
Sanitary Sewer Manhole	10+38.54, 1.90' Rt.	178.89	179.21

NOTE:
The Proposed Improvements shall match Proposed Construction on Central Avenue. Contractor shall coordinate Construction activities with Central Contractor.

Top of Curb Elevations shown are for Full-Height Curb

J:\Civil\06656\Par\06656-E1.dwg 11/20/2006 10:22:38 AM CST

BROOKSIDE PARKWAY PAVING IMPROVEMENTS
PROJECT NAME

PLAN SHEET
SHEET TITLE

JRA DESIGN BY:	JSB DRAWN BY:	JRA CHECKED BY:
JAN. 2007 DATE	06656 JOB NO.	3 / 23 SHEET/OF

411 N. WEBB ROAD
WICHITA, KS. 67206
316-684-9600