



**UTILITY LEGEND**

= Fire Hydrant	= Flag Pole
= Water Meter	= SS Manhole
= Water Valve	= SWS Manhole
= Gas Meter	= Sign
= Gas Valve	= Misc. Post
= Telephone Riser	= Guy Anchor
= Mailbox	= Power Pole
= Deciduous Tree or Shrub	= Light Pole
= Existing Fence	
= Right of Way Line	
= Underground Telephone	
= Underground Electric	
= Overhead Electric	
= Water Line	
= Sanitary Sewer	
= Gas Line	
= Cable TV or Fiber Optic	

**HORIZONTAL CONTROL POINTS**

C.P. NO. 1	N 20000.00 E 20000.00	1/2" REBAR w/TERRA TECH CAP FOUND ON SOUTH PROPERTY LINE LOT 25, SPURRIER GARDENS ADDITION
C.P. NO. 2	N 19940.00 E 20000.09	1/2" REBAR w/SAVOY CAP SET ON NORTHEAST PROPERTY CORNER LOT 24, SPURRIER GARDENS ADDITION
C.P. NO. 3	N 19939.40 E 19758.32	1/2" REBAR FOUND ON NORTHWEST PROPERTY CORNER LOT 24, SPURRIER GARDENS ADDITION
C.P. NO. 4	N 19997.16 E 19097.90	1/2" IRON PIPE FOUND ON SOUTHWEST PROPERTY CORNER LOT 30, SPURRIER GARDENS ADDITION

UTILITIES SHOWN REPRESENT THE BEST INFORMATION AVAILABLE FOR DESIGN. ADDITIONAL UTILITIES MAY BE PRESENT ON THIS PROJECT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING THE EXACT LOCATION, DEPTH AND SIZE OF ALL UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL BE LIABLE FOR ANY DAMAGE CAUSED BY THE FAILURE TO DO SO.

Bench Mark: Square Cut " Top of Drive 10.5' N. & 1.5' W. of the N.W. corner Lot 24, Spurrier Gardens Sedgwick County, Kansas. Elevation = 1348.64 NGVD88

**SURVEY DISCLAIMER:**  
TOPOGRAPHIC SURVEY AND CONTOUR MAP USED IN PREPARING PLANS WAS PROVIDED BY SAVOY COMPANY, P.A., 535 S. EMPORIA, SUITE 104, WICHITA, KS. ENGINEER DOES NOT GUARANTEE SURVEY ELEVATIONS FOR ACCURACY. CONTRACTOR SHALL VERIFY ELEVATIONS AND NOTIFY ENGINEER OF ANY DISCREPANCIES.

WATER LINE PLANS FOR  
**SITE PLAN**  
FIRE STATION #20, WICHITA, SEDGWICK COUNTY, KS  
CED PROJ. NO.: 20071568  
**CERTIFIED ENGINEERING DESIGN, P.A.**  
810 WEST DOUGLAS, SUITE C  
WICHITA, KANSAS 67203  
PH.(316)262-8808 FAX.(316)262-1669

DESIGNED: HDF	SCALE: 1"=20'	SHEET 2
DRAWN: JDT	DATE: 04-08	
CHECKED: HDF	CED FILE: FireStation20-Base(1-21-08)	TOTAL 5