

REINF CONC DRIVE PAVEMENT (8") (INCL WWF)

STATION	ROADWAY	SIDE	AREA (Sq. Ft.)
11+68.87	West St.	Rt.	893.51
11+89.73	West St.	Lt.	484.51
12+63.96	West St.	Lt.	513.82
13+24.79	West St.	Rt.	661.23
13+99.04	West St.	Rt.	655.03
14+05.32	West St.	Lt.	534.30
14+74.70	West St.	Rt.	617.39
15+04.24	West St.	Lt.	529.92
15+48.94	West St.	Lt.	522.00
16+50.00	West St.	Lt.	402.00
16+50.79	West St.	Rt.	522.00
17+00.91	West St.	Rt.	543.58
17+33.00	West St.	Lt.	616.85
17+77.25	West St.	Rt.	379.64
17+93.42	West St.	Lt.	653.64
18+24.88	West St.	Rt.	379.68
18+86.41	West St.	Lt.	755.48
19+10.66	West St.	Rt.	540.95
19+55.29	West St.	Rt.	526.06
19+98.66	West St.	Lt.	614.52
20+07.35	West St.	Rt.	582.97
21+06.62	West St.	Rt.	642.03
21+11.78	West St.	Lt.	655.97
21+90.00	West St.	Lt.	487.14
24+26.18	West St.	Lt.	456.78
24+91.94	West St.	Rt.	523.90
25+99.53	West St.	Lt.	319.11
26+51.74	West St.	Rt.	612.27
26+60.21	West St.	Lt.	327.53
28+39.93	West St.	Rt.	612.14
28+73.80	West St.	Lt.	731.78
29+60.73	West St.	Rt.	613.74
29+89.98	West St.	Lt.	919.42
31+06.31	West St.	Rt.	633.14
31+23.10	West St.	Lt.	613.26
32+19.86	West St.	Rt.	731.82
32+54.24	West St.	Lt.	612.96
33+20.08	West St.	Rt.	734.04
33+63.28	West St.	Lt.	441.66
38+87.95	West St.	Rt.	237.99
38+90.70	West St.	Lt.	369.66
40+46.39	West St.	Rt.	732.89
41+27.88	West St.	Lt.	479.73
41+52.46	West St.	Rt.	724.55
41+58.85	West St.	Lt.	255.15
42+16.64	West St.	Rt.	726.58
43+16.47	West St.	Rt.	892.05
43+64.92	West St.	Lt.	292.46
44+29.46	West St.	Rt.	740.80
45+67.46	West St.	Rt.	388.48
46+11.56	West St.	Lt.	739.73
47+07.91	West St.	Rt.	328.02
48+00.87	West St.	Lt.	614.75
48+34.04	West St.	Rt.	634.51
48+98.92	West St.	Rt.	638.46
50+50.92	West St.	Lt.	725.51
51+84.40	West St.	Lt.	611.40
52+68.41	West St.	Rt.	691.49
53+07.94	West St.	Lt.	759.47
53+28.84	West St.	Rt.	631.72
54+12.86	West St.	Lt.	1054.26
54+66.09	West St.	Rt.	628.81
55+47.58	West St.	Rt.	629.09
56+20.18	West St.	Lt.	1104.24

REINF CONC DRIVE PAVEMENT (8")

(INCL WWF) (Continued)

STATION	ROADWAY	SIDE	AREA (Sq. Ft.)
56+49.40	West St.	Rt.	497.41
57+18.39	West St.	Rt.	690.06
57+70.62	West St.	Rt.	564.97
58+16.21	West St.	Lt.	1006.80
58+90.54	West St.	Rt.	583.34
59+91.17	West St.	Lt.	889.92
60+53.20	West St.	Rt.	1049.26
60+86.01	West St.	Lt.	1073.62
61+39.53	West St.	Rt.	933.13
64+06.90	West St.	Lt.	483.14
64+38.83	West St.	Lt.	397.03
65+01.19	West St.	Lt.	409.39
65+49.85	West St.	Lt.	1090.48
11+85.58	Maple	Rt.	572.12
13+70.10	Maple	Rt.	94.86
21+31.14	Douglas	Lt.	542.68
21+78.84	Douglas	Lt.	520.89
22+40.25	Douglas	Rt.	484.44
54+74.02	Central Ave.	Lt.	771.41
55+38.33	Central Ave.	Lt.	509.10
55+72.21	Central Ave.	Rt.	608.47
56+41.49	Central Ave.	Lt.	514.79
57+38.42	Central Ave.	Lt.	475.02
57+92.79	Central Ave.	Rt.	1065.43
58+15.46	Central Ave.	Lt.	678.20
58+62.38	Central Ave.	Lt.	799.45
62+12.02	Central Ave.	Lt.	1009.86
62+65.10	Central Ave.	Lt.	507.35
62+66.12	Central Ave.	Rt.	1020.98
TOTAL			58073.17

ASPHALT PARKING LOT PAVEMENT (6")

STATION	ROADWAY	SIDE	AREA (Sq. Ft.)
11+89.73	West St.	Lt.	141.24
19+55.29	West St.	Rt.	143.82
19+98.66	West St.	Lt.	144.74
20+07.35	West St.	Rt.	144.04
21+11.78	West St.	Lt.	675.41
21+90.00	West St.	Lt.	585.00
26+60.21	West St.	Lt.	49.42
28+39.93	West St.	Rt.	333.22
29+60.73	West St.	Rt.	251.20
31+06.31	West St.	Rt.	248.48
31+23.10	West St.	Lt.	657.86
32+54.24	West St.	Lt.	219.31
38+90.70	West St.	Lt.	73.27
42+16.64	West St.	Rt.	192.93
43+16.47	West St.	Rt.	216.56
43+64.92	West St.	Lt.	585.35
48+98.92	West St.	Rt.	137.78
50+50.92	West St.	Lt.	174.87
51+84.40	West St.	Lt.	306.19
52+68.41	West St.	Rt.	356.46
53+07.94	West St.	Lt.	523.43
53+28.84	West St.	Rt.	601.48
54+12.86	West St.	Lt.	175.31
54+66.09	West St.	Rt.	348.06
55+47.58	West St.	Rt.	125.48
54+74.02	Central Ave.	Lt.	193.22
55+38.33	Central Ave.	Lt.	133.07
55+72.21	Central Ave.	Rt.	181.68
62+65.10	Central Ave.	Lt.	146.46
TOTAL			8065.34

CURB & GUTTER (Combined) (Type I) (6")

STA. TO STA. (BASELINE)	ROADWAY	SIDE	LENGTH (ft.)	REMARKS	
8+75.71	9+04.58	West St.	Lt.	28.88	South of Maple
8+75.71	9+05.46	West St.	Rt.	29.76	South of Maple
10+93.15	22+56.77	West St.	Lt.	1165.82	Maple-Douglas
10+84.50	22+38.46	West St.	Rt.	1154.12	Maple-Douglas
23+92.10	33+80.61	West St.	Lt.	988.55	Douglas-S. of 2nd
24+05.98	42+55.84	West St.	Rt.	974.67	Douglas-S. of 2nd
38+90.70	39+55.34	West St.	Lt.	365.14	N. of 2nd-3rd
38+90.70	49+66.47	West St.	Rt.	1075.77	N. of 2nd-St. Louis
43+39.98	49+15.21	West St.	Lt.	597.24	3rd-St. Louis
50+05.21	61+81.75	West St.	Lt.	1177.30	St. Louis-Central
50+56.47	61+81.24	West St.	Rt.	1125.23	St. Louis-Central
63+61.30	65+83.55	West St.	Lt.	306.86	North of Central
63+58.85	65+83.55	West St.	Rt.	296.40	North of Central
8+29.00	9+07.11	Maple	Lt.	78.11	West of West St.
7+78.00	9+04.46	Maple	Rt.	126.46	West of West St.
10+82.51	13+24.27	Maple	Rt.	241.76	East of West St.
18+59.77	19+17.71	Douglas	Lt.	57.94	West of West St.
18+59.77	19+24.96	Douglas	Rt.	65.19	West of West St.
20+84.95	23+03.92	Douglas	Lt.	218.86	East of West St.
20+82.57	23+03.92	Douglas	Rt.	221.72	East of West St.
53+77.74	59+04.02	Central	Lt.	504.86	West of West St.
54+00.00	59+05.58	Central	Rt.	527.87	West of West St.
60+82.68	63+89.45	Central	Lt.	306.86	East of West St.
60+94.93	63+90.80	Central	Rt.	296.40	East of West St.
SW Radius of Maple & Illinois			-	25.58	30' R.
SW Radius of Maple & West St.			-	78.83	50' R.
NW Radius of Maple & West St.			-	77.55	50' R.
NE Radius of Maple & West St.			-	79.35	50' R.
SE Radius of Maple & West St.			-	78.43	50' R.
SW Radius of Douglas & West St.			-	63.64	40' R.
NW Radius of Douglas & West St.			-	77.53	50' R.
NE Radius of Douglas & West St.			-	79.25	50' R.
SE Radius of Douglas & West St.			-	77.83	50' R.
SW Radius of Central & West St.			-	78.36	50' R.
NW Radius of Central & West St.			-	79.26	50' R.
NE Radius of Central & West St.			-	77.90	50' R.
SE Radius of Central & West St.			-	78.63	50' R.
TOTAL			12883.91		

CURB & GUTTER (Combined) (Type III) (8")

STA. TO STA. (BASELINE)	ROADWAY	SIDE	LENGTH (ft.)	REMARKS	
8+75.70	9+15.70	West St.	Lt.	67.56	South of Maple
10+79.00	12+61.00	West St.	Rt.	341.88	North of Maple
21+60.00	22+55.00	West St.	Lt.	168.00	South of Douglas
23+87.00	24+81.00	West St.	Rt.	167.80	North of Douglas
61+44.00	61+94.00	West St.	Lt.	76.00	South of Central
63+43.00	63+93.50	West St.	Rt.	76.00	North of Central
8+57.00	9+17.00	Maple	Lt.	96.00	West of West St.
10+73.00	12+96.00	Maple	Rt.	422.12	East of West St.
18+80.00	19+45.00	Douglas	Lt.	109.78	West of West St.
20+66.00	21+60.00	Douglas	Rt.	165.84	East of West St.
58+68.00	59+18.00	Central	Lt.	76.00	West of West St.
60+82.00	61+32.00	Central	Rt.	76.00	East of West St.
TOTAL			1842.98		

A.C. COLD MILLING (2" Nominal) & A.C. Surface (2") (BM-2)

STA. TO STA. (BASELINE)	ROADWAY	SIDE	AREA (Sq. Yds.)	REMARKS	
8+55.70	8+75.70	West St.	-	152.16	South of Maple
10+97.12	12+98.90	Maple	Lt.	633.81	East of West St.
TOTAL			785.97		

CURB & GUTTER (Combined) (Std. City) (6 5/8")

STA. TO STA. (BASELINE)	ROADWAY	SIDE	LENGTH (ft.)	REMARKS	
10+85.12	10+97.12	Maple	Lt.	12.00	East of West St.
0+60.0	0+75.0	St. Louis	Rt.	15.00	St. Louis East of West St.
0+60.0	0+75.0	St. Louis	Lt.	15.00	St. Louis East of West St.
TOTAL			42.00		

Conc. Protection Curb (6")

STA. TO STA. (BASELINE)	ROADWAY	SIDE	LENGTH (ft.)	REMARKS	
12+19.5	12+50.0	West St.	Lt.	30.5	
13+72.0	13+90.3	West St.	Lt.	18.3	
14+90.0	16+34.0	West St.	Rt.	144.0	
21+52.0	22+51.9	Douglas	Lt.	75.0	
TOTAL			267.8		

PAVING BRICKS (Medians) (Includes Sand Base)

STA. TO STA. (BASELINE)	ROADWAY	AREA (Sq. Yds.)	THICKNESS (in.)	REMARKS	
7+79.45	9+09.49	West St.	59.70	3/8"	South of Maple
10+85.23	12+56.17	West St.	75.97	3/8"	North of Maple
21+65.00	22+49.00	West St.	37.33	3/8"	South of Douglas
23+92.10	24+76.12	West St.	37.29	3/8"	North of Douglas
61+49.50	61+87.48	West St.	16.89	3/8"	South of Central
61+49.25	63+87.27	West St.	16.89	3/8"	North of Central
8+63.37	9+11.37	Maple	26.42	3/8"	West of West St.
10+78.87	12+89.92	Maple	76.94	3/8"	East of West St.
18+85.11	19+40.00	Douglas	24.40	3/8"	West of West St.
20+72.00	21+54.92	Douglas	36.85	3/8"	East of West St.
58+74.00	59+12.00	Central	16.89	3/8"	West of West St.
60+88.00	61+26.00	Central	16.89	3/8"	East of West St.
TOTAL			442.46	3/8"	

PAVING BRICKS (Cross Walks) (Includes Sand Base)

STA. TO STA. (BASELINE)	ROADWAY	AREA (Sq. Yds.)	THICKNESS (in.)	REMARKS	
9+20.50	9+30.50	West St.	91.47	3/8"	Maple/West St.
10+64.23	10+74.23	West St.	92.05	3/8"	Maple/West St.
22+57.40	22+67.40	West St.	75.77	3/8"	Douglas/West St.
23+93.98	23+83.98	West St.	74.18	3/8"	Douglas/West St.
61+98.46	62+08.46	West St.	106.05	3/8"	Central/West St.
63+28.43	63+38.43	West St.	99.30	3/8"	Central/West St.
9+22.04	9+32.04	Maple	105.85	3/8"	West St./Maple
10+07.89	10+17.84	Maple	92.12	3/8"	West St./Maple
19+47.48	19+57.48	Douglas	72.99	3/8"	West St./Douglas
20+53.59	20+63.59	Douglas	85.18	3/8"	West St./Douglas
59+22.80	59+32.80	Central	94.96	3/8"	West St./Central
60+67.13	60+77.13	Central	89.92	3/8"	West St./Central
Total			1079.84		

CITY PROJECT ONLY