

CITY OF WICHITA PROJECT 472-84761/448-89975		
Lump Sum Bid Items - Paving (706995)		
Mobilization	1	LS
Site Clearing and Preparation	1	LS
Site Restoration	1	LS
Removal of Existing Structures	1	LS
Concrete Pavement Removal (Includes Curb & Gutter)	42,380	sy
A.C. Pavement Removal	3,586	sy
Parking Lot, Sidewalk, & Driveway Removal (Conc. & Asphalt)	13,125	sy
Excavation	23,867	cy
Compacted Fill (90% Std. Density)	716	cy
Concrete Pavement (9") (NRDJ)	38,913	sy
Reinforced Concrete Pavement (9") (Intersection)	7,797	sy
A.C. Cold Milling (2" Nominal)	786	sy
2" A.C. Surface Pavement (BM-2)(PG 70-28)	786	sy
7" A.C. Pavement (5" Bit. Base) (BM-2) (PG 70-28)	1,710	sy
Reinforced Crushed Stone Base (6") (Includes Geogrid Reinf.)	52,365	sy
Reinforced Crushed Stone Base (7") (Includes Geogrid Reinf.)	702	sy
Reinforced Crushed Stone Base (8") (Includes Geogrid Reinf.)	1,780	sy
Curb & Gutter (Combined) (Type I) (6") & (1 1/2")	12,884	lf
Curb & Gutter (Combined) (Type III) (8")	1,843	lf
Curb & Gutter (Combined) (Std. City) (6 5/8")	42	lf
Monolithic Edge Curb (6")	300	lf
6.0' Solid Conc Median Ramp-type Nose Section	24	ea
Wheelchair Ramps (5')	33	ea
Paving Bricks (3 1/8") (Cross Walks) (Includes Sand Base)	1,080	sy
Paving Bricks (2 3/8") (Medians) (Includes Sand Base)	442	sy
Reinforced Concrete Valley Gutter Pavement (8")	518	sy
Reinforced Concrete Pavement (8") (Intersection)	157	sy
Reinforced Concrete Alley Pavement (8")	35	sy
Type 1A Inlet Hookups (Existing)	4	ea
Sodding	5,037	sy
Lump Sum Bid Items - Drainage (706995)		
Inlet (Curb) (Type 1A) (6'-4" X 4'-4")	7	ea
Inlet (Curb) (Type 1A) (11'-4" X 4'-4")	14	a
Inlet (Curb) (Type 1A) (11'-4" X 5'-4")	6	ea
Inlet (Curb) (Type 1A) (11'-4" X 6'-4")	2	ea
Inlet (Curb) (Type 1A) (11'-4" X 7'-4")	1	ea
Inlet (Special) (Type 2) (6'-3" X 8'-9")	1	ea
Inlet Hookups	30	ea
Reinf. Conc. Manhole (4' Dia.)	1	ea
Reinf. Conc. Manhole (5'-4" X 5'-4")	1	ea
Special Shallow Manhole (5' Dia.)	1	ea
Access Manhole w/Ring and Lid	7	ea
Storm Sewer (12") (DICL)	980	lf
Storm Sewer (15") (RCP)	481	lf
Storm Sewer (18") (RCP)	396	lf
Storm Sewer (23" X 14") (HERCP)	175	lf
Storm Sewer (24") (RCP)	815	lf
Storm Sewer (30") (RCP)	935	lf
Storm Sewer (36") (RCP)	518	lf
Storm Sewer (42") (RCP)	237	lf
Storm Sewer (48") (RCP)	261	lf
8x5' RCB	882	lf
Removal of Exist. 8x4' RCB	30	lf
Curb Openings (Includes PVC Pipe & Fittings)	3	ea
Adjustment of Storm Sewer Inlets	4	ea
Adjustment of Storm Sewer Manholes	6	ea
Storm Sewer Pipe Abandoned	2,400	lf
Ditch Grading	103	lf

Lump Sum Bid Items - Traffic (706995)		
Project Signage	1	LS
Pavement Marking	1	LS
Temporary Traffic Signalization (3 Locations)	3	ea
Traffic Signalization at West Street & Maple	1	LS
Traffic Signalization at West Street & Douglas	1	LS
Traffic Signalization at West Street & Central	1	LS
Traffic Control (Construction)	1	LS
Lump Sum Bid Items - Non Standard (706995)		
Transportation of Salvage Materials	1	LS
Adjustment of Water Valves	1	LS
Adjustment of AT&T Manholes	25	ea
Bus Stop (Reset Ex. Bench)	3	ea
Measured Quantity Bid Items - Paving (706995)		
Sidewalk Concrete (4")	30,455	sf
Sidewalk Concrete (6") (Reinforced)	18,824	sf
Reinf Conc Drive Pavement (8") (Incl WWF)	58,073	sf
Concrete Parking Lot Pavement (8")	4,131	sf
A.C. Drive Pavement (7") (BM-2) (PG 70-28)	1,610	sf
Asphalt Parking Lot Pavement (6")	8,065	sf
Concrete Protection Curb (6")	268	lf
Abandoned Gas Pipeline Removal	1,000	lf
Concrete Flume	33	lf
Small Tree Removal (<15")	15	ea
Large Tree Removal (>15")	4	ea
Temp Pavement (6")	5,475	sy
Erosion Control (Back of Curb Protection)	13,184	lf
Erosion Control (Inlet Protection)	34	ea
Portable Changeable Electronic Message Sign	200	day
Lump Sum Bid Items (706995) - Sanitary Sewer		
Standard Type P Manholes (4')	3	ea
8" PVC SS Pipe	93	lf
Abandon Ex. SS Manhole	1	ea
Measured Quantity Bid Items (636133) - Waterline		
WL Pipe 02"	207	lf
WL Pipe 08"	895	lf
WL Pipe 12"	6,033	lf
WL Pipe 24"	16	lf
DICL SJ Pipe 04"	3	lf
DICL SJ Pipe 06"	3	lf
DICL SJ Pipe 08"	67	lf
DICL SJ Pipe 12"	123	lf
DICL SJ Pipe 24"	30	lf
Anchor Valve Assembly 04" (Gate Valve)	1	ea
Anchor Valve Assembly 06" (Gate Valve)	1	ea
Anchor Valve Assembly 08" (Gate Valve)	8	ea
Valve Assembly 12" (Butterfly Valve)	7	ea
Anchor Valve Assembly 12" (Butterfly Valve)	4	ea
Service Outlet Assembly 02"	2	ea
Custom Set and Service 02"	2	ea
Fire Hydrant Assembly	9	ea
Fire Hydrant Removal	11	ea
Blowoff Assembly 02"	6	ea
Adjustment of Water Vault Manhole (With New Ring & Cover)	1	ea
Relocate & Re-install Water Service (Short)	42	ea
Relocate & Re-install Water Service (Long)	34	ea
Temp Pavement (6")	1,870	sy

CITY OF WICHITA MANHOLE ADJUSTMENTS					
STREET	STA.	OFFSET	TYPE	EX. ELEV.	PROP. ELEV.
West St.	58+61	0.0'	SWS	120.46	121.20
West St.	60+00	0.0'	SWS	120.77	121.83
West St.	63+08	19' Lt.	SWS	121.29	122.55
West St.	63+65	20' Lt.	SWS	120.83	122.09
Maple	8+93	42' Lt.	SS	116.34	116.28
Douglas Ave.	20+95	23' Lt.	WTR	117.42	117.59
Douglas Ave.	21+25	29' Rt.	SS	118.06	117.25
Second St.	28+12	21' Lt.	SS	118.93	118.83
Second St.	31+69	21' Lt.	SS	119.51	119.45
Central	62+73	53' Rt.	SWS	120.64	120.71
Central	62+78	6' Lt.	SWS	120.54	121.01

AT&T MANHOLE ADJUSTMENTS				
STREET	STA.	OFFSET	EX. ELEV.	PROP. ELEV.
West St.	9+85	13' Rt.	116.96	117.18
West St.	14+70	13' Rt.	117.83	118.56
West St.	14+70	19' Rt.	117.69	118.41
West St.	16+46	16' Rt.	118.21	119.05
West St.	23+08	16' Rt.	117.45	118.40
West St.	23+12	6' Rt.	117.48	118.47
West St.	23+15	13' Rt.	117.47	118.46
West St.	29+60	10' Rt.	117.41	116.87
West St.	29+79	8' Rt.	117.36	116.76
West St.	36+18	10' Rt.	118.41	119.32
West St.	36+24	6' Rt.	118.50	119.40
West St.	36+59	12' Rt.	118.48	119.41
West St.	36+64	12' Rt.	118.40	119.38
West St.	42+47	7' Rt.	119.08	119.13
West St.	42+47	15' Rt.	118.94	118.88
West St.	42+55	7' Rt.	119.09	119.09
West St.	42+55	15' Rt.	118.93	118.84
West St.	42+63	7' Rt.	119.06	119.05
West St.	42+63	15' Rt.	118.93	118.80
West St.	49+37	10' Rt.	119.76	119.59
West St.	49+37	15' Rt.	119.59	119.45
West St.	49+46	10' Rt.	119.73	119.55
West St.	49+46	15' Rt.	119.53	119.40
West St.	56+10	11' Rt.	119.64	119.53
West St.	62+70	5' Rt.	121.42	122.56
West St.	62+70	15' Rt.	121.35	122.50
West St.	62+78	10' Rt.	121.33	122.56
Maple St.	10+71	13' Rt.	116.82	116.90

SWS INLET ADJUSTMENTS				
STREET	STA.	OFFSET	EX. ELEV.	PROP. ELEV.
West St.	28+00	33' Lt.	117.28	116.66
West St.	28+00	36' Rt.	117.30	116.66
West St.	29+17	33' Lt.	117.39	116.35
West St.	29+17	36' Rt.	117.43	116.35
Maple St.	7+96	45' Rt.	116.45	116.10
Maple St.	8+45	48' Lt.	117.05	117.05
Maple St.	8+54	48' Lt.	117.01	117.05
Central	53+86	44' Rt.	120.60	120.45

CITY PROJECT ONLY