

# GENERAL NOTES

FHWA REGION NO.	STATE	PROJECT NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
7	KANSAS	87N-0459-01	2008	3	32

Fed. Aid # HSIP-N045(901)

- Utility service lines, poles, valve boxes, gas meters, and etcetera are to be adjusted as necessary by others prior to construction unless the plans specifically call for their adjustment by the Contractor or unless the plans specifically identify a utility to be adjusted by its owner during construction. Existing utilities and their location, as shown on the plans, represent the best information obtainable for design. The Contractor will be required to work around existing utilities within the right-of-way which do not conflict with proposed construction.
- The Contractor shall give all property owners and/or tenants of developed property abutting the project limits a minimum of ten (10) days advance notice prior to start of construction.
- The Contractor shall notify pipeline companies at least forty-eight (48) hours in advance of any work being performed across from and/or adjacent to any pipelines.
- A full depth saw cut of the existing surface courses of the existing total pavement thickness shall be provided at the locations where proposed construction abuts an existing surface course or pavement for which partial removal of that surface or pavement is required. Sawed joint to facilitate removal within three (3) feet of existing joints will not be permitted and for such instances the limits of removal shall extend to the existing joint. Such saw cuts will not be paid for directly and this cost shall be considered SUBSIDIARY to the specific Pavement Removal bid item.
- All project waste including any trees, milled asphalt, rubble from miscellaneous structures, abandoned pipes, excess excavation & etc. shall be disposed of on sites to be provided by the Contractor. These sites shall be approved by the Engineer as to suitability, appearance and site location. Locations that, in the opinion of the Engineer, will leave an unsightly appearance will not be approved. All disposal sites must be approved by the Kansas Department of Health and Environment. Material either stockpiled or disposed of in a flood plain would require a Kansas State Board of Agriculture permit. Any material dumped in waters of the United States or wetlands is subject to U.S. Corps. of Engineers permitting regulations. Any material buried or stockpiled beyond approved construction limits would require additional archaeological investigations unless buried in a previously approved borrow location.
- Prior to bidding the project, each bidder shall visit the site and satisfy himself of surface & subsurface conditions. Each bidder shall also fully inform himself as to the extent of the scope of work to be performed.
- Contractor shall be aware that some gas & telephone lines within the project corridor may have been abandoned in place as new lines are installed. The Contractor shall be responsible for contacting the appropriate owners to determine the status of said lines.
- The Water Department shall field locate water valves one time during construction when requested by the Contractor. It shall be the Contractor's responsibility to preserve such field locations during the construction process. Water valves, water valve boxes or fire hydrant damaged during construction shall be repaired by the Contractor at his own expense.
- Excavations for Storm Water Sewer systems beneath pavement shall be sand filled and flushed for a minimum distance of two (2) feet behind curb lines, to a level of one (1) foot below the subgrade. The upper one foot of fill shall be approved backfill material, compacted to a minimum of 95% Standard Density. Approved Additional material and Sand Flush and Fill operations will not be paid for directly, but shall be considered SUBSIDIARY to the installation of the pipe
- The Lump Sum Bid Item "Site Restoration" shall INCLUDE all costs for relocating or reconstructing traffic signs, temporary pole bracing, final grading of the work area, and other such items requiring replacement for which a pay item is not provided for in the Proposal.
- Contractor shall be responsible for preserving all property irons. The Contractor will be required to re-establish any property irons which are damaged or destroyed by his construction operations. Such irons shall be re-established by a licensed land surveyor in accordance with state laws.
- The Reinforced Concrete Box Culvert (RCBC) & manholes shall be pre-cast, unless otherwise noted. The RCBC shall conform to ASTM C-850 Standards for loading unless otherwise noted in the plans. Contractor shall provide the Engineer with shop drawings of the structures for approval prior to construction. All Pre-cast RCB Sections shall have filter fabric wrapped at each joint to prevent infiltration of fines and other material into the conduit.
- Removal of all fences, trees, shrubs, stumps, drain pipes (<12"), pavement markings, and any other items slated for removal for which a pay item is not provided shall be INCLUDED in the lump sum bid item "R/W Clearing and Site Preparation."
- In locations where existing mail boxes conflict with construction, the Contractor shall remove and salvage the existing mail box for reinstallation. Only approved, non-hazardous supports shall be used for the re-installation. Hazardous mail box supports shall not be re-installed but may be returned to Owner. All costs associated with mail box removal & re-installation shall be SUBSIDIARY to the bid item "R/W Clearing & Site Restoration".
- Trees and Shrubs in public right-of-way which are in direct conflict with proposed new construction shall be removed and disposed of by the Contractor with the Engineer's approval. Trees and shrubs which are not in direct conflict with proposed new construction shall be saved and protected from damage.
- Fences with in the public right-of-way which are in direct conflict with proposed new construction shall be removed and stockpiled on the land owners property by the Contractor with the Engineer's approval. Cost to be INCIDENTAL to "R/W Clearing & Site Preparation.
- All lawn/turf areas disturbed by the construction shall be restored with the same grass/sod as existing. Restoration of disturbed areas shall include, but not limited to, top soil preparation and sodding. All sodding work shall be in accordance with City Standard specifications and the City Administrative Regulations No. AR6.5, which governs cleanup and restoration or replacement following construction. When the weather/season prevents the installation of the sod the Contractor shall be responsible for installing Erosion Control Blanket (Curlax), or approved equivalent, at the back of curb (8' wide minimum). All costs for this work shall paid for as "sodding".
- Construction of temporary drives required for residential access during construction shall be SUBSIDIARY to the bid item "Construction Traffic Control" and shall include all grading, fill, compaction, removal, disposal, and etc. necessary for residential access.
- New Sidewalk shall have a maximum side slope of not more than one-quarter inch (1/4") per foot and a maximum longitudinal slope of five (5) percent unless otherwise approved by the Engineer. The sidewalk location shown on the plan is tentative. The Contractor shall be aware that the final sidewalk alignment may be subject to field changes based on the new location of power poles, utility pedestals, and trees. However, the Contractor shall make every effort to adhere to the sidewalk plan with respect to slope and drainage conditions.
- The Contractor shall not start work on the Project until the Project Inspector is assigned and is present on site. Any work done without inspection will be required to be uncovered for inspection.
- Areas over-excavated in surface or pavement removal shall be filled to sub grade elevation and compacted to 95% Std. Density. Cost shall be INCIDENTAL to the Project.
- Geogrid Reinforcement for the rock base shall be Tensar BX1100 as manufactured by the Tensar Corporation, or approved equal. Geogrid fabric shall be INCIDENTAL to the bid item "Reinf. Crushed Rock Base."
- Valve Boxes and Water Meters within the Project Limits shall be adjusted to match Final Grade. Cost to be SUBSIDIARY to the bid item "Adjustment of Water Valves".

## LIST OF UTILITY COMPANIES

Contractor shall be required to provide notice to Kansas One Call at 687-2470 a minimum of two (2) working days prior to any excavation or work adjacent to utilities.

TYPE	OWNER	CONTACT	TELEPHONE	(ALT)
Locator Service	Kansas One-Call		687-2470	800-344-7233
TV	Cox Communications (Cable)	Eva Moore	262-4270	
Electric	Westar Energy (K.G.E.)	Ken McLemore	261-6824	
Gas	Black Hills	Daryl L Keller	941-1608	
Gas	Kansas Gas Service	Jim Coe	831-3165	
Telephone	AT&T Telephone	Jim Fagan	268-2759	800-286-8313
Water	Wichita Water Department	Greg Lally	268-4563	268-4908
Storm Water Sewer	Wichita SWS Maintenance	Doug Arvidson	268-4095	
Sanitary Sewer	Wichita Sewer Maintenance	Calvin Fugit	268-4024	262-6000
Electric	Rural Electric Coop			

Drawing File: F:\eng\West street paving new\Details\KDOT West and 2nd\SH-03 2nd street Notepage.dwg

Design: AZIERE  
Drawn: STAFF  
Approved: JFB  
Scale: None

Project No. 0404EB59 CAPITAL IMPROVEMENT PROJECT

### GENERAL NOTE PAGE

WEST STREET PAVING - 2nd & West St.

**Baughman**  
ENGINEERING | SURVEYING | PLANNING | LANDSCAPE ARCHITECTURE

**Baughman Company, P.A.**  
315 Ellis St. Wichita, KS 67211 P 316-262-7271 F 316-262-0149

November 2008

SHEET  
3  
OF  
32