

STATION	AREAS		VOLUMES		CUMULATIVE VOLUMES	
	Square Feet		Cubic Yards		Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
0+26.43	28.55	0.00	14.02	0.00	14.02	0.00
0+42.80	17.71	0.00	5.01	0.00	19.03	0.00
0+50	19.85	0.00	40.29	0.00	59.32	0.00
1+00	23.66	0.00	42.31	0.00	101.63	0.00
1+50	22.17	0.00	36.25	0.00	137.88	0.00
2+00	17.07	0.00	15.63	0.00	153.51	0.00
2+24	18.16	0.00	18.40	0.00	171.91	0.00
2+50	20.12	0.00	37.65	0.21	209.56	0.22
3+00	20.63	0.23	33.72	0.52	243.28	0.73
3+50	15.92	0.33	29.04	0.54	272.32	1.27
4+00	15.54	0.25	30.24	0.46	302.56	1.73
4+50	17.22	0.25	30.43	0.33	332.99	2.06
5+00	15.72	0.10	25.96	0.37	358.95	2.43
5+50	12.39	0.29	28.15	0.81	387.10	3.23
6+00	18.19	0.57	29.38	1.41	416.48	4.64
6+50	13.71	0.93	24.76	1.75	441.24	6.39
7+00	13.10	0.93	25.22	1.06	466.47	7.45
7+50	14.17	0.21	26.46	0.39	492.93	7.84
8+00	14.45	0.21	27.18	0.46	520.11	8.30
8+50	15.02	0.27	25.66	0.45	545.77	8.75
9+00	12.78	0.20	24.25	0.40	570.03	9.15
9+50	13.47	0.23	23.28	0.45	593.31	9.60
10+00	11.73	0.25	23.11	0.35	616.41	9.95
10+50	13.30	0.12	23.88	0.37	640.29	10.32
11+00	12.43	0.29	30.30	0.32	670.59	10.64
11+59.56	14.94	0.00	12.94	0.13	683.52	10.77
11+78.69	21.64	0.34	14.83	0.66	698.35	11.42
11+95.69	26.04	1.62	16.58	0.57	714.94	11.99
12+12.69	26.63	0.19	5.58	0.04	720.52	12.03
12+24	0.00	0.00	0.00	0.00	720.52	12.03

Note: Earthwork Quantities listed reflect the existing ground at the time of the survey. Quantities have been calculated using the average End area method. No factors for soil expansion, loss, or compaction have been figured into these Quantities.