

CONCRETE PAVEMENT					
STATION/LOCATION	SIDE	8" (AE) (NRDJ) (SQ.YD.)	9" (AE) (NRDJ) (SQ.YD.)	10" (Unif.) (AE) (SQ.YD.)	REMARKS
CENTRAL:					
14+71.71 to 14+84.81	℄			88.81	East Approach Slab
15+18.34 to 15+31.45	℄			88.81	West Approach Slab
30+34.80 to 32+20.32	Lt.	80.88			Pavement Widening
30+34.80 to 34+25.49	Rt.	152.48			Pavement Widening
35+66.17 to 37+86.54	℄		2228.82		Edgemoor Intersection
41+91.51 to 44+08.38	Lt.	72.38			Pavement Widening
TOTAL		305.74	2228.82	177.62	

REINFORCED CONCRETE VALLEY GUTTER				
STATION	SIDE	RCVG PAVEMENT (8") (SQ.YD.)	ASPHALT # HOOK-UP (SQ.YD.)	REMARKS
SIDEROADS:				
13+36.79	Rt.	168.17		Bleckley Dr.
16+63.36	Rt.	184.97	29.95	Harding St.
19+94.44	Rt.	190.10	31.11	Battin (South)
19+95.12	Lt.	166.44		Battin (North)
23+26.70	Rt.	167.18		Pinecrest
26+57.29	Lt.	207.75	44.00	Old Manor
29+89.85	Rt.	166.66		Parkwood
42+53.93	Lt.	290.09	57.42	Carriage Parkway
46+74.70	Rt.	179.48		Brookside
48+15.76	Rt.	168.32	31.14	Brookside
60+04.62	Rt.	168.42		Hillcrest
TOTAL		2,057.58	193.62	

# Payment for "Asphalt Hook-up" will include 7" Asphalt Pavement on 8" Rock Base.

A. C. PAVEMENT				
LOCATION	SURFACE PG (70-28) (SQ.YD.)	BIT. BASE (PG 70-28) (5") (SQ.YD.)	BIT. BASE (PG 70-28) (1 1/2") (SQ.YD.)	REMARKS
CENTRAL:				
10+83.86 to 14+71.71	2,413.29	2,413.29		
15+31.45 to 30+34.80	9,354.22	9,354.22		
30+34.80 to 35+66.17	3,258.41		3,025.05	
37+86.54 to 44+08.38	4,561.30		4,488.92	
44+08.38 to 62+21.59	13,678.10	13,678.10		
TOTAL	33,265.32	25,445.61	7,513.97	

CURB AND GUTTER, COMBINED			
STATION TO STATION	SIDE	QUANTITY (L.F.)	REMARKS
CENTRAL:			
10+83.86 to 32+35.48	Lt.	1939.23	Excluding 2 Valley Gutter
10+83.86 to 34+25.49	Rt.	1859.99	Excluding 5 Valley Gutter
35+42.57 to 36+31.33	Lt.	118.80	
35+66.17 to 36+31.21	Rt.	83.55	
36+86.25 to 37+86.54	Rt.	118.89	
36+97.26 to 37+86.54	Lt.	131.16	
43+17.31 to 62+21.59	Lt.	1904.38	
44+04.48 to 62+21.59	Rt.	1549.60	Excluding 3 Valley Gutter
SUBTOTAL		7,705.6	
EDGE MOOR:			
10+74.28 to 11+29.81	Lt.	55.54	
10+85.29 to 11+29.81	Rt.	24.67	
SUBTOTAL		80.21	
TOTAL		7,866.02	

EARTHWORK							
STATION TO STATION	EXCAVATION		COMPACTION			REMARKS	
	PAVEMENT REMOVAL (SQ.YD.)	SIDEWALK REMOVAL (SQ.FT.)	COMMON (CU. YD.)	95% COMPACTION (CU. YD.)	90% COMPACTION (CU. YD.)		LOOSE FILL (CU. YD.)
10+83.86 to 14+84.81	2,669.09					Includes Alley, Curb, Valley Gutter Removal	
10+85.10 to 31+78.88		7,960.98				Includes Parking lot Removal. See Note	
12+91.72 to 34+33.23		3,721.63				Includes Parking lot Removal. See Note	
15+18.34 to 34+32.94	8,962.78					Includes Alley, Curb, Valley Gutter Removal	
35+47.64 to 37+73.28		1,004.72				Includes Parking lot Removal. See Note	
35+66.17 to 37+86.54	2,710.47					Includes Alley, Curb, Valley Gutter Removal	
35+98.68 to 37+12.30		307.08				Includes Parking lot Removal. See Note	
41+91.51 to 43+17.31	261.73					Includes Alley, Curb, Valley Gutter Removal	
41+91.51 to 62+19.54		6,700.48				Includes Parking lot Removal. See Note	
44+03.98 to 62+21.59	13,496.93					Includes Alley, Curb, Valley Gutter Removal	
44+04.48 to 62+21.59		7,045.14				Includes Parking lot Removal. See Note	
TOTAL	28,101	26,740.03	7,020	5,615	125		

DRIVEWAY PAVEMENT						DRIVEWAY ITEMS ON PRIVATE PROPERTY			
STATION	SIDE	CONC. PVMT (8") (REINF.) (SQ.FT.)	P (FT.)	L (FT.)	WIDTH (FT.)	CONC. PVMT (8") (SQ.FT.)	7" ASPHALT (SQ.FT.)	CURB & GUTTER COMBINED (AE) (L.F.)	REMARKS
CENTRAL:									
11+25.50	Lt.	288.00	6.00	10.00	30.00		*155.97		* See Note Below
11+53.30	Rt.	252.54	7.66	7.66	21.80				
11+98.40	Lt.	258.03	6.00	10.00	25.00	*135.99			* See Note Below
12+11.60	Rt.	271.44	7.38	7.38	26.00				
12+57.80	Lt.	258.03	6.00	10.00	25.00		*258.03		* See Note Below
13+80.30	Lt.	189.00	6.00	10.50	13.50		*101.25		* See Note Below
14+12.50	Lt.	198.00	6.00	10.50	15.00		*108.00		* See Note Below
14+57.80	Lt.	227.97	6.00	13.50	20.00		217.53		
14+72.30	Rt.	311.13	8.50	12.46	21.50		118.89		
15+77.80	Lt.	347.22	9.50	13.50	21.00		101.79		
17+08.10	Lt.	265.23	10.50	10.50	17.10				
49+46.45	Lt.	131.67	11.76	11.76	10.16				Harding St.
49+43.66	Rt.	59.31	4.50	4.50	10.08				Harding St.
18+34.70	Lt.	403.83	13.50	13.50	17.20				
49+48.60	Lt.	137.61	13.24	13.24	8.00				Battin (South)
49+48.50	Rt.	115.92	9.64	9.64	10.00				Battin (South)
21+21.70	Lt.	270.99	13.52	19.50	9.20	45.90			
21+80.00	Rt.	296.73	9.50	13.50	19.90	79.47			
21+91.40	Lt.	594.93	13.50	18.50	22.90				
22+92.00	Lt.	825.19	13.50	18.50	35.30				35.32 S.F. P. Lot Removal
49+40.25	Lt.	88.74	7.90	7.90	9.40			10.00	Pinecrest
23+77.40	Rt.	718.74	19.50	22.50	30.00		*90.45		* See Note Below
24+57.70	Rt.	819.18	19.50	19.50	30.00				
24+65.10	Lt.	841.00	13.50	18.50	36.10				36.19 S.F. P. Lot Removal
25+10.80	Rt.	659.88	18.50	18.50	24.00				
26+65.90	Rt.	669.51	18.50	18.50	25.00				
27+06.50	Rt.	674.73	18.50	19.50	23.60				
28+00.00	Lt.	538.97	13.50	18.50	20.00				
28+03.20	Rt.	298.71	8.50	14.50	29.30		*162.54		* See Note Below
28+47.70	Rt.	320.04	8.50	9.50	23.80				
29+04.30	Rt.	305.01	8.50	17.50	22.00		*205.02		* See Note Below
29+25.10	Lt.	539.17	13.50	18.50	20.00				
30+34.80	Lt.	616.18	13.50	18.50	23.90				
31+02.50	Rt.	664.38	16.34	16.34	29.50				25.68 S.F. P. Lot Removal
31+54.40	Rt.	517.59	14.53	14.53	25.80				
31+98.70	Lt.	846.85	19.81	24.81	24.00				
32+37.80	Rt.	492.84	12.50	20.00	25.20	*171.72			* See Note Below
33+32.60	Rt.	293.04	6.58	13.94	26.50	*261.00			* See Note Below
35+67.50	Lt.	818.82	25.50	25.80	30.10				
51+05.82	Lt.	349.20	10.50	10.50	30.00				Edgemoor (North)
44+34.40	Rt.	377.01	12.85	13.37	16.60				
44+49.20	Lt.	984.51	16.21	21.23	48.10		166.68	19.76	
45+02.20	Rt.	476.46	14.55	14.55	19.60				
46+03.10	Lt.	522.09	12.47	16.22	29.50		110.79		
46+85.42	Lt.	414.99	12.47	12.47	26.00				
48+65.10	Lt.	415.35	12.47	12.47	20.70				
50+29.40	Lt.	467.64	12.46	12.46	29.60				
50+57.40	Rt.	825.84	24.55	24.55	26.60				
51+14.70	Rt.	566.82	24.55	29.55	15.50	61.83			
51+79.60	Rt.	478.26	24.55	29.55	12.00	47.97			
52+18.60	Lt.	528.57	12.45	12.45	29.90				
52+40.40	Rt.	466.29	24.55	24.55	12.00				
53+04.20	Rt.	761.31	24.55	24.55	24.00				
53+64.50	Rt.	478.35	24.55	29.55	12.00	47.97			
54+28.50	Rt.	580.59	24.55	29.55	16.00	63.99			
54+70.60	Lt.	700.56	12.44	12.44	43.60				
54+84.70	Rt.	559.17	24.55	25.55	15.20	136.35			
55+54.60	Rt.	712.08	24.55	29.55	22.00	*124.83			* See Note Below
56+45.20	Rt.	739.71	24.55	29.55	24.00	*127.44			* See Note Below
56+76.10	Rt.	743.58	24.56	29.56	26.00	*137.50			* See Note Below
57+33.50	Rt.	600.93	24.56	29.56	17.00	*51.66			* See Note Below
57+34.50	Lt.	417.87	12.43	12.43	30.20				
58+23.30	Rt.	456.57	12.18	26.18	25.00	322.02			
59+08.30	Rt.	523.53	9.25	23.25	44.70	634.32			
60+03.90	Lt.	801.54	18.28	18.28	31.50				
49+20.20	Rt.	530.46	14.58	14.58	30.00			40.29	Hillcrest Ave.
61+09.30	Rt.	473.13	12.06	18.07	25.00		*132.03	12.30	* See Note Below
61+51.60	Lt.	957.42	28.42	28.42	24.40				
TOTAL		33,335.98				2,362.32	2,064.96	82.35	

\* Items designated as Parking lot removal will be bid as "Sidewalk Removal" and bid per square foot.

≠ Included in "Sidewalk Removal" quantity.

KANSAS DEPARTMENT OF TRANSPORTATION			
SUMMARY OF QUANTITIES			
PROJ. NO. 87 N-0135-01		SEDGWICK CO.	
MKEC ENGINEERING CONSULTANTS, INC. WICHITA, KANSAS			
DESIGNED BY: JRA	CHECKED BY: JRA		
DRAWN BY: JSB	DATE: DEC 05	SHEET 82 OF 137	