

Address	Addition	Lot #	Block #
3210 W 2nd St. N	Mount Carmel 2nd Addition	Lot 10	
3300 W 2nd St. N	Clark's Addition	Lot 7	
308 Sheridan	Mount Carmel 2nd Addition	Lot 11	
311 Sheridan	Leah Mea Addition	Lot 2	Block 1
314 Sheridan	Mount Carmel 2nd Addition	Lot 12	
315 Sheridan	Leah Mea Addition	Lot 1	Block 1
320 Sheridan	Mount Carmel 2nd Addition	Lot 13	
326 Sheridan	Mount Carmel 2nd Addition	Lot 14	
331 Sheridan	Clark's Addition	Lot 6	
332 Sheridan	Mount Carmel 2nd Addition	Lot 15	
335 Sheridan	Clark's Addition	Lot 5	
338 Sheridan	Mount Carmel 2nd Addition	Lot 16	
339 Sheridan	Clark's Addition	Lot 4	
344 Sheridan	Mount Carmel 2nd Addition	Lot 17	
347 Sheridan	Clark's Addition	Lot 3	
349 Sheridan	Clark's Addition	Lot 2	
350 Sheridan	Mount Carmel 2nd Addition	Lot 18	
362 Sheridan			
406 Sheridan (shop)	Wilson Gardens Addition	Lot 2	
406 Sheridan (house)	Wilson Gardens Addition	Lot 1	
409 Sheridan	Farrice Addition	Lot 2	
420 Sheridan	Farrice Addition	Lot 1	

DRIVEWAYS				
LABEL	STATION	OFFSET	WIDTH	AREA
A	11+37.77	15.01 Rt	10.76'	140.08 SY
B	11+94.93	14.99 Rt	10.95'	142.19 SY
C	12+49.42	14.97 Rt	10.95'	142.17 SY
D	13+04.62	14.95 Rt	10.97'	141.79 SY
E	13+58.08	14.93 Rt	10.92'	142.60 SY
F	14+13.63	14.91 Rt	10.96'	142.43 SY
G	14+66.53	14.89 Rt	10.90'	141.94 SY
H	15+19.41	14.87 Rt	10.73'	140.60 SY
I	16+13.36	14.84 Rt	10.01'	145.79 SY

Match Exist Widths on all Driveways

CRUSHED ROCK BASE		
LOCATION	6" CRUSHED ROCK BASE (SY)	REMARKS
TOTAL SITE	1316.18	

CONCRETE PAVEMENT		
LOCATION	REINFORCED CONCRETE (8") (SY)	REMARKS
TOTAL SITE	1053.31	

CURB AND GUTTER		
LOCATION	6" CURB 2.50' GUTTER (LF)	REMARKS
RIGHT SIDE	675.70	
LEFT SIDE	26.07	AROUND SOUTH INLET
LEFT SIDE	35.77	AROUND NORTH INLET
TOTAL	737.54	

EROSION CONTROL			
ITEM	QUANTITY	UNITS	REMARKS
Inlet Protection	6	EA	
Back of Curb Protection	805	LF	
Project Seeding	1	LS	

DRIVEWAYS			
STATION, OFFSET	QUANTITY	UNITS	REMARKS
11+37.77, 15.01 Rt	140.08	SY	
11+94.93, 14.99 Rt	142.19	SY	
12+49.42, 14.97 Rt	142.17	SY	
13+04.62, 14.95 Rt	141.79	SY	
13+58.08, 14.93 Rt	142.60	SY	
14+13.63, 14.91 Rt	142.43	SY	
14+66.53, 14.89 Rt	141.94	SY	
15+19.41, 14.87 Rt	140.60	SY	
16+13.36, 14.84 Rt	145.79	SY	
TOTAL SITE	1279.59	SY	

WATER LINE			
ITEM	QUANTITY	UNITS	REMARKS
WL PIPE 12"	220.87	LF	
BUTTERFLY VALVE 12"	1	EA	
FIRE HYDRANT ASSEMBLY	1	EA	
WM SERVICE SHORT	1	EA	
WM SERVICE LONG	7	EA	


STORM WATER SEWER			
ITEM	QUANTITY	UNITS	REMARKS
RCP 24"	91.53	LF	
RCP 60"	677.66	LF	
Renf. Conc. MH 8.5'x8.5'	4	EA	
TYPE 1A INLET 15'	6	EA	

RECAPITULATION OF ROAD QUANTITIES		
ITEM	QUANTITY	UNITS
Crushed Rock Base, 6"	1316.18	SY
Concrete Pavement 8"	1053.31	SY
Curb and Gutter	737.54	LF
Inlet Hook-ups	6	EA
Driveway Entrance	1279.59	SY
Sawed Joint	742.68	LF
Conc. Pavement Removal	1053.31	SY
Comb. Curb & Gutter Removed	737.54	LF
Conc. Sdwk, Drive, &/ or Parking Lot Removed	1279.59	SY
WL Pipe 12"	220.87	LF
DICL SJ Pipe 12"	7.25	LF
Butterfly Valve 12"	1	EA
Fire Hydrant Assembly	1	EA
Water Meter Service (short)	1	EA
Water Meter Service (long)	7	EA
12" Water Line Removal	243.03	LF
Fire Hydrant Removal	1	EA
24" RCP	91.53	LF
RCP 60"	677.66	LF
8.5'x8.5' Reinforced Concrete Manhole	4	EA
15' Type 1A Inlet	6	EA
Inlet Removal	4	EA
Manhole Removal	1	EA
Inlet Protection	6	EA
Back of Curb Protection	805	LF
Project Seeding	1	LS
Site Clearing & Restoration	1	LS

Water Meter Summary					
Service Number	BL Sta.	Lt./Rt.	Service (Long/Short)	Meter Size (inches)	Service Address
1	11+01.84	Lt	Long	0.63	3300 W 2nd St.
2	12+32.23	Lt	Long	0.63	311 Sheridan St.
3	13+16.39	Lt	Long	0.63	315 Sheridan St.
4	13+95.34	Lt	Long	0.63	335 Sheridan St.
5	15+03.98	Lt	Long	0.63	335 Sheridan St.
6	15+30.78	Rt	Short	0.63	362 Sheridan St.
7	16+03.18	Lt	Long	0.63	339 Sheridan St.
8	17+06.90	Lt	Long	0.63	347 Sheridan St.

General Notes:

- Quantities for Paving Items & Waterline Items will be paid by Measured Quantity.
- Saw cut existing concrete pavement along centerline joint.
 - If remaining concrete from saw cut to joint is less than 4' remove concrete to joint.
- Match all existing grades for new pavement along centerline.
- Match existing widths and edge of pavement elevations for all driveways.
- Replace all service meters effected by water line relocation.
- Drop off removed fire hydrant at City of Wichita Maintenance Facility located at 1801 South McLean.

Sheridan Street Drainage Quantities Wichita, Kansas			
PROJECT NUMBER			
 516 S. Market, Wichita, KS 67202	KEM NO. 07141	FILE quant	DATE 6/2008
	DESIGN KM	DRAWN NS	REVISED
		SHEET 17	OF 17
316/264-0242			