NOTE:
INDIVIDUAL TREES TO BE REMOVED OR TRIMMED WILL BE IDENTIFIED DURING THE PRE-BID SITE VISIT.

ENLARGEMENT 37 — 37 / LM-7.10

ENLARGEMENT 38 — 38 / LM-7.10

ENLARGEMENT 39 — 39 / LM-7.10

ENLARGEMENT 40 — 40 / LM-7.10

ENLARGEMENT 41 — 41 / LM-7.10

ENLARGEMENT 42 — 42 / LM-7.10

Tree Group	Enlargement	Removal	Trim	Notes
1	1	1	6	9"-15" dia trees
1	2		15	18"-24" trees
1	3		1	24" dia tree
1	4	3	20	12"-24" dia. trees
1	5	5		12" dia trees
1	6		13	12"-24" dia trees
2	7	1		18" dia stump
2	8	5		12"-18" dia. trees
2	9		2	12"-18" dia. trees
2	22	1	9	remove wet side stump, trim 12" dia trees
2	43		7	trim 12"-18" dia trees
3	21	1	2	remove wet side stump, trim 36" dia trees
3	23	20	1	9"-15" dia. trees
3	24	25		9"-24" dia trees
3	25	25		6"-18" dia. trees
3	26	22		6"-24" dia. trees
3	44	68		6" - 36" diam trees
4	10	4		36" trees
4	11	17		4-6" cedars, 13-12"to24" trees
4	12	14	4	remove 12"-24" on N, trim back 6"-12" trees on T
4	13	43		20-large trees, 23 small trees
4	14	33		23-large trees, 10 small trees
4	15	31		3 > 48", 6-30", 22-15" trees
5	16	6	6	12"-18" dia. trees (wood fence may need relocated)
5	17	43	5	13 - 15" trees, 30 - < 6" dia. trees (wire mesh fence may need relocated)
5	18	40		12"-24" trees
5	19	30	10	4"-12" dia. trees
5	20	75	30	4"-36" dia trees
5	27	6		6"-12" dia. trees (may need to relocate fence)
6	28	1		18" tree
6	29	15	5	12"-24" dia. trees
6	30	3		18"-24" dia. trees
6	45	5		18" dia trees
7	31	1		12"
7	32	13		9"-24"
7	33	5		remove small trees around floodwalls
7	34	4		remove small trees around floodwalls
7	35	1		24" tree
7	36	1		24" tree
8	37	2	15	12"-18" trees
8	38	1	5	remove stump trim trees
8	39	1		18"
8	40	1		12"-18" stump
8	41	1		6"-9"
8	42	1		6"-18"

N

0 2000' 4000'
SCALE: 1"=2000'

MARK	DESCRIPTION	DATE	APPR.

amec
AMEC Earth & Environmental, Inc.
1129 SW Wanamaker
Topeka, Kansas 66604
Phone: (785) 272-6830
Fax: (785) 272-6878

CITY OF WICHITA

LEVEE "L"
WICHITA-VALLEY CENTER LOCAL FLOOD PROTECTION PROJECT
WICHITA, KANSAS

PREPARED FOR
THE CITY OF WICHITA, KANSAS
455 N. Main
Wichita, KS 67202

LAWRENCE J. SAMPLE
LICENSED
15855
KANSAS
PROFESSIONAL ENGINEER
7/17/09

DESIGNED BY: Lawrence J. Sample, P.E.		DATE: 2009/JUL/17
DWN BY: Staff	CKD BY: MG	APP BY: DWD
FILE NAME: 561500000-LM-702.dgn		
AMEC PROJ. NO. 5-6150-0000		

TREE REMOVAL LOCATION PLAN
LM-7.02
SHEET 40 OF 48