

CRUSHED ROCK BASE		
LOCATION	5" CRUSHED ROCK BASE (SY)	REMARKS
46th Street South	620	
Elizabeth Street	2339	
TOTAL SITE	2959	

ROAD PAVEMENT		
LOCATION	5" AC PVMT with 3" BIT BASE (SY)	REMARKS
46th Street South	315	
Elizabeth Street	1914	
TOTAL SITE	2229	

REINFORCED CONCRETE VALLEY GUTTER		
LOCATION	5" RC PVMT with 2" BIT BASE (SY)	REMARKS
TOTAL SITE	137	

COMBINED CURB AND GUTTER		
LOCATION	FULL HEIGHT 6 1/2" TALL (LF)	REMARKS
46th Street South	261	
Elizabeth Street	0	
TOTAL SITE	261	

COMBINED CURB AND GUTTER		
LOCATION	ROLL TYPE 3 3/8" TALL (LF)	REMARKS
46th Street South	0	
Elizabeth Street	1242	
TOTAL SITE	1242	

MONOLITHIC EDGE CURB		
LOCATION	FULL HEIGHT 6 1/2" TALL (LF)	REMARKS
TOTAL	81	


STREET SIGNS		
LOCATION	AMOUNT (EA)	REMARKS
20+00.00, 19.50 Lt	1	W1-7
30+28.50, 20.50 Rt	1	SNS (S. Elizabeth Ave - 46th St S)

DRIVEWAYS				
STATION, OFFSET	QUANTITY	UNITS	REMARKS	
30+49.76, 15.50 Rt	37.74	SY	Lot 2, Blk 24 Purcell's 11th Add	
30+80.68, 15.50 Lt	35.00	SY	Lot 10, Blk 11 Purcell's 11th Add	
31+43.93, 15.50 Rt	39.50	SY	Lot 8, Blk 24 Purcell's 11th Add	
31+49.62, 15.50 Lt	34.78	SY	Lot 11, Blk 11 Purcell's 11th Add	
32+18.23, 15.50 Lt	35.18	SY	Lot 12, Blk 11 Purcell's 11th Add	
32+26.08, 15.50 Rt	34.29	SY	Lot 7, Blk 24 Purcell's 11th Add	
32+55.51, 15.50 Lt	39.20	SY	Lot 13, Blk 11 Purcell's 11th Add	
32+92.31, 15.50 Rt	39.20	SY	Lot 6, Blk 24 Purcell's 11th Add	
33+20.39, 15.50 Rt	50.78	SY	Lot 5, Blk 24 Purcell's 11th Add	
33+75.18, 15.50 Lt	41.31	SY	Lot 14/15, Blk 11 Purcell's 11th Add	
34+19.98, 15.50 Rt	31.85	SY	Lot 4, Blk 24 Purcell's 11th Add	
34+63.60, 15.50 Rt	37.44	SY	Lot 3, Blk 24 Purcell's 11th Add	
35+02.63, 15.50 Lt	37.88	SY	Lot 16, Blk 11 Purcell's 11th Add	
35+61.17, 15.50 Rt	35.29	SY	Lot 2, Blk 24 Purcell's 11th Add	
35+72.39, 15.50 Lt	36.85	SY	Lot 17, Blk 11 Purcell's 11th Add	
36+01.41, 15.50 Lt	35.26	SY	Lot 18, Blk 11 Purcell's 11th Add	
TOTAL SITE	601.55	SY		

DIRT WORK			
LOCATION	CUT (CY)	FILL (CY)	REMARKS
46th Street South	390.03	7.17	
S. Elizabeth Avenue	969.88	30.76	
STREET TOTAL	1359.91	37.93	
Ditch	187.86	0.00	
JOB TOTAL	1547.76	37.93	1509.84 CY Net Cut

EROSION CONTROL			
ITEM	QUANTITY	UNITS	REMARKS
BOC MATTING	1770	SY	
MATTING	1227	SY	
HAY BAIL DITCH CHECK	11	EA	
Project Seeding	1	LS	

RECAPITULATION OF ROAD QUANTITIES		
ITEM	QUANTITY	UNITS
AC Pavement 5" with 3" Bit Base	2229	SY
Reinforced Cruched Rock Base 5"	2959	SY
RCVG 5" RC Pvmt with 2" Bit Base	137	SY
Combined Curb & Gutter (6 5/8" Full Height)	261	LF
Combined Curb & Gutter (3 5/8" Roll Type)	1242	LF
Monolithic Edge Curb (6 5/8" Full Height)	81	LF
Driveway Pavement	601.55	SY
Sawed Joint	58	LF
Sediment Barrier, Hay Bail	11	EA
Back of Curb Matting	1770	SY
Erosion Matting	1227	SY
RCVG Removal	80	SY
Combined Curb & Gutter Removal	165	LF
Trees, Large Removal	6	EA
Trees, Small Removal	3	EA
Hedge Row Removal	20	LF
Wooven Wire Fence Removed & Replaced	265	LF
Gate Removed & Replaced	1	EA
Site Clearing & Restoration	1	LS
Project Seeding	1	LS
Street Signage	1	LS
Traffic Control	1	LS
Total Street Cut	1359.91	CY
Total Street Fill	37.93	CY
Total Ditch Cut	187.86	CY

Elizabeth Avenue Paving Quantities Wichita, Kansas				
 <small>516 S. Market, Wichita, KS 67202</small>		PROJECT NUMBER 472-84753		
		KEM NO. 08168	FILE quant	DATE 05/07/09
<small>316/264-0242</small>		DESIGN KM	DRAWN NS	REVISED