

SIERRA

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
	4+54.34	100.46	0.77	181.34	0.65	181.34
5+00	114.01	0.00	199.68	0.02	381.02	0.67
5+50	101.65	0.02	177.41	0.17	558.43	0.84
6+00	89.95	0.16	159.98	1.31	718.41	2.15
6+50	82.83	1.26	161.83	1.17	880.23	3.32
7+00	91.94	0.00	151.92	2.49	1032.15	5.81
7+50	72.13	2.69	134.44	4.91	1166.60	10.73
8+00	73.07	2.61	129.11	4.19	1295.71	14.91
8+50	66.37	1.91	126.35	4.36	1422.06	19.27
9+00	70.09	2.80	161.14	2.59	1583.21	21.86
9+50	103.95	0.00	219.93	0.69	1803.13	22.55
10+12.81	85.13	0.59	105.27	3.49	1908.40	26.04
10+50	67.71	4.47	113.17	14.03	2021.57	40.07
11+00	54.51	10.68	88.48	17.78	2110.05	57.85
11+50	41.06	8.53	74.09	15.99	2184.14	73.83
12+00	38.96	8.74	41.75	16.54	2225.89	90.37
12+30.62	34.66	20.43	0.00	0.00	2225.89	90.37


PUEBLO

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
	0+45.87	112.25	0.00	242.17	0.00	242.17
1+00	129.33	0.00	243.12	0.00	485.29	0.00
1+50	133.24	0.00	251.06	0.00	736.35	0.00
2+00	137.91	0.00	258.31	0.00	994.66	0.00
2+50	141.07	0.00	249.13	0.00	1243.80	0.00
3+00	128.00	0.00	218.34	0.00	1462.14	0.00
3+50	107.81	0.00	205.27	0.00	1667.41	0.00
4+00	113.88	0.00	211.59	0.00	1878.99	0.00
4+50	114.64	0.00	205.27	0.00	2084.27	0.00
5+00	107.06	0.00	199.46	0.12	2283.73	0.12
5+50	108.36	0.13	187.39	0.31	2471.12	0.43
5+95	116.50	0.24	209.32	0.24	2680.44	0.68
6+50	89.01	0.00	150.68	5.71	2831.11	6.39
7+00	73.72	6.17	137.51	10.85	2968.63	17.24
7+50	74.79	5.55	129.32	12.81	3097.94	30.04
8+00	64.87	8.29	120.18	13.22	3218.12	43.27
8+50	64.92	6.00	143.68	10.88	3361.79	54.15
9+00	90.25	5.76	143.40	8.71	3505.19	62.87
9+50	64.62	3.65	100.00	11.36	3605.19	74.23
10+00	43.39	8.62	92.11	9.57	3697.30	83.80
10+50	56.09	1.72	99.48	4.32	3796.78	88.12
11+00	51.35	2.95	106.81	5.80	3903.60	93.92
11+50	64.01	3.31	80.88	2.05	3984.48	95.97
11+79.75	82.80	0.41	0.00	0.00	3984.48	95.97

MARIPOSA

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
	0+50.02	55.09	1.13	128.87	1.08	128.87
1+00	84.15	0.04	150.90	0.13	279.77	1.20
1+50	78.83	0.10	151.67	0.88	431.44	2.09
2+00	84.97	0.86	167.32	0.81	598.76	2.89
2+50	95.73	0.02	184.91	0.01	783.67	2.91
3+00	103.98	0.00	179.38	0.00	963.05	2.91
3+50	89.76	0.00	210.64	0.00	1173.70	2.91
4+08.03	106.26	0.00	168.08	0.00	1341.78	2.91
4+48.03	120.65	0.00	230.31	0.00	1572.09	2.91
5+00	118.65	0.00	213.31	0.00	1785.40	2.91
5+50	111.72	0.00	211.13	0.00	1996.53	2.91
6+03.62	100.91	0.00	153.11	0.00	2149.65	2.91
6+50	77.36	0.00	63.40	0.64	2213.05	3.54
6+75	59.59	1.37	58.28	0.73	2271.33	4.28
7+00	66.29	0.21	154.67	0.19	2426.00	4.47
7+50	100.76	0.00	184.96	0.00	2610.96	4.47
8+00	99.00	0.00	189.18	0.00	2800.14	4.47
8+50	105.32	0.00	177.52	0.00	2977.66	4.47
9+00	86.40	0.00	168.37	0.00	3146.02	4.48
9+50	95.43	0.00	165.68	2.78	3311.71	7.25
10+00	83.50	2.99	166.59	9.19	3478.30	16.44
10+50	96.42	6.94	163.15	10.13	3641.45	26.58
11+00	79.79	4.01	142.59	7.57	3784.04	34.15
11+50	74.21	4.17	71.18	4.25	3855.22	38.40
11+76.90	68.69	4.35	0.00	0.00	3855.22	38.40

EARTHWORK QUANTITIES
WICHITA, KANSAS



Ruggles & Bohm, P.A.
Engineering, Surveying, Land Planning
924 North Main
Wichita, Kansas 67203
www.rbkansas.com
(316) 264-8008
(316) 264-4621 fax
E-mail: info@rbkansas.com

DRAWING FILE {Survey Base} PROJECT NUMBER 482-84648 DATE Sept 24, 2008

DESIGN KWL
DRAWN RLS
REVIEW
UTILITY
SHEET 33 OF 33