NOTE:
1) CONTRACTOR SHALL COORDINATE UTILITIES RELOCATION WITH:
   JADE DUNDAS
   WATER UTILITIES SEWAGE TREATMENT SUPT.
   PHONE: (316) 303-8702
   JDUNDAS@wichita.gov
2) CONTRACTOR SHALL COORDINATE BUILDING AND FENCE RELOCATION WITH:
   KENT SCHIERKOLK, UNIT MANAGER
   KDHE BER
   1000 SW JACKSON, SUITE 410
   TOPEKA, KS 66612-1367
   PHONE: (785) 368-7301
   kschierkolk@kdheks.gov
3) CONTRACTOR SHALL DISCONNECT AND RECONNECT ALL EXISITNG UTILITIES IN ACCORDANCE WITH ALL FEDERAL, STATE AND LOCAL REQUIREMENTS.
4) CONTRACTOR IS TO GRADE NEW LOCATION TO PROVIDE ADEQUATE DRAINAGE AWAY FROM BUILDING, AND TO PREVENT SETTLING.
5) PLACE 3" COMPACTED AB3 STONE OVER ENTIRE AREA WITHIN FENCE, INCLUDING UNDER BUILDING AND ALSO ON ACCESS DRIVE AS SHOWN.
6) ELECTRICAL SERVICE IS CURRENTLY BEING SUPPLIED THROUGH PLANT #2'S ELECTRICAL SYSTEM (THERE IS NO METER FOR THIS BUILDING TO RELOCATE) AND IS 100 AMP, SINGLE PHASE.
7) THE BUILDING WEIGHS APPROX. 18,000 LBS.
8) THE BUILDING DIMENSIONS ARE 10' X 24' X 9'.

MARK	DESCRIPTION	DATE	APPR.

amec
AMEC Earth & Environmental, Inc.
1129 SW Wanamaker
Topeka, Kansas 66604
Phone: (785) 272-4630
Fax: (785) 272-4678

CITY OF WICHITA

LEVEE "P"
WICHITA-VALLEY CENTER LOCAL FLOOD PROTECTION PROJECT
WICHITA, KANSAS

PREPARED FOR
THE CITY OF WICHITA, KANSAS
455 N. Main
Wichita, KS 67202

DON W. DOTSON LICENSED 19964 12/24/09 KANSAS PROFESSIONAL ENGINEER

DESIGNED BY: Don W. Dotson, P.E.		DATE: 2009/Oct/26
DWN BY: Staff	CKD BY: DWD	APP BY: MG
FILE NAME: 561500000-C-SP-210.dgn		
AMEC PROJ. NO. 5-6150-0000		

STORAGE BUILDING RELOCATION

SP-2.10

SHEET 16 OF 65