

VALVE BOX ADJUSTMENT TABLE			
STATION	ROADWAY	SIDE	VLV. NO.
108+83	Meridian	64' Lt.	34264
108+83	Meridian	25' Lt.	34263
112+98	Meridian	40' Lt.	26954
112+99	Meridian	60' Rt.	24565
118+53	Meridian	43' Lt.	22097
118+57	Meridian	45' Lt.	22099
124+76	Meridian	42' Lt.	22096
126+40	Meridian	22' Lt.	22095
153+79	Meridian	42' Rt.	19450
154+59	Meridian	42' Rt.	20413
156+78	Meridian	44' Rt.	19452
156+79	Meridian	42' Rt.	19451
158+98	Meridian	44' Rt.	19454
158+99	Meridian	42' Rt.	19453
161+33	Meridian	44' Rt.	19456
161+34	Meridian	42' Rt.	19455
163+06	Meridian	44' Rt.	19458
163+07	Meridian	42' Rt.	19457
164+95	Meridian	43' Rt.	19460
164+96	Meridian	45' Rt.	19459
165+86	Meridian	39' Rt.	26866
166+99	Meridian	40' Rt.	12666
168+71	Meridian	55' Rt.	20058
184+27	Meridian	80' Rt.	13492?
184+30	Meridian	80' Rt.	13492?
192+25	Meridian	44' Rt.	27235
192+29	Meridian	45' Rt.	27234
192+79	Meridian	49' Rt.	16375
193+14	Meridian	42' Rt.	32385
196+26	Meridian	53' Rt.	10810
196+27	Meridian	50' Rt.	27233
199+29	Meridian	42' Rt.	27236
199+47	Meridian	48' Rt.	27237
206+17	Meridian	45' Rt.	7152
206+29	Meridian	40' Rt.	7581
206+84	Meridian	39' Rt.	26652
297+56	31st Street	41' Lt.	18604
297+57	31st Street	39' Lt.	12579
297+58	31st Street	41' Lt.	18603
297+59	31st Street	39' Lt.	12578
299+27	31st Street	40' Lt.	7299

FOR INFORMATION ONLY. Cost to be SUBSIDIARY to the Bid Item "Adjustment of Water Valves".

WATER METER REPLACEMENT & ADJUSTMENT TABLE							
Address	Ex. Station	Ex. Offset	Prop. Station	Prop. Offset	Service	Remarks	Prop. Elev.
4650 S. Meridian	107+86	38' Rt.	107+86	42.5' Rt.	Long	Replace	1280.46
4636 S. Meridian	109+58	36' Rt.	109+58	45.0' Rt.	Long	Replace	1280.59
4631 S. Meridian	111+57	43' Lt.	--	--	Short	Adjust as Necessary	1279.97
4560 S. Meridian	114+70	31' Rt.	114+70	42.5' Rt.	Long	Replace	1280.17
4560 S. Meridian	114+74	31' Rt.	114+74	42.5' Rt.	Long	Replace	1280.18
4355 S. Meridian	127+67	32' Lt.	127+67	42.5' Lt.	Short	Replace	1281.21
4351 S. Meridian	128+08	28' Lt.	128+08	40.0' Lt.	Short	Replace	1280.78
4339 S. Meridian	129+08	28' Lt.	129+08	35.0' Lt.	Short	Replace	1280.78
4303 S. Meridian	132+75	33' Lt.	132+75	42.5' Lt.	Short	Replace	1281.94
4056 S. Meridian	139+10	31' Rt.	139+10	40.0' Rt.	Long	Replace	1282.15
2433 W. 31st St. S.	301+13	30' Rt.	301+30	35.0' Rt.	Long	Replace	1283.92
2433 W. 31st St. S.	301+83	32' Rt.	301+95	35.0' Rt.	Long	Replace	1284.15
2405 W. 31st St. S.	302+87	26' Rt.	302+87	35.0' Rt.	Long	Replace	1284.14
2405 W. 31st St. S.	302+89	25' Rt.	302+89	35.0' Rt.	Long	Replace	1284.16

The Contractor shall be aware that due to the roadway cuts and the depth of the existing 12" water line from Sta. 128+50 to Sta. 133+00 that there is the possibility of damaging the service line taps that come up vertically from the water line. The Contractor will be required to replace any taps damaged during construction. Cost for replacement taps shall be considered SUBSIDIARY to the Bid Item for the replacement of water meters.