



"Retaining Wall" includes compacted granular material, top soil removal and replacement, adjustment to lighting and irrigation appurtenances and paverstone units. Wall units shall be of the model and manufacture shown or approved equal. The color shall be "Sand Blend" or as directed by the Engineer.

GENERAL NOTES:

1. COMPACTION SHALL BE TO MANUFACTURER'S RECOMMENDATIONS.
2. PROVIDE LATERAL DRAINAGE. TURF SHALL BE ESTABLISHED IMMEDIATELY AFTER COMPLETION OF THE RETAINING WALL.
3. ALL MATERIALS AND LABOR REQUIRED TO INSTALL RETAINING WALL SHALL BE CONSIDERED SUBSIDIARY TO THE BID ITEM "MODULAR CONCRETE BLOCK RETAINING WALL".
4. THE AREA OF OF RETAINING WALL IS MEASURED FROM THE TOP OF FOOTING TO THE TOP OF WALL

Location	Dir.	Lin. Ft.	Sq. Ft. Face
Sta. 36+06 to 37+30	Maize Rd. Lt.	124.0	282
Sta. 39+35 to 40+10	Maize Rd. Lt.	75.0	169
Sta. 49+35 to 51+85	Maize Rd. Lt.	250.0	445

KANSAS DEPARTMENT OF TRANSPORTATION

MAIZE ROAD
MODULAR CONCRETE
BLOCK RETAINING WALLS