FHWA REG. NO.	STATE	PROJECT NO.:	YEAR	SHEET NUMBER	TOTAL SHEETS
7	KANSAS	87 N-0502-01	2009	53	226
		A.R.R.A-N05(201)			

20 0 10 20 40 (IN FEET) 1 INCH = 20 FT.

Sta. 51+38.99 42.57' Lt.
Construct Type 1 Curb Inlet
L=16'-10", W=6'-4",
H=6'-6"
Install 163.3 L.F. 42" RCP(N)
See Sheet No. 58

Sta. 51+39.39 58.23' Lt.
Construct Type 1 Manhole
Dia.=4.0', H=6'-6"
Install 15.7 L.F. 18" RCP(E)
See Sheet No. 58

Sta. 53+02.03, 34.67' Lt.
Construct Type 1-A Curb Inlet
L=11'-4", W=6'-4", H=6'-6"
Install 48.8 L.F. 42" RCP(N)
See Sheet No. 58

Sta. 53+50.86, 34.67' Lt.
Construct Type 1-A Curb Inlet
L=11'-4", W=6'-4", H=7'-0"
Install 219.2 L.F. 42" RCP(N)
See Sheet No. 58

Sta. 51+46.15, 33.67' Rt.
Construct Type 1-A Curb Inlet
L=11'-4", W=4'-4", H=5'-0"
Install 76.9 L.F. 24" RCP(W)
See Sheet No. 58

Sta. 52+99.88 33.67' Rt.
Construct Type 1-A Curb Inlet
L=11'-4", W=4'-4", H=6'-0"
Install 68.3 L.F. 30" RCP(W)
See Sheet No. 58

Sta. 53+42.69, 33.67' Rt.
Construct Type 1-A Curb Inlet
L=6'-4", W=4'-4", H=5'-0"
Install 42.8 L.F. 18" RCP(S)
See Sheet No. 58

MAIZE ROAD
WEST KELLOGG AVE. TO PAWNEE AVE.
CITY OF WICHITA, KANSAS
STORM SEWER P & P 49+80 to 55+60

No.	Date	By	Approved	Revision

POE & ASSOCIATES, INC.
CONSULTING ENGINEERS
5940 E. Central, Suite 200 ■ Wichita, KS 67208-4242
Phone 316/685-4114 ■ FAX 316/685-4444

FINAL

Engineer: P. FERGUSON
Designer: K. WARREN
KDOT Job No.: 87 N-0502-01 Poe Job No.: 1935
Date: SEPTEMBER 2009

Sheet 53 of 226