


PHASE	MAJOR CONSTRUCTION LIMITS	TRAFFIC CONTROL	CONFLICTS - COMMENTS
1	FULL SECTION OF HARRY STREET FROM STA. 17+32 TO THE HALF SECTION LINE AT STA. 45+44.	COMPLETE CLOSURE OF HARRY STREET IN CONSTRUCTION LIMITS.	MAINTAIN ALL DRIVEWAY ACCESS DURING CONSTRUCTION. CONFLICTS WITH PHASES 2, 3, 4 AND 5.
2	FULL SECTION OF HARRY FROM STA. 45+44 TO THE WEST LINE OF 127TH ST. EAST AT STA. 62+59.	COMPLETE CLOSURE OF HARRY STREET IN CONSTRUCTION LIMITS.	MAINTAIN ALL DRIVEWAY ACCESS DURING CONSTRUCTION. CONFLICTS WITH PHASES 1, 3, 4 AND 5.
3	HARRY STREET SOUTH HALF IMPROVEMENTS, FROM STA. 63+02 TO STA. 69+00 AND EAST HALF 127TH ST. EAST IMPROVEMENTS FROM STA. 4+22 TO 5+00.	ONE LANE EACH WAY ON HARRY AND 127TH ST. EAST. TEMPORARY PAVEMENT REQUIRED ON WEST SIDE OF HARRY. NO LEFT TURNS AT INTERSECTION.	MAINTAIN ALL DRIVEWAY ACCESS DURING CONSTRUCTION. CONFLICTS WITH PHASES 1, 2, 4 AND 5.
4	HARRY STREET SOUTH HALF IMPROVEMENTS FROM STA. 62+59 TO STA. 63+02 AND WEST HALF 127TH ST. EAST IMPROVEMENTS FROM STA. 4+22 TO 5+00.	ONE LANE EACH WAY ON HARRY AND 127TH ST. EAST. NO LEFT TURNS AT INTERSECTION.	CONFLICTS WITH PHASES 1, 2, 4 AND 5.
5	NORTH HALF OF HARRY AND 127TH ST. INTERSECTION IMPROVEMENTS AND 127TH ST. IMPROVEMENTS FROM STA. 5+04 TO 8+57.	ONE LANE EACH WAY ON HARRY. 127TH CLOSED AT NORTH LINE OF HARRY TO STA. 8+57. FULL CLOSURE LIMITED TO FOUR WEEKS. ONE LANE NORTHBOUND MUST BE MAINTAINED AFTER FOUR WEEKS.	MAINTAIN ALL DRIVEWAY ACCESS DURING CONSTRUCTION. CONFLICTS WITH PHASES 1, 2, 3 AND 4.

IN ADDITION TO UTILITY COMPANIES, THE CONTRACTOR SHALL CONTACT ALL OTHER PROPERTY OWNERS AND/OR TENANTS ADJACENT TO THIS PROJECT AT LEAST TEN DAYS PRIOR TO CONSTRUCTION.

CONSTRUCTION PHASING PLANS
PROJECT PHASING
WICHITA, KANSAS



Ruggles & Bohm, P.A.
 Engineering, Surveying, Land Planning

924 North Main
 Wichita, Kansas 67203
 www.rbkansas.com

DESIGN: KWL
 DRAWN: AML
 REVIEW: [blank]
 UTILITY: [blank]
 DATE: [blank]

(316) 264-8008
 (316) 264-4621 fax
 E-mail: info@rbkansas.com

SHEET
 104
 OF
 148

DRAWING FILE
Construction Phasing {Phasing}

PROJECT NUMBER
87 N-0514-01