

| PROJECT NO. | YEAR | SHEET NO. | TOTAL SHEETS |
|-------------|------|-----------|--------------|
| KA-1006-04  | 2010 | 31        | 71           |

| SIDEWALK CONSTRUCTION (4") (AE) |            |         |           |        |
|---------------------------------|------------|---------|-----------|--------|
| STATION TO STATION              | LOCATION   | SIDE    | AREA (SY) |        |
| 2065+10.35                      | 2071+27.73 | 47th St | RT        | 294.8  |
| 2071+71.45                      | 2077+56.43 | 47th St | RT        | 301.0  |
| 2065+04.48                      | 2071+27.98 | 47th St | LT        | 292.8  |
| 2071+57.96                      | 2076+92.03 | 47th St | LT        | 220.4  |
| <b>TOTAL</b>                    |            |         |           | 1109.1 |

| WHEELCHAIR RAMP W/ DETECTABLE WARNINGS |          |      |      |
|--|----------|------|------|
| STATION                                | LOCATION | SIDE | EACH |
| 2065+11                                | 47th St  | LT   | 1    |
| 2067+92                                | 47th St  | LT   | 1    |
| 2068+40                                | 47th St  | LT   | 1    |
| 2071+19                                | 47th St  | LT   | 1    |
| 2071+67                                | 47th St  | LT   | 1    |
| 2074+43                                | 47th St  | LT   | 1    |
| 2074+96                                | 47th St  | LT   | 1    |
| 2068+11                                | 47th St  | RT   | 1    |
| 2071+20                                | 47th St  | RT   | 1    |
| 2071+76                                | 47th St  | RT   | 1    |
| <b>TOTAL</b>                           |          |      | 10   |

| CURB AND GUTTER, COMBINED (AE) |            |          |                   |                   |                   |          |
|--------------------------------|------------|----------|-------------------|-------------------|-------------------|----------|
| STATION TO STATION             | SIDE       | LOCATION | TYPE 1 (LIN. FT.) | TYPE 2 (LIN. FT.) | TYPE 3 (LIN. FT.) | COMMENTS |
| 2065+10.66                     | 2071+27.99 | RT       | 473.0             | 185.8             |                   |          |
| 2071+68.49                     | 2077+10.24 | RT       | 494.3             | 68.7              |                   |          |
| 2065+05.03                     | 2071+27.63 | LT       | 640.7             |                   |                   |          |
| 2071+58.47                     | 2076+85.42 | LT       | 469.5             | 71.2              |                   |          |
| <b>TOTAL</b>                   |            |          | 2077.5            | 325.7             |                   |          |
| <b>COMBINED</b>                |            |          | 2403.2            |                   |                   |          |

| PAVEMENT REMOVAL        |           |         |
|-------------------------|-----------|---------|
| ITEM                    | AREA (SF) | SQ. YD. |
| Pavement (includes C&G) | 72223     | 8024.8  |
| Driveways               | 3291      | 365.7   |
| Conc. Parking           | 332       | 36.9    |
| Sidewalk                | 7876      | 875.1   |
| <b>Subtotal</b>         |           | 1277.7  |

| EARTHWORK SUMMARY  |            |            |      |         |     |                      |     |                |                |               |              |
|--------------------|------------|------------|------|---------|-----|----------------------|-----|----------------|----------------|---------------|--------------|
| STATION TO STATION | LOCATION   | EXCAVATION |      |         |     |                      |     | COMPACTION     |                |               |              |
|                    |            | COMMON     |      | ROCK    |     | CONTRACTOR FURNISHED |     | TYPE AA MR-0-5 | TYPE AA MR-5-5 | TYPE B MR-5-5 | TYPE B MR-90 |
|                    |            | CU. YD.    | VMF  | CU. YD. | VMF | CU. YD.              | VMF | CU. YD.        | CU. YD.        | CU. YD.       | CU. YD.      |
| 2064+77.14         | 2075+45.00 | 47th St.   | 1397 | 0.68    | 0   | 1.00                 | 0   | 0.68           | 114            |               |              |
| <b>TOTAL</b>       |            |            | 1397 |         | 0   |                      | 0   |                | 114            |               |              |



| SUMMARY OF QUANTITIES SHEET 1 OF 2 |            |          |
|------------------------------------|------------|----------|
| CITY ENGINEER                      |            |          |
| JAMES L. ARMOUR, P.E., L.S.        |            |          |
| PROJECT NUMBER                     | OCA NUMBER | DATE     |
| 472-84872                          | 991306     | 03/10    |
| CITY ENGINEER'S OFFICE             |            | DESIGN   |
| CITY HALL - SEVENTH FLOOR          |            | EGS      |
| 455 NORTH MAIN STREET              |            | RAM      |
| WICHITA, KANSAS 67202-1620         |            | SHEET    |
| (316) 268-4501                     |            | 31 OF 71 |
| (316) 268-4114 FAX                 |            |          |

Plotted on: Friday, March 19, 2010  
 h0  
 Kschoncker Plot Output: \\CBSM00\KCS08935-PS  
 Plot Scale: 0.9999981 Pen Table: 5037\_half.pen  
 Design Filename: \\Kc0w00\jobs\5037\Roadway\CD\SummaryofQuantities\quan0.dgn



\\Kc0w00\jobs\5037\Roadway\CD\SummaryofQuantities\quan0.dgn