STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	54–87 K–8259–02	2003	38	76

DATE	BY	
		REFERENCE NOTED
		REFERENCE CHECKED

EARTHWORK SUMMARY

	LOCATION	EXCAVATION						EMBANKMENT CONTRACTOR FURNISHED		COMPACTION			THROUGH CUTS NOT SUBGRADED					WASTE	
		COMMON		ROCK (PVMT. REMOVAL)						TYPE AA MR–0–5	TYPE B MR–90	TYPE	COMMON EXCAVATION	TYPE AA MR–0–5				COMMON	ROCK
		m^3	VMF	m^3	VMF			m^3	VMF	m^3	m^3							m^3	
	NORTH FRONTAGE ROAD	189	0.80	189	1.000			689	0.80	702									
																			189
	W.B. KELLOGG	479	0.80	477	1.000			3 410	0.80	3 111									
																			477
	E.B. KELLOGG	153	0.80	418	1.000			758	0.80	728									
																			418
	ARMOUR BRANCH BOX	904	0.80	–	–			5 375	0.80	5 023									
																			–
	GYPSUM CREEK BOX	4 472	0.80	–	1.000			2 544	0.80	5 613									
																			–
TOTAL		6 197		1 084				12 776		15 177									1 084

NOTE: QUANTITIES SHOWN ARE FOR INFORMATION ONLY. THE CONTRACT WILL BE BASED ON A LUMP SUM BID AS NOTED IN THE PROJECT SPECIAL PROVISIONS.

Plotted: SCALE 1:500

Drawn by:

File:

Cook, Flatt & Strobel
ENGINEERS, P.A.

KANSAS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

J:\02049-RCB\TRAFFIC CONTROL\sum1.dwg 4/25/2003 1:58:24 PM CDT