

DATE	
BY	
REFERENCE NOTED	
REFERENCE CHECKED	

SUMMARY OF QUANTITIES

LOCATION	STATION TO STATION	FULL DEPTH PLANT MIX BITUMINOUS MIXTURE - COMMERCIAL GRADE (Mg)	GEOGRID REINFORCED BASE		EMULSIFIED ASPHALT FOR TACK (Mg)	MILLING (40 mm) m ²	OVERLAY PLANT MIX BITUMINOUS MIXTURE - COMMERCIAL GRADE (Mg)	REMARKS
			AGGREGATE BASE m ²	GEOGRID m ²				
NORTH FRONTAGE ROAD	4+595 - 4+668						271	Variable Thichness (400 mm - 40 mm)
	4+663 - 4+740	367	936	936	0.131			
	4+740 - 4+775						86	Variable Thichness (160 mm - 40 mm)
W.B. KELLOGG	4+405 - 4+595					2 567	238	
	4+595 - 4+775	1 095	2 373	2 373	0.332			
	4+775 - 5+035					2 526	235	
E.B. KELLOGG	4+405 - 4+595					2 560	238	
	4+595 - 4+775	980	2 151	2 151	0.301			
	4+775 - 5+035					2 533	235	
MEDIAN PAVING		2 097	3 612	3 612	0.506			
TOTAL		4 539	9 072	9 072	1.403	10 186	1 303	

- Use 2 322 kg/m³
- Use 0.00014 Mg/m²

NOTE: QUANTITIES SHOWN ARE FOR INFORMATION ONLY. THE CONTRACT WILL BE BASED ON A LUMP SUM BID AS NOTED IN THE PROJECT SPECIAL PROVISIONS.

Drawn by: [blank] Plotted: [blank] File: 00011ph1/standards/sum.3.dwg SCALE: 1:500

