GRAPHIC SCALE
20 0 10 20 40
(IN FEET)
1 INCH = 20 FT.

67+00 | 67+50 | 68+00 | 68+50 | 69+00 | 69+50 | 70+00, HOR. PI | 71+07.91, PC | 71+50.25, HOR. PI | 72+07.91 | 73+00

−0.60% ℄ Grade

200' VC

Sta. 67+38.22, Construct Entrance Lt. See Sht. No. 35,81

Sta. 69+29.04, Construct Entrance Lt. See Sht. No. 35,81

Sta. 71+24.57, Construct Intersection Lt., Remove 22.6 S.Y. Concrete Flume See Sht. No. 33,81

Sta. 71+98.16, Construct Entrance Lt. Remove 19.3 L.F. 18" CMP See Sht. No. 35,81

Sta. 72+40.71, Construct Entrance Lt. Remove 17.0 L.F. 24" CMP See Sht. No. 35,81

Sta. 70+00.00 Horiz. PI

Sta. 71+50.25 Horiz. PI

Sta. 69+25.53, Construct Intersection Rt. See Sht. No. 31,34,81

Sta. 68+86.3, 14.3' – Sta. 69+09.7, 29.9' Rt. Remove 29.7 L.F. Split Rail Fence See Sht. No. 81

Sawcut (Full depth) Match Existing

Existing R/W

Construction Limits

℄ Pawnee Avenue Roadway = Section Line

℄ Pawnee Avenue Roadway

Section Line

CRESTLINE AVE.

PAWNEE AVENUE

PAWNEE CT.

BERNARD J

JOHNSON, MARION M ETUX

JOHNSON, MARION M & BEVERLY LIV TR

KILGROE, KORVIN J & TAMERA S

HURLEY, JOHN M JR & TAMARA R KING

LANE, RONALD F

VOEGELI, MICHAEL J JR & KARI L

HANNA, TODD A & MICHELLE R

V28808

V28635

8'x6' RCB @ 0.45%

8'x6' RCB @ 0.75%

Roadway ℄ +73.90

Roadway ℄ +80.69

LEGEND

Asphalt Removal

Tree Removal

No.	Date	By	Approved	Revision

PAWNEE AVENUE
119TH TO MAIZE ROAD
CITY OF WICHITA, KANSAS
PAVEMENT PLAN

POE & ASSOCIATES, INC.
CONSULTING ENGINEERS
5940 E. Central, Suite 200 ■ Wichita, KS 67208-4242
Phone 316/685-4114 ■ FAX 316/685-4444

FINAL

Engineer: P. FERGUSON
Designer: J. UNRUH
Poe Job No.: 1793
Date: JULY 2005