STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	87 N-0353-01	2005	117	162

SUMMARY OF TRAFFIC CONTROL DEVICES (EACH)

CONSTRUCTION SIGN (SPECIAL)		
SIGN NO.	16.25 SQ.FT. & LESS	16.26 SQ.FT. & OVER

SUMMARY OF TRAFFIC CONTROL DEVICES (EACH PER DAY)

✳ QUANTIFY MOST USED ON THE PROJECT AT ANY ONE TIME

FOR INFORMATION ONLY			
CONSTRUCTION SIGNS ✳			
MUTCD NO.	SIZE - SQ.FT.		
	0-9.25	9.26-16.25	16.26 & OVER
R11-2		12	
W20-3		7	
R11-4		9	
W20-1		2	
R2-1	2		
G20-2a	2		
R9-9	2		

FOR INFORMATION ONLY		
BARRICADES ✳	CHANNELIZING DEVICES ✳	
TYPE III (4' TO 8')	FIXED	PORTABLE
40		

FOR INFORMATION ONLY	
LIGHTED DEVICES ✳	
CONSTRUCTION WARNING LIGHT (TYPE "A" LOW INTENSITY)	80
CONSTRUCTION WARNING LIGHT (RED TYPE "B" HIGH INTENSITY)	
ARROW DISPLAY	
PORTABLE CHANGEABLE MESSAGE SIGN (LED)	

FOR INFORMATION ONLY		
RECAPITULATION OF QUANTITIES		
ITEM	QUANTITY	UNIT
CONSTRUCTION SIGNS (0 TO 9.25 SQ.FT.)	4	EACH PER DAY
CONSTRUCTION SIGNS (9.26 TO 16.25 SQ.FT.)	30	EACH PER DAY
CONSTRUCTION SIGNS (16.26 SQ.FT. & OVER)		EACH PER DAY
CONSTRUCTION BARRICADES (TYPE III - 4' TO 8')	40	EACH PER DAY
CHANNELIZER (FIXED)		EACH PER DAY
CHANNELIZER (PORTABLE)	96	EACH PER DAY
CONSTRUCTION WARNING LIGHT (TYPE "A" LOW INTENSITY)	80	EACH PER DAY
CONSTRUCTION WARNING LIGHT (RED TYPE "B" HIGH INTENSITY)		EACH PER DAY
ARROW DISPLAY		EACH PER DAY
PORTABLE CHANGEABLE MESSAGE SIGN (LED)		EACH PER DAY
PAVEMENT MARKING (TEMPORARY)		
4" SOLID (TEMPORARY TAPE)	36	STA./LINE
4" SOLID (TYPE II TAPE)		STA./LINE
4" BROKEN (8.2') (TYPE I TAPE)		STA./LINE
4" BROKEN (8.2') (TYPE II TAPE)		STA./LINE
4" BROKEN (3.3') (TYPE I TAPE)		STA./LINE
4" BROKEN (3.3') (TYPE II OR IIA TAPE)		STA./LINE
4" BROKEN (3.3') (PAINT)		STA./LINE
4" DOTTED EXTENSION (TYPE I TAPE)		STA./LINE
4" DOTTED EXTENSION (TYPE II TAPE)		STA./LINE
SOLID (LINE MASKING TAPE)		STA./LINE
BROKEN (LINE MASKING TAPE)		STA./LINE
EXISTING PAVEMENT MARKING REMOVAL		LIN. FT.
GLARE SCREEN		LIN. FT.
CONCRETE SAFETY BARRIER (TYPE 1)	255	LIN. FT.
CONCRETE SAFETY BARRIER (TYPE F3)(TEMP.-INSTALL ONLY)		LIN. FT.
CONCRETE SAFETY BARRIER (TYPE F3)(TEMP.-RELOCATE)		LIN. FT.
INERTIAL BARRIER SYSTEM		EACH
MODULE F200 (REPLACEMENT)		EACH
MODULE F400 (REPLACEMENT)		EACH
MODULE F700 (REPLACEMENT)		EACH
MODULE F1400 (REPLACEMENT)		EACH
MODULE F2100 (REPLACEMENT)		EACH
CONSTRUCTION SIGN (SPECIAL)		EACH
TEMPORARY RAISED PAVEMENT MARKER (TYPE I)		EACH
TEMPORARY RAISED PAVEMENT MARKER (TYPE II)		EACH
TRAFFIC SIGNAL INSTALLATION (TEMPORARY)		LUMP SUM
TEMPORARY TRAFFIC SIGNALS		LUMP SUM
TRAFFIC CONTROL (INITIAL SET UP)	LUMP SUM	LUMP SUM
TRAFFIC CONTROL	LUMP SUM	LUMP SUM
FLAGGER (SET)	1	HOUR
FENCE (CONSTRUCTION)(TEMPORARY)	AS NEEDED	LIN. FT.

NOTE:
TRAFFIC CONTROL BID AS "LUMP SUM".
QUANTITIES SHOWN ARE FOR INFORMATION ONLY AND MAY NOT BE COMPLETE.

NO.	DATE	REVISIONS	BY	APP'D
3	12-29-05	ADDED TYPE A & RED TYPE B LIGHTS	B.H.	A.A.A.
2	2-1-05	CONST. SIGN SPECIAL CHART	B.H.	A.A.A.
1	12-17-03	REMOVED TYPE I AND IV CSB, MODIFIED CSB NOTE	B.H.	S.A.B.

KANSAS DEPARTMENT OF TRANSPORTATION

SUMMARY OF DEVICES AND RECAPITULATION OF QUANTITIES

TE795 9/1/00

FHWA APPROVAL	12-29-05	APP'D Anthony A. Airobaire	
DESIGNED B.A.H.	DETAILED B.A.H.	QUANTITIES	TRACED
DESIGN CK.	DETAIL CK.	QUAN. CK.	TRACE CK.

Plotted By : $$USERNAME$$ $$$KDOTGRP$$$$, 6th Floor
Plot File : $$$$$$$$$$DGNSPEC$$$$$$$$$$$$$$$$
Plot Date : $$$$STIME$$$$