

PAVEMENT AND DRAINAGE IMPROVEMENTS – 751422 633791 620473

PHASE 2

WATERMAN ST. – MAIN ST. TO WASHINGTON ST.

OCA NO. 751422

CITY OF WICHITA PROJECT NO. 468-84167

AND

SOUTHEAST 48" WATERLINE – PHASE 1B

OCA NO. 633791

CITY OF WICHITA PROJECT NO. 448-90182

AND

WATERMAN SANITARY SEWER IMPROVEMENTS

EMPORIA ST. TO COMMERCE ST.

OCA NO. 620473

CITY OF WICHITA PROJECT NO. 468-84333

CITY OF WICHITA, KANSAS

JAMES L. ARMOUR, P.E. – CITY ENGINEER

FEBRUARY 2007

PLANS PREPARED BY

PROFESSIONAL ENGINEERING CONSULTANTS, P.A.
ENGINEERS
WICHITA, KANSAS

GENERAL NOTES

ALL ELEVATIONS SHOWN ARE NGVD29 DATUM.

THE CONTRACTOR SHALL NOT START WORK ON THE PROJECT UNTIL THE PROJECT INSPECTOR IS ASSIGNED TO THE PROJECT AND IS PRESENT ON THE SITE. ANY WORK DONE WITHOUT INSPECTION WILL BE REQUIRED TO BE UNCOVERED FOR INSPECTION.

ALL CONSTRUCTION WORK AND MATERIAL IN THIS PROJECT SHALL COMPLY WITH CITY OF WICHITA STANDARD SPECIFICATIONS FOR THE CONSTRUCTION OF CITY PROJECTS UNLESS OTHERWISE NOTED IN THE PLANS OR SPECIAL PROVISIONS.

UNDERGROUND UTILITY SERVICE LINES AND OVERHEAD UTILITY POLE LINES ARE TO BE ADJUSTED AS NECESSARY BY OTHERS DURING CONSTRUCTION UNLESS THE PLANS SPECIFICALLY CALL FOR THEIR ADJUSTMENT BY THE CONTRACTOR. EXISTING UTILITIES AND THEIR LOCATION, AS SHOWN ON THE PLANS, REPRESENT THE BEST INFORMATION OBTAINABLE FOR DESIGN. LOCATION INFORMATION HAS BEEN OBTAINED FROM THE VARIOUS UTILITY COMPANIES AND IS EITHER FROM COMPANY RECORD DRAWINGS OR COMPANY PROVIDED FIELD LOCATIONS. THE CONTRACTOR WILL BE REQUIRED TO WORK AROUND EXISTING UTILITIES WITHIN THE RIGHT-OF-WAY WHICH DO NOT CONFLICT WITH PROPOSED CONSTRUCTION.

TREES AND SHRUBS IN PUBLIC RIGHT-OF-WAY WHICH ARE IN DIRECT CONFLICT WITH PROPOSED NEW CONSTRUCTION SHALL BE REMOVED BY THE CONTRACTOR WITH THE ENGINEER'S APPROVAL. TREES AND SHRUBS WHICH ARE NOT IN DIRECT CONFLICT WITH PROPOSED NEW CONSTRUCTION SHALL BE SAVED AND PROTECTED FROM DAMAGE.

RUBBLE FROM THE REMOVAL OF MISCELLANEOUS STRUCTURES SHALL BE DISPOSED OF ON SITES TO BE PROVIDED BY THE CONTRACTOR AND APPROVED AS NOTED BELOW.

ALL DISPOSAL SITES MUST BE APPROVED BY THE KANSAS DEPARTMENT OF HEALTH AND ENVIRONMENT. MATERIAL EITHER STOCKPILED OR DISPOSED OF IN A FLOOD PLAIN WOULD REQUIRE A KANSAS STATE BOARD OF AGRICULTURE PERMIT. ANY MATERIAL DUMPED IN WATERS OF THE UNITED STATES OR WETLANDS IS SUBJECT TO U.S. CORPS OF ENGINEERS PERMITTING REGULATIONS. ANY MATERIAL BURIED OR STOCKPILED BEYOND APPROVED CONSTRUCTION LIMITS WOULD REQUIRE ADDITIONAL ARCHEOLOGICAL INVESTIGATIONS UNLESS BURIED IN A PREVIOUSLY APPROVED BORROW LOCATION.

CONTRACTOR SHALL SATISFY HIMSELF OF SURFACE AND SUBSURFACE CONDITIONS PRIOR TO BIDDING.

FIELD LOCATE ALL EXISTING UTILITIES PRIOR TO BEGINNING ANY EXCAVATION WORK. CONTACT THE KANSAS ONE-CALL SYSTEM AT 316-687-2470 AT LEAST 48 HOURS IN ADVANCE TO REQUEST FIELD LOCATES. FOR UTILITIES THAT ARE NOT MEMBERS OF THE KANSAS ONE-CALL SYSTEM, CONTACT THOSE COMPANIES DIRECTLY.

CONTRACTOR IS RESPONSIBLE FOR PRESERVING EXISTING PROPERTY IRONS. RE-ESTABLISH ANY EXISTING PROPERTY IRONS WHICH ARE DAMAGED OR DESTROYED BY CONSTRUCTION OPERATIONS, OR WHICH ARE COVERED BY 12" OR MORE OF FILL MATERIAL BY THIS PROJECT. SUCH IRONS SHALL BE RE-ESTABLISHED BY A LICENSED LAND SURVEYOR IN ACCORDANCE WITH STATE LAWS AND AT NO ADDITIONAL COST TO THE CITY.

THE CONTRACTOR SHALL REMOVE EXISTING ROAD SIGNS THAT INTERFERE WITH CONSTRUCTION. SIGNS DAMAGED THRU NEGLIGENCE OF THE CONTRACTOR SHALL BE REPLACED BY THE CONTRACTOR AT NO COST TO THE CITY. THE CONTRACTOR SHALL STOCKPILE THE SIGNS ALONG THE R/W (AT A CENTRAL LOCATION) FOR REMOVAL BY CITY FORCES.

ALL EXISTING PAVEMENT, SIDEWALK AND CURB AND GUTTER WITHIN THE CONSTRUCTION LIMITS SHALL BE SAW CUT, FULL DEPTH, TO THE NEAT LINES SHOWN ON THE PLANS, OR TO THE NEAREST JOINT, AND REMOVED, UNLESS OTHERWISE NOTED. SAW CUTTING SHALL BE SUBSIDIARY TO THE BID ITEM "PAVEMENT REMOVED".

EXISTING BRICK PAVERS THAT CONFLICT WITH CONSTRUCTION SHALL BE CAREFULLY REMOVED BY THE CONTRACTOR, PROTECTED FROM DAMAGE, AND DELIVERED TO THE CITY WICHITA'S WEST SUBSTATION LOCATED AT 661 N. ELDER. ALL COSTS FOR THIS WORK SHALL BE SUBSIDIARY TO "PAVEMENT REMOVED".

ALL RCB, STORM WATER SEWER, DUCT BANK, WATERLINE AND SANITARY SEWER EXCAVATION UNDER PROPOSED PAVEMENT SHALL BE SAND FILLED AND FLUSHED (JETTED AND VIBRATED) WITH WATER PER THE REQUIREMENTS LISTED IN THE STANDARD SPECIFICATIONS FOR THE CITY OF WICHITA, UNLESS FLOWABLE FILL OR OTHER IMPROVED BACKFILL MATERIAL IS OTHERWISE SPECIFIED. THE SAND FILL SHALL BE BROUGHT UP UNIFORMLY TO AN ELEVATION 12 INCHES ABOVE THE TOP OF THE PIPE OR 2 FEET BELOW THE BOTTOM OF PROPOSED PAVEMENT, WHICHEVER IS HIGHER. ALL COSTS FOR SAND FILLING AND FLUSHING SHALL BE INCLUDED IN THE UNIT PRICE BID FOR "SAND FILL, FLUSH AND VIBRATE". THIS ITEM SHALL BE PAID FOR AT THE UNIT PRICE BID PER LINEAR FOOT OF TRENCH FILLED REGARDLESS OF TRENCH DEPTH AND/OR PIPE SIZE UNLESS INDICATED OTHERWISE BY THE PLANS OR CONTRACT.

ALL LABOR, MATERIALS, AND EQUIPMENT NECESSARY TO MAKE CONNECTIONS TO EXISTING PIPE OR EXISTING SMALL STRUCTURES SHALL NOT BE PAID FOR DIRECTLY; BUT SHALL BE SUBSIDIARY TO OTHER ITEMS OF THE CONTRACT.

PLANS PREPARED BY

Professional Engineering Consultants, P.A.

303 S. TOPEKA • WICHITA, KANSAS 67202
316-262-2691 • FAX 316-262-3003

APPROVED - DATE

Feb 27, 2007

James L. Armour
JAMES L. ARMOUR, P.E. CITY ENGINEER
CITY OF WICHITA, SEDGWICK COUNTY, KANSAS
CITY NO. 468-84167

CITY OF WICHITA PROJECT NO. 468-84167
CITY OF WICHITA PROJECT NO. 448-90182
CITY OF WICHITA PROJECT NO. 468-84333

INDEX OF SHEETS	
R1.-R1.	Title Sheet
R2.-R3.	Typical Sections
R4.-R10.	Road Plans
R11.-R13.	Coordinate Geometry Plans
R14.	Curve Stake Out Tables
R15.-R23.	Intersection Details
R24.	Concrete Pavement
R25.	Contraction Joint Dowel Assemblies
R26.	Miscellaneous Details
R27.	Concrete Safety Barrier Details
R28.	Concrete Header at R.R. Crossing
R29.	Entrance Detail
R30.	Standard Drive Entrances Full Height Curb
R31.	Special Entrances Full Height Curb
R32.	Reinforced Concrete Alley Paving Details
R33.-R34.	Wheelchair Ramp Details
R35.	Sidewalk and Steps
R36.-R38.	Summary and Recapitulation of Quantities
R39.-R42.	Erosion Control – BMP'S
R43.	Traffic Signal General Notes
R44.-R54.	Traffic Signal Plans and Quantities
R55.	Steel Signal Pole Assembly Details
R56.	Traffic Signal Service Box Details
R57.-R58.	Signing and Marking Plans
R59.	Typical Miscellaneous Pavement Marking Details
R60.	Signing Details
R61.	Traffic Handling and Construction Sequence
R62.-R70.	Traffic Control Plans
R71.-R73.	Summary of Traffic Control Devices
R74.-R78.	Traffic Control Standards
R79.-R111.	Cross-Sections
D1.	Storm Water Sewer Key Map
D2.-D16.	Storm Sewer Plan/Profile
D17.	Standard Type 2 Inlet
D18.	Area Inlet
D19.	Drop Inlet
D20.	Driveway Grated Inlet Double
D21.	Underdrain Detail
D22.-D24.	Reinforced Concrete and Precast Manhole Details
D25.	RCB General Notes and Layout
D26.	Typical RCB Sections and Miscellaneous Details
D27.-D31.	RCB Transition Sections
D32.	Precast Concrete Plugs
D33.-D35.	RCB Details
E1.-E7.	Electrical Streetscape Plans
E8.	Electrical Lighting Detail
L1.-L7.	Landscape Plans
L8.-L9.	Landscape Details
U1.-U6.	Electric Duct Bank Plan/Profile
U7.-U8.	Electric Duct Bank Manhole Details
W1.	Title Sheet
W2.	Key Map and General Notes
W3.	Horizontal and Vertical Control
W4.	City of Wichita Waterline Map
W5.-W7.	Water Details
W8.-W16.	Waterline Plan/Profile
W17.-W25.	Waterline Adjustment Plans
W26.-W27.	Miscellaneous Adjustment Plans
W28.	Sanitary Sewer Plan/Profile
W29.	Type "P" Manhole Details
W30.	Frame and Cover Details
W31.	Manhole Adjustment Details