



NOTE:
TOP OF CURB ELEVATIONS SHOWN
ARE FOR FULL CURB. CONSTRUCT
CURB AND GUTTER AS NOTED.

CURVE TABLE - C2

$\Delta = 06^{\circ}42'23''$ $R = 1520.00'$ $T = 89.06'$ $L = 177.91'$ $LC = 177.81'$

CURVE DATA BASED ON CENTERLINE $\Delta/2 = 03^{\circ}21'12''$

| STATION | CHORD LENGTH | CHORD LENGTH | | DEFLECTION | TOTAL DEFLECTION |
|----------|--------------|--------------|-------------|------------|------------------|
| | | 8' Off LtCb | 8' Off RtCb | | |
| 17+56.98 | - | - | - | 00°00'00" | 00°00'00" |
| 17+75.00 | 18.02' | 18.28' | 17.76' | 00°20'23" | 00°20'23" |
| 18+00.00 | 25.00' | 25.36' | 24.64' | 00°28'16" | 00°48'39" |
| 18+25.00 | 25.00' | 25.36' | 24.64' | 00°28'16" | 01°16'55" |
| 18+50.00 | 25.00' | 25.36' | 24.64' | 00°28'16" | 01°45'11" |
| 18+75.00 | 25.00' | 25.36' | 24.64' | 00°28'16" | 02°13'28" |
| 19+00.00 | 25.00' | 25.36' | 24.64' | 00°28'16" | 02°41'44" |
| 19+25.00 | 25.00' | 25.36' | 24.64' | 00°28'16" | 03°10'00" |
| 19+34.89 | 9.89' | 10.04' | 9.75' | 00°11'11" | 03°21'12" |

Def/Ft = 1.13084 Min.

PAVING AND INCIDENTAL DRAINAGE PLANS FOR
BOTANICA - THE WICHITA GARDENS
STREETS AND UTILITIES IMPROVEMENTS

PAVING PLAN
SHEET TITLE
472-84758
PROJECT NUMBER

DMU
DESIGN BY
DMU
DRAWN BY
GJA
CHECKED BY

ISSUED
July 2010
REVISED

SHEET NO.
9 of 23