STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	54–87 K–8258–01	2007	113	556

SCHEDULE OF INLETS & MANHOLES

STRUCT. NO.	STATION	LOCATION	OFFSET DIST.	OFFSET SIDE	GRATE INLET SPECIAL	CURB INLET TYPE 10	PRE CAST MH	STD. TYPE P MH	CURB INLET TYPE I	SPEC STM J BOX	CURB INLET TYPE IA	GRATE INLET SPECIAL (2)	PIPE DATA: INFLOW PIPES SIZE (mm)	INFLOW PIPES FL EL.	INFLOW PIPES SIZE (mm)	INFLOW PIPES FL EL.	INFLOW PIPES SIZE (mm)	INFLOW PIPES FL EL.	OUTFLOW PIPE SIZE (mm)	OUTFLOW PIPE FL EL.	OUTFLOW PIPE SL. (%)	STRUCTURE INFO. TOP ELEV.	FLOOR ELEV.	H mm	W mm	L mm	STEPS (No.)	STORM SEWER RCP (m) (mm)	375 (mm)	450 (mm)	600 (mm)	750 (mm)	900 (mm)	1050 (mm)	1200 (mm)	1350 (mm)	1500 (mm)	1650 (mm)	2100 (mm)	RCPHE ✻(1) (mm)	Ht. Fill (m)	Remarks
301	2+920.000	Kellogg Avenue	17.6	Rt.								1							375(N)	411.395	0.715	412.784							15.8													
302	2+960.000	Kellogg Avenue	16.7	Rt.								1							375(N)	411.735	0.799	413.448							14.9													
303	3+000.000	Kellogg Avenue	16.7	Rt.								1							375(N)	412.367	0.779	414.088							14.9													
304	3+040.000	Kellogg Avenue	16.7	Rt.								1							375(N)	413.031	1.584	414.744							14.9													
305	3+080.000	Kellogg Avenue	16.7	Rt.								1							375(N)	413.682	2.799	415.395							14.9													
306	3+120.000	Kellogg Avenue	16.7	Rt.								1							375(N)	414.225	5.537	415.938							14.9													
307	3+160.000	Kellogg Avenue	16.7	Rt.								1							375(N)	414.618	5.583	416.331							15.1													
308	3+200.000	Kellogg Avenue	16.7	Rt.								1							375(N)	414.860	5.695	416.573							15.1													
317	3+300.000	Kellogg Avenue	16.7	Rt.								1							375(N)	414.805	2.020	416.518							15.1													
315	3+335.000	Kellogg Avenue	16.7	Rt.								1							375(N)	414.563	0.387	416.276							16.3													
350	3+420.000	Kellogg Avenue	16.7	Rt.								1							375(N)	413.498	0.795	415.211							15.1													
349	3+460.000	Kellogg Avenue	16.7	Rt.								1							375(N)	412.761	0.795	414.474							15.1													
348	3+500.000	Kellogg Avenue	16.7	Rt.								1							375(N)	411.873	0.795	413.586							15.1													
347	3+540.000	Kellogg Avenue	16.7	Rt.								1							375(N)	410.839	0.795	412.552							15.1													
346	3+580.000	Kellogg Avenue	16.7	Rt.								1							375(N)	409.763	2.604	411.476							14.9													
386	3+618.000	Kellogg Avenue	16.7	Rt.								1	375(S)	408.278					375(N)	408.268	0.623	410.453							15.1													
387	3+618.000	Kellogg Avenue	27.5	Rt.	1														375(N)	408.339	0.604	410.052							10.1													
385	3+665.000	Kellogg Avenue	26.0	Rt.	1														375(N)	407.301	0.615	409.014							24.4													
384	3+710.000	Kellogg Avenue	24.4	Rt.	1														375(N)	406.122	0.614	407.835							22.8													
383	3+755.000	Kellogg Avenue	22.8	Rt.	1														375(N)	404.945	0.618	406.658							21.2													
382	3+795.000	Kellogg Avenue	21.4	Rt.	1														375(N)	404.044	0.619	405.757							19.7													
381	3+835.000	Kellogg Avenue	20.0	Rt.	1														375(N)	403.379	0.623	405.092							18.3													
461	4+030.000	Kellogg Avenue	18.3	Rt.	1														375(N)	403.410	0.629	405.123							16.7													
462	4+075.000	Kellogg Avenue	16.7	Rt.	1														375(N)	404.190	0.629	405.903							15.1													
463	4+125.000	Kellogg Avenue	16.7	Rt.	1														375(N)	405.045	0.629	406.758							15.1													
464	4+175.000	Kellogg Avenue	16.7	Rt.	1														375(N)	405.910	0.629	407.623							15.1													
465	4+225.000	Kellogg Avenue	16.7	Rt.	1														375(N)	406.775	0.629	408.488							15.1													
291	2+920.000	Kellogg Avenue	25.9	Lt.	1								600(S)	410.860					600(N)	410.8±	1.000	412.542																			
292	2+960.000	Kellogg Avenue	16.7	Lt.								1							375(S)	411.719	0.609	413.432							16.9													
293	3+000.000	Kellogg Avenue	16.7	Lt.								1							375(S)	412.375	0.734	414.088							16.9													
294	3+040.000	Kellogg Avenue	16.7	Lt.								1							375(S)	413.031	1.396	414.744							16.9													
295	3+080.000	Kellogg Avenue	16.7	Lt.								1							375(S)	413.682	2.467	415.395							16.9													
296	3+120.000	Kellogg Avenue	16.7	Lt.								1							375(S)	414.225	4.882	415.938							16.9													
297	3+160.000	Kellogg Avenue	16.7	Lt.								1							375(S)	414.618	4.928	416.331							17.1													
298	3+200.000	Kellogg Avenue	16.7	Lt.								1							375(S)	414.852	4.982	416.573							17.1													
316	3+300.000	Kellogg Avenue	16.7	Lt.								1							375(S)	414.805	1.784	416.518							17.1													
314	3+335.000	Kellogg Avenue	16.7	Lt.								1							375(S)	414.563	0.459	416.276							18.1													
340	3+420.000	Kellogg Avenue	16.7	Lt.								1							375(S)	413.498	0.702	415.211							17.1													
339	3+460.000	Kellogg Avenue	16.7	Lt.								1							375(S)	412.761	0.702	414.474							17.1													
338	3+500.000	Kellogg Avenue	16.7	Lt.								1							375(S)	411.873	0.702	413.586							17.1													
337	3+540.000	Kellogg Avenue	16.7	Lt.								1							375(S)	410.839	0.702	412.552							17.1													
336	3+580.000	Kellogg Avenue	16.7	Lt.								1	600(S)	408.940					600(S)	408.890	2.426	411.476								20.2												
376	3+618.000	Kellogg Avenue	17.3	Lt.								1	375(S)	408.338					375(S)	408.150	0.621	410.361							17.7													
377	3+620.000	Kellogg Avenue	28.6	Lt.	1														375(S)	408.401	0.636	410.114							9.9													
375	3+665.000	Kellogg Avenue	27.1	Lt.	1														375(S)	407.279	0.615	408.992							27.5													
374	3+710.000	Kellogg Avenue	25.6	Lt.	1														375(S)	406.098	0.615	407.811							26.0													
373	3+755.000	Kellogg Avenue	24.1	Lt.	1														375(S)	404.919	0.616	406.632							24.5													
372	3+795.000	Kellogg Avenue	22.8	Lt.	1														375(S)	404.017	0.619	405.730							23.1													
371	3+835.000	Kellogg Avenue	21.4	Lt.	1														375(S)	403.35	0.622	405.063							21.7													
451	4+030.000	Kellogg Avenue	16.7	Lt.	1														375(S)	403.430	0.620	405.143							17.1													
452	4+075.000	Kellogg Avenue	16.7	Lt.	1														375(S)	404.180	0.620	405.893							17.1													
453	4+125.000	Kellogg Avenue	16.7	Lt.	1														375(S)	405.045	0.620	406.758							17.1													
454	4+175.000	Kellogg Avenue	16.7	Lt.	1														375(S)	405.910	0.620	407.623							17.1													
455	4+225.000	Kellogg Avenue	16.7	Lt.	1														375(S)	406.775	0.626	408.488							17.1													
		TOTALS			23							31																	894.1		20.2											

NOTE: ALL STATION & OFFSETS ARE FROM CENTERLINE KELLOGG.

Cook, Flatt & Strobel ENGINEERS, P.A.

KANSAS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF INLETS & MANHOLES
KELLOGG AVENUE

BY | DATE
REFERENCE NOTED
REFERENCE CHECKED

Plotted: 1/9/2006 2:41:51 PM CST
Drawn by:
File: J:\00011PH2 FINAL\DRAINAGE\SCHEDULE OF INLETS.dwg

J:\00011PH2 FINAL\DRAINAGE\SCHEDULE OF INLETS.dwg 1/9/2006 2:41:51 PM CST