STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	472–84703	2010	21	36

RECAPITULATION OF QUANTITIES

Line	Item	Quantity	Unit
1	Site Clearing & Restoration	1	L.S.
2	Common Excavation	149	C.Y.
3	Rock Excavation	68	C.Y.
4	Compaction of Earthwork (Type B)(MR–90)	42	C.Y.
5	Reinforced Crushed Rock Base	323	S.Y.
6	Curb & Gutter	182	L.F.
7	Adjust Manhole	1	Ea.
8	15" Storm Sewer (RCP)	26	L.F.
9	7" AC Pavement (BM–2)(PG70–28)	280	S.Y.
10	17 1/2" to 8 1/2" Variable AC Pvmt. (BM–2)(PG70–28)	210	S.Y.
11	Saw Cuts	188	L.F.
12	Wheelchair Ramp Construction	4	Ea.
13	Field Office & Lab. (Type A)	1	Ea.
14	Mobilization	1	L.S.
15	Seeding (w/ Erosion Mat)	1	L.S.
16	Traffic Control	1	L.S.
17	Pavement Marking	1	L.S.
18	Sidewalk Construction (4")	513	S.F.
19	Sidewalk Construction (Variable 8" to 14")	630	S.F.
20	Electronic Message Board	90	Days
21	Curb Inlet Protection	2	Ea.
22	Silt Fence	160	L.F.
23	Erosion Control Blanket	60	S.Y.
24	Construction Entrance	1	Ea.
	BRIDGE: 3–12'x 5'x 72'– 1 1/8" R.F.B. w/ Conc. Apron & Soil Saver Lt.		
25	Removal of Existing Structures	1	L.S.
26	Slope Protection (Rip Rap Stone)(24" Light Stone)	60	S.Y.

For Bridge Quantities, See Sh. 11

J:\2008Proj\08566\DWGS\SUMMARY OF QTY.dwg 7/20/2010 – 7:54am lmartin

CITY OF WICHITA

SUMMARY OF QUANTITIES

Lincoln Street Bridge at Armour Drive

City of Wichita Proj. No. 472–84703

Cook, Flatt & Strobel ENGINEERS, P.A.

DESIGNED	SCALE
DETAILED	DATE
QUANTITIES	SHEET OF