FHWA REG. NO.	STATE	PROJECT NO.:	YEAR	SHEET NUMBER	TOTAL SHEETS
7	KANSAS	87 U-2227-01	2010	3	17

ESTIMATE OF QUANTITES

BASE BID

ITEM	DESCRIPTION	QUANTITY	UNIT
1*	AC SURFACE COURSE (BM-1B) (PG 70-28)	1,297	TN
2*	COLD MILLING ASPHALT SURFACE (2" NOM.)	11,787	SY
3*	REINFORCED CONCRETE BASE REPAIR (10")	1,400	SY
4*	ASPHALT SHOULDER REPAIR (BM2)	200	TN
5*	GRAVEL SHOULDER REPAIR	100	TN
6*	6" WHITE OR YELLOW PVMT MARKINGS (THERMOPL)	8,000	LF
7*	12" WHITE OR YELLOW PVMT MARKINGS (THERMOPL)	246	LF
8*	TURN ARROW PVMT MARKINGS	8	EA
9*	TRAFFIC CONTROL	1	LS

* PARTICIPATING ITEMS

THE CITY OF WICHITA
CITY ENGINEER'S OFFICE
CITY HALL - SEVENTH FLOOR
455 NORTH MAIN STREET
WICHITA, KANSAS 67202
(316) 268-4501
(316) 268-4114 FAX

KELLOGG (U.S. 54/400) FROM 119TH ST. W. TO 111TH ST. W.

JAMES L. ARMOUR P.E. - CITY ENGINEER

ENGINEER:	DRAWN BY:
B. RAHBAR	A. P. ROSAS
PROJECT NUMBER: 472-84815b	INDEX CODE: 707006
DATE: FEB. 2010	SHEET 3 OF 17