



CONTRACTOR TO VERIFY LOCATION AND DEPTH OF EXISTING 12" PRIOR TO CONSTRUCTION.

N 1762324.36 E 1596076.80
STA. 0+64.07 LINE 1
BL STA. 3+86.00, 64.00' RT
1 -90° 12"x16" M.J. REDUCING BEND

CAUTION: OVERHEAD POWER LINES

REMOVE AND REPLACE 20 L.F. EXISTING WIRE FENCE.

REMOVE AND REPLACE 20 L.F. EXISTING WIRE FENCE.

54.07 +/- L.F. 12" PIPE

485.93 L.F. 16" PIPE

REMOVE EXIST 12" C.I. TO DIP FITTING @ WELL HOUSE. REPLACE WITH 17 LF 12" DIP AND 1-90° 12" MJ BEND.

BENTLEY PUMP STATION AND BACKFLOW PREVENTION DEVICE.

APPROXIMATE LOCATION OF 6" WATER LINE CONNECTION. 6" WATER LINE BY OTHERS, CONNECTION BY CITY OF WICHITA.

REMOVE EXISTING TREES ONLY AS NECESSARY FOR CONSTRUCTION. SUBSIDIARY TO BID ITEM FOR "SITE CLEARING".

N 1762270.20 E 1596067.31
STA. 0+00.00 LINE 1
BL STA. 3+76.00, 118.07' RT
BEGIN CONSTRUCTION OF 12" WATER LINE 10 L.F. 12" D.I.P. (E)

N 1762270.29 E 1596077.31
STA. 0+10.00 LINE 1
BL STA. 3+86.00, 118.07' RT
1 -90° 12" M.J. BEND



Ruggles & Bohm, P.A.
Engineering, Surveying, Land Planning
602 North Main Street
Wichita, Kansas 67202
www.rugglesandbohm.com



REVISION
DRAWN
DATE
REVIEW
DATE
UTILITY
June 24, 2010

PROJECT NUMBER
W-549 / 448-90498
DRAWING FILE
ENGINEERING BASE (07 Plan 1)

BENTLEY TIE IN
LINE 1
WICHITA, KANSAS
RB JOB
3523W
SHEET
7
23