



***NOTE**
Contractor shall be required to grade the existing ground beyond the limits of the concrete ditch to match. All disturbed or graded areas beyond the concrete ditch limits shall be seeded, mulched, and covered with Curlex II or Excelsior blanket. Grading, seeding, mulching, erosion blanket, and etc. shall be considered **SUBSIDIARY** to the Lump Sum BID ITEM "Site Clearing and Restoration".

