


FHWA REG. NO.	STATE	PROJECT NO.	YEAR	SHEET NUMBER	TOTAL SHEETS
7	KANSAS	15-87 U-2192-01	2010	3	16

ESTIMATE OF QUANTITIES

ITEM	DESCRIPTION MEASURED QUANTITY ITEMS (707016)	QUANTITY	UNIT
1	A.C. Surface Course (BM-1B) (PG-70-28)	2,100	tn
2	Cold Milling Asphalt Surface (2" Nom.)	19,335	sy
3	Reinf. Concrete Base Repair	500	sy
4	Asphalt Shoulder Repair (BM2) (PG-64-22)	120	tn
5	6" White or Yellow Pavement Markings (Thermopl.)	13,050	lf
6	12" White or Yellow Pavement Markings (Thermopl.)	30	lf
7	Turn Arrow Pavement Markings (Thermopl.)	5	ea.
8	Traffic Control	1	ls

KDOT PROJECT NO. 15-87 U-2192-01

 CITY OF WICHITA PUBLIC WORKS & UTILITIES ENGINEERING DIVISION	2010 KLINK SB K-15, I-135 TO KTA		
	CITY ENGINEER JAMES L. ARMOUR, P.E., L.S.		
	PROJECT NUMBER 472-84897	OCA NUMBER 707016	DATE 12/2010
	CITY ENGINEER'S OFFICE CITY HALL - SEVENTH FLOOR 455 NORTH MAIN STREET WICHITA, KANSAS 67202-1620 (316) 268-4501		DESIGN DRAWN A.P.ROSAS SHEET 3 of 16