STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	87N-0494-01	2011	41	69

SUMMARY OF TRAFFIC CONTROL DEVICES (EACH)

WORK ZONE SIGN (SPECIAL)		
SIGN NO.	16.25 SQ.FT. & LESS	16.26 SQ.FT. & OVER

SUMMARY OF TRAFFIC CONTROL DEVICES (EACH PER DAY)

✳ QUANTITY MOST USED ON THE PROJECT AT ANY ONE TIME

WORK ZONE SIGNS ✳			
SIGN NO.	SIZE - SQ.FT.		
	0-9.25	9.26-16.25	16.26 & OVER
W20-1	4		
W4-2 LT.	2		
W4-2 RT.	2		
R3-2	4		
R9-9	4		
R5-1	3		
W1-4L	2		
W1-4R	2		
W13-1	4		
R4-7b	3		
KG20-2	4		
KM4-20	8		
KI-104a	4		
KI-105a	4		
R2-1	4		

BARRICADES ✳	CHANNELIZING DEVICES ✳	
TYPE III (4' TO 12')	FIXED	PORTABLE
30		

LIGHTED DEVICES ✳	
WORK ZONE WARNING LIGHT (TYPE "A" LOW INTENSITY)	
WORK ZONE WARNING LIGHT (RED TYPE "B" HIGH INTENSITY)	
ARROW DISPLAY	
PORTABLE CHANGEABLE MESSAGE SIGN	

RECAPITULATION OF QUANTITIES		
ITEM	QUANTITY	UNIT
WORK ZONE SIGNS (O TO 9.25 SQ.FT.)	54	EACH PER DAY
WORK ZONE SIGNS (9.26 TO 16.25 SQ.FT.)		EACH PER DAY
WORK ZONE SIGNS (16.26 SQ.FT. & OVER)		EACH PER DAY
WORK ZONE BARRICADES (TYPE III - 4' TO 12')	30	EACH PER DAY
CHANNELIZER (FIXED)		EACH PER DAY
CHANNELIZER (PORTABLE)	LUMP SUM	EACH PER DAY
WORK ZONE WARNING LIGHT (TYPE "A" LOW INTENSITY)		EACH PER DAY
WORK ZONE WARNING LIGHT (RED TYPE "B" HIGH INTENSITY)		EACH PER DAY
ARROW DISPLAY		EACH PER DAY
PORTABLE CHANGEABLE MESSAGE SIGN		EACH PER DAY
PAVEMENT MARKING (TEMPORARY)		
4" SOLID (TYPE I TAPE)	LUMP SUM	STA./LINE
4" SOLID (TYPE II TAPE)		STA./LINE
4" BROKEN (8.2') (TYPE I TAPE)		STA./LINE
4" BROKEN (8.2') (TYPE II TAPE)		STA./LINE
4" BROKEN (3.3') (TYPE I TAPE)		STA./LINE
4" BROKEN (3.3') (TYPE II OR IIA TAPE)		STA./LINE
4" BROKEN(3.3')(FLEXIBLE RAISED PAVEMENT MARKER)		STA./LINE
4" DOTTED EXTENSION (TYPE I TAPE)		STA./LINE
4" DOTTED EXTENSION (TYPE II TAPE)		STA./LINE
SOLID (LINE MASKING TAPE)		STA./LINE
BROKEN (LINE MASKING TAPE)		STA./LINE
PAVEMENT MARKING REMOVAL		LIN. FT.
GLARE SCREEN		LIN. FT.
CONCRETE SAFETY BARRIER (TYPE F3)(TEMPORARY)		LIN. FT.
CONCRETE SAFETY BARRIER (TYPE F3)(TEMP.-INSTALL ONLY)		LIN. FT.
CONCRETE SAFETY BARRIER (TYPE F3)(TEMP.-RELOCATE)		LIN. FT.
INERTIAL BARRIER SYSTEM		EACH
REPLACEMENT MODULES (F2OO)		EACH
REPLACEMENT MODULES (F4OO)		EACH
REPLACEMENT MODULES (F7OO)		EACH
REPLACEMENT MODULES (F14OO)		EACH
REPLACEMENT MODULES (F21OO)		EACH
WORK ZONE SIGN (SPECIAL) (16.25 SQ. FT. & LESS)		EACH
WORK ZONE SIGN (SPECIAL) (16.26 SQ. FT. & MORE)		EACH
TEMPORARY RAISED PAVEMENT MARKER (TYPE I)		EACH
TEMPORARY RAISED PAVEMENT MARKER (TYPE II)		EACH
TRAFFIC SIGNAL INSTALLATION (TEMPORARY)		LUMP SUM
TRAFFIC CONTROL (INITIAL SET UP)	LUMP SUM	LUMP SUM
TRAFFIC CONTROL		LUMP SUM
FLAGGER (SET PRICE)		HOUR
TWORKS SIGN ASSEMBLY	4	EACH

NO.	DATE	REVISIONS	BY	APP'D
3	8/8/07	2007 Spec Revision	M.B.	A.A.A.
2	12/29/05	Added Type A & Red Type B Lights	B.H.	A.A.A.
1	2/1/05	Const. Sign Special Chart	B.H.	A.A.A.

KANSAS DEPARTMENT OF TRANSPORTATION

SUMMARY OF DEVICES AND RECAPITULATION OF QUANTITIES

TE795 9/1/00

FHWA APPROVAL		8/8/2007	APP'D	Anthony A. Alrobaire	
DESIGNED	B.A.H.	DETAILED	B.A.H.	QUANTITIES	TRACED
DESIGN CK.		DETAIL CK.		QUAN. CK.	TRACE CK.

KDOT Graphics Certified 10-04-2010

KDOT Graphics Certified

Plotted$$SYTIME$$
$$KDOTGRP$$

Drawn By untitled
File$$DGNSPEC$$