

DELANO CIRCLE

STATION	AREAS		VOLUMES		CUMULATIVE VOLUMES	
	CUT	FILL	CUT	FILL	CUT	FILL
0+00	0.00	0.00				
0+34.14	30.20	0.00	19.09	0.00	19.09	0.00
0+50	33.67	0.00	18.76	0.00	37.85	0.00
1+00	28.83	0.00	57.87	0.00	95.72	0.00
1+50	25.57	0.07	50.37	0.07	146.09	0.07
2+00	20.42	0.26	42.59	0.31	188.68	0.37
2+50	16.60	0.46	34.28	0.67	222.95	1.04
3+00	16.41	0.47	30.56	0.86	253.52	1.90
3+50	15.56	0.51	29.61	0.91	283.12	2.82
4+00	20.19	0.27	33.11	0.73	316.23	3.54
4+50	29.93	0.00	46.41	0.25	362.64	3.80
4+78.93	35.23	0.00	34.91	0.00	397.55	3.80
5+04.66	70.78	0.00	50.51	0.00	448.06	3.80
5+22.16	67.84	0.00	44.92	0.00	492.99	3.80
5+39.66	71.61	0.00	45.19	0.00	538.18	3.80
5+57.66	9.44	0.50	27.02	0.17	565.20	3.96
5+73.16	0.00	0.00	2.71	0.14	567.90	4.11
			0.00	0.00	567.90	4.11

EARTHWORK SUMMARY				
STREET	STREET	CUT	LOOSE FILL	COMPACTED FILL
		CU. YDS.	CU. YDS.	CU. YDS.
	DELANO CIRCLE	568	4	0
	15% SHRINKAGE		1	0
	STREETS TOTAL	568	5	0

No.	Date	By	Approved	Revision
1				
2				
3				
4				

FOUR H. ADDITION
STREET IMPROVEMENTS
EARTHWORK SUMMARY
CITY OF WICHITA, KANSAS
JAMES ARMOUR, P.E. - CITY ENGINEER
C.O.W. Project # 472-82312 O.C.A. # 765923

POE & ASSOCIATES, INC.
CONSULTING ENGINEERS
5940 E. Central, Suite 2000 Wichita, KS 67208-4242
Phone 316/685-4114 FAX 316/685-4444



FINAL
Designed By: T. Austin
Drawn By: S. Schmidt
Poe Job No.: AM 04106-02
Date: January 2005