

APPROVED	DESIGNED	QUANTITIES	QUANLCK.
DESIGNED CK.	QUANTITIES	QUANLCK.	TRACE CK.
DETAILED	DETAILED CK.	TRACED	TRACE CK.

Plotted on: Friday, December 16, 2011 09:34 AM
 By: Jwoolard Plot Scale: 2.0000044
 Design File Name: \\ovp\p00\Jobs\4324\CD\Detail\Gyp_Arm_quantities.dgn

RECAPITULATION OF QUANTITIES			
NO.	ITEM	UNIT	QUANTITY
Grading and Heavy Construction			
1	Site Clearing	LS	1
2	Site Restoration	LS	1
3	SWS Pipe Removed 0"-20"	LF	64
4	Excavation	CY	38,272
5	SWS Pipe RCP 15"	LF	62
6	SWS Pipe RCP 18"	LF	120
7	SWS Pipe RCP 18" End Section	EA	3
8	SWS Pipe RCP 24" End Section	EA	1
9	SWS Pipe RCP 48" End Section	EA	2
10	SWS Pipe CMP 24" End Section	EA	4
11	Inlet, Area 4'x4'	EA	2
12	MH, Adj. w/New Ring & Cover	EA	1
13	Temporary Project Construction Sign	EA	1
14	Permanent Informational Sign	EA	2
15	Contractor Construction Staking	LS	1
16	Concrete Pavement (8") (Reinforced)	SY	270
17	Reinforced Crushed Rock Base (6")	SY	270
18	Lower WL Pipe 12"	LF	60
Bank Stabilization			
19	Rip-Rap, Heavy Stone	CY	8,241
20	Project Seeding	AC	3.4
21	Hydraulic Mulching	AC	3.4
Erosion Control			
22	Silt Fence	LF	8,495
23	Erosion Control Mat	SY	10,207
24	Temporary Construction Entrance and Stream Crossing	EA	3
25	Temporary Slope Drain	LF	212
26	Temporary Berm	LF	2,650
27	Temporary Seeding	AC	3.4



CITY OF
 WICHITA, KANSAS



NO.	DATE	BY	APPRO	REVISIONS
4				
3				
2				
1				

**GYPSUM CREEK BANK STABILIZATION
 QUANTITIES**