

CONCRETE SIDEWALK 4" & 5" (20401004) & (20401005)				
STATION	STREET	SIDE	THICKNESS	AREA S.F.
7+15.36	21st Street	LT	5"	119.10
16+74.88	21st Street	LT	5"	94.04
16+74.88	21st Street	LT	5"	152.54
17+05.74	21st Street	RT	4"	46.63
17+05.74	21st Street	RT	4"	47.44
17+24.87	21st Street	LT	5"	93.96
19+39.10	21st Street	LT	5"	414.97
21+00.00	21st Street	RT	4"	1243.58
23+00.00	21st Street	RT	4"	763.95
23+01.43	21st Street	LT	5"	107.00
23+01.43	21st Street	LT	5"	105.69
25+00.00	21st Street	RT	4"	1094.82
27+00.00	21st Street	RT	4"	955.47
28+50.00	21st Street	RT	4"	578.33
30+00.00	21st Street	RT	4"	736.46
33+00.00	21st Street	RT	4"	2372.77
36+00.00	21st Street	RT	4"	933.40
45+42.64	Maize Road	RT	4"	73.84
45+42.64	Maize Road	RT	4"	1278.58
45+73.05	Maize Road	LT	4"	154.07
46+23.71	Maize Road	RT	4"	257.42
47+00.00	Maize Road	LT	4"	1016.41
48+50.00	Maize Road	LT	4"	910.25
51+00.00	Maize Road	LT	4"	60.08
52+00.00	Maize Road	RT	4"	1637.81
53+09.57	Maize Road	LT	4"	64.68
53+09.57	Maize Road	LT	4"	489.52
53+19.60	Maize Road	RT	4"	384.50
Total 4"				14099.60
Total 5"				1087.30

CONCRETE PROTECTION CURB (20405000)		
STREET	LOCATION	LENGTH L.F.
21st and Maize	SW Corner	20
Total		20

CONCRETE FLUME (50121000)			
STREET	STATION	SIDE	LENGTH L.F.
21st Street	30+50.00	Lt	15
21st Street	32+45.00	Rt	25
Total			40

MANHOLES ADJUSTED					
STREET	STATION	OFFSET	TYPE	EX ELEV	PROP ELEV
21st Street	17+94	25' LT	SWS	1349.53	1349.47
21st Street	17+98	51' RT	SWS	1349.62	1349.42
Maize Road	48+00	45' LT	A1&T	1351.81	1352.40
Maize Road	52+55	50' RT	SWS	1351.36	1351.78
Maize Road	54+09	47' RT	SWS	1352.01	1351.88

WATER VALVES ADJUSTED					
NUMBER	STREET	STA.	OFFSET	EX ELEV	PROP ELEV
27640	21st STREET	8+35	42' RT	?	As Rqd.
27644	21st STREET	8+83	43' RT	?	As Rqd.
27641	21st STREET	9+54	46' RT	1352.03	As Rqd.
72178	21st STREET	9+60	46' RT	1352.00	As Rqd.
27645	21st STREET	17+12	75' RT	1350.26	As Rqd.
27642	21st STREET	19+19	73' RT	1351.63	1351.20
27646	21st STREET	19+29	78' RT	1351.10	1351.40
29188	21st STREET	19+32	73' RT	1350.56	1350.60
29189	21st STREET	20+76	79' RT	1351.09	1351.33
29190	21st STREET	20+80	82' RT	1351.24	1351.50
29193	Maize Road	50+57	76' RT	1350.90	1351.20
29194	Maize Road	53+58	59' RT	1352.67	1352.10

NOTE:  
 For Sodding Quantities, see Sodding Plan  
 For Erosion Control BMP Quantities, See Erosion Control Plan  
 For Pavement Marking Quantities, See Marking & Signing Plan  
 For Signing Quantities, See Sign Detail Sheet

CONCRETE PAVEMENT 9" (Reinforced) (20373009)				
STREET	STATION	LOCATION	DESCRIPTION	AREA S. Y.
21st Street	18+98.19 - 21+12.46	Intersection	-	3737.72
Maize Road	48+83.19 - 50+89.92	Intersection	-	-
21st and Maize	-	NW Corner	APRON	13.10
21st and Maize	-	SW Corner	APRON	16.89
21st and Maize	-	NE Corner	APRON	8.22
21st and Maize	-	SE Corner	APRON	34.15
Total				3810.08

CONCRETE PAVEMENT 9" (NRDJ) (20372009)		
STREET	STATION	AREA S. Y.
21st Street	16+50.00 - 18+98.19	2708.33
21st Street	21+12.46 - 23+39.80	2462.79
Maize Road	47+34.89 - 48+83.19	1628.81
Maize Road	50+89.92 - 53+50.00	2817.32
Total		9617.25

CRUSHED ROCK BASE 8" REINFORCED (20431008)		
STREET	STATION	AREA S. Y.
21st Street	8+00.00 - 16+50.00	8424.57
21st Street	23+39.80 - 31+00.00	7684.51
Maize Road	43+50.00 - 47+34.89	3183.36
Maize Road	53+50.00 - 55+00.00	1581.14
Total		20873.58

CRUSHED ROCK BASE 6" REINFORCED (20431006)		
STREET	STATION	AREA S. Y.
21st Street	16+50.00 - 23+39.80	9415.20
Maize Road	47+34.89 - 48+85.24	1745.94
Maize Road	53+50.00 - 55+00.00	3019.59
Total		14180.73

CONCRETE C&G, COMB. TYPE 1 (6" & 1-1/2") (20323000)			
STREET	STATION	SIDE	LENGTH Ft.
21st Street	14+50.00 - 19+11.08	Left	461.10
21st Street	14+50.00 - 18+96.13	Right	446.28
21st Street	-	NW Radius	77.47
21st Street	-	SW Radius	79.65
21st Street	-	NE Radius	79.65
21st Street	-	SE Radius	80.48
21st Street	21+12.46 - 25+00.00	Left	387.58
21st Street	20+97.93 - 25+00.00	Right	402.23
21st Street	28+50.00 - 31+00.00	Left	249.39
Maize Road	45+00.00 - 48+83.19	Left	384.64
Maize Road	45+00.00 - 48+88.44	Right	386.59
Maize Road	50+85.28 - 55+00.00	Left	414.56
Maize Road	50+89.92 - 55+00.00	Right	411.31
Total			3861.17

CONCRETE C & G, COMB. TYPE 3 (8" & 1-1/2")(20326000)			
STREET	STATION	HEIGHT	LENGTH Ft.
21st Street	8+00.00 - 16+50.00	8"	208.56
21st Street	20+98.45 - 21+65.66	8"	134.42
21st Street	21+71.66 - 23+39.80	1 1/2"	324.28
Maize Road	43+50.00 - 47+34.89	8"	153.54
Maize Road	53+50.00 - 55+00.00	8"	623.92
Total			1444.72

CONCRETE C&G REMOVED AND REPLACED (20322000)			
STREET	STATION	SIDE	LENGTH L.F.
21st Street	17+24.87	Left	30
Maize Road	53+14.76	Right	48
Total			78.0

CONCRETE DRIVEWAY 8" (REINFORCED) (20344008)				
STREET	STATION	SIDE	WIDTH	AREA S.F.
21st Street	7+15.36	LT	PARTIAL	523.32
21st Street	14+53.25	LT	PARTIAL	314.65
21st Street	15+33.87	RT	36'	1367.72
21st Street	16+74.88	LT	32'	839.23
21st Street	17+05.74	RT	25'	798.27
21st Street	17+24.87	LT	36'	923.47
21st Street	22+04.78	RT	30'	1054.35
21st Street	23+01.43	LT	31'	847.36
21st Street	23+74.02	RT	30'	947.35
Maize Road	45+42.64	RT	24'	1066.96
Maize Road	45+73.05	LT	27'	985.41
Maize Road	46+23.71	RT	47'	1352.23
Maize Road	47+68.55	LT	24'	735.45
Maize Road	53+09.57	LT	31'	732.16
Maize Road	53+14.76	RT	41'	1679.35
Total				14167.28

BRICK PAVERS (CONCRETE), MEDIAN (20267000)		
STREET	STATION	AREA S.Y.
21st Street	18+06.00 - 19+10.28	46.34
21st Street	20+98.45 - 21+65.66	37.32
Maize Road	48+06.00 - 48+80.04	32.84
Maize Road	50+81.81 - 53+93.33	141.52
Total		258.02

BRICK PAVERS (CONCRETE), CROSSWALK (20266000)		
STREET	STATION	AREA S.Y.
21st Street	19+30	121.55
21st Street	20+81	122.05
21st Street	21+71.66 - 23+39.80	90.06
Maize Road	49+00	112.01
Maize Road	50+62	121.82
Total		567.49

BRICK PAVERS SALVAGED AND REPLACED (20270000)			
STREET	STATION	SIDE	AREA S.Y.
Maize Road	53+14.76	Right	8.17
Total			8.17

AC PAVEMENT 7" (5" BIT BASE)(BM-2, PG 70-28)(20158007)		
STREET	STATION	AREA S. Y.
21st Street	8+00.00 - 16+50.00	8261.06
21st Street	23+39.80 - 31+00.00	7349.54
Maize Road	43+50.00 - 47+34.89	2999.33
Maize Road	53+50.00 - 55+00.00	1463.01
Total		20072.94

AC PAVEMENT 6" (4" BIT BASE) (PARKING LOT) (20151006)			
STREET	STATION	SIDE	AREA S.Y.
21st Street	7+15.36	Left	1.63
21st Street	17+24.87	Left	54.10
Maize Road	53+14.76	Right	15.23
Total			70.96

CONCRETE CURB, MONO EDGE (6" & 1-1/2") (20328000)			
STREET	STATION	SIDE	LENGTH L.F.
Maize Road	53+14.76	Right	35.31
Total			35.31