



EROSION CONTROL PLAN LEGEND
(Installation Details Found in the SWP2 Plan)

	- DROP INLET PROTECTION
	- CURB INLET PROTECTION
	- DITCH CHECKS
	- SILT FENCING
	- CUT-OFF TRENCH
	- BACK OF CURB PROTECTION
	- EROSION CONTROL MAT
	- TEMPORARY DITCH
	- RIP RAP

NO SCALE

EROSION CONTROL MEASURE	QUANTITY
BACK OF CURB PROTECTION (LF)	1,795
CONSTRUCTION ENTRANCE (EA)	0
CURB INLET BARRIER (EA)	2
DITCH CHECK (EA)	0
DROP INLET PROTECTION (EA)	0
EROSION CONTROL BERM (LF)	0
SILT FENCE (LF)	0
EROSION CONTROL MAT (SY)	0
RIP-RAP (SY)	29

QUANTITIES ARE FOR INFORMATION ONLY! CONTRACTOR SHALL VERIFY QUANTITIES PER FINAL BID QUANTITY SHEET.

ALL BMPs INCLUDING CONSTRUCTION ENTRANCE, DITCH CHECKS, SILT FENCE, INLET PROTECTION AND BACK OF CURB PROTECTION SHALL BE MAINTAINED AND REPAIRED IF NECESSARY.

	36TH STREET NORTH	
	EROSION CONTROL PLAN	
PAVING PLANS		
<small>Baughman Company, P.A. 315 Ellis St. Wichita, KS 67211 P 316-262-7271 F 316-262-0149 ENGINEERING SURVEYING PLANNING LANDSCAPE ARCHITECTURE</small>		
PROJECT NUMBER 472-84992	DESIGN KEK	DRAWN TMS
APPROVED JFB	DATE 01/12	
REVISIONS:	SCALE Noted	SHEET
		16 OF 24