


RECAPITULATION OF QUANTITIES		
ITEM	QUANTITY	UNIT
LUMP SUM BID ITEMS - PAVING (707022)		
Mobilization	1	LS
Mobilization (DBE)	1	LS
Field Office & Laboratory (Type A)	1	ea
Site Clearing	1	LS
Removal of Existing Structures	1	LS
Concrete &/or Asphalt Pavement Removed	6183	sy
Concrete Sidewalk Removed	19	sy
Excavation	5926	cy
Excavation, Borrow (Contractor Furnished)	1060	cy
Fill, Compacted (95% Density)	5678	cy
AC Pavement 7" (5" Bit Base) (BM-2)	8479	sy
Crushed Rock Base 8", Reinforced	10133	sy
Concrete C&G, Comb Type I (6" & 1-1/2")	4251	lf
Wheelchair Ramp w/Detectable Warnings	1	ea
Signing	1	LS
Pavement Marking	1	LS
Traffic Control	1	LS
LUMP SUM BID ITEMS - DRAINAGE (707022)		
Inlet, Curb (Type I) (L=5' W=3')	4	ea
Inlet, Curb (Type I) (L=10' W=3')	13	ea
Inlet, Curb (Type I) (L=10' W=4')	2	ea
Inlet Hookup	19	ea
MH, Reinforced Concrete (4' x 4')	2	ea
Pipe, PVC 4", Perforated (Inlet Underdrain)	209	lf
Pipe, SWS 15"	400	lf
Pipe, SWS 15" (RCP)	781	lf
Pipe, SWS 18"	375	lf
Pipe, SWS 18" (RCP)	44	lf
Pipe, SWS 24" (RCP)	87	lf
Pipe, SWS 30" (RCP)	53	lf
Pipe, Entrance 15"	72	lf
Pipe, 15' End Section	4	ea
Pipe, RCBC (2-10' x 6') w/ Wingwalls (Sta. 220+25)	106	lf
Handrail (Steel), Pedestrian (3'-6") (Sta. 220+25)	104	lf
Pipe, RCBC (4' x 3') w/ Wingwalls (Sta. 226+05)	91	lf
Handrail (Steel), Pedestrian (3'-6") (Sta. 226+05)	49	lf
Fill, Sand (Flushed & Vibrated)	1161	lf
LUMP SUM BID ITEMS - LANDSCAPE (707022)		
Seeding	1	LS
Sodding, Fescue	1	LS
MEASURED QUANTITY BID ITEMS - PAVING (707022)		
Concrete Sidewalk 4"	12866	sf
Concrete Sidewalk 5"	22098	sf
Concrete Sidewalk Protection Curb	70	lf
Concrete Driveway 8" (Reinforced)	5546	sf
Surfacing Material 2" (SA-1) (Driveway)	1300	sf
AC Pvmf 6" (4" Bit Base), Temp for Widening (w/5" Crushed Rock Base)	354	sy
AC Pvmf 6", Temp for Patching	117	sy
Riprap, Light Stone	393	sy
Sign, Electronic Portable Message	50	day
MEASURED QUANTITY BID ITEMS - LANDSCAPE (707022)		
Tree, Japanese Tree Lilac - 2.5" caliper	12	ea
Tree, Oklahoma Redbud - 2.5" caliper	14	ea
Tree, Professor Sprenger Crabapple - 2.5" caliper	20	ea
Tree, Zumi Crabapple - 2.5" caliper	16	ea
Tree, Goldenraintree - 2.5" caliper	7	ea
Tree, Hedge Maple - 2.5" caliper	7	ea
Tree, Chinquapin Oak - 3" caliper	13	ea
MEASURED QUANTITY BID ITEMS - BMP's (707022)		
BMP, Curb Inlet Protection	19	ea
BMP, Silt Fence	4250	lf
BMP, Construction Entrance	2	ea
BMP, Back of Curb protection	4081	lf
WATERLINE IMPROVEMENTS - NON-PARTICIPATING		
MEASURED QUANTITY BID ITEMS (635813)		
Pipe, WL 16"	1778	lf
Pipe, DICL RJ 16"	113	lf
Pipe, DICL SJ 16"	48	lf
Valve Assembly, Anchored, 16" (Tied)	2	ea
Fire Hydrant Assembly	4	ea
Fill, Sand (Flushed & Vibrated)	82	lf
Conc. Pvmf. Rem. - Asph. Repl.	30	lf
Concrete Driveway Removed & Replaced	30	lf
Gravel Streets/Drives Removed & Replaced	41	lf
BMP, Silt Fence	346	lf

See Sh. No. 52 for Summary of Pavement Markings.
 See Sh. No. 53 for Sign Assembly Tables.
 See Sh. No. 62 for List of Traffic Control Devices.

No.	Revision	By	Date
135TH ST.			
RECAP OF QUANTITIES			
GARY JANZEN, P.E.-CITY ENGINEER CITY OF WICHITA PROJECT NO. 472-84915			
		PROFESSIONAL ENGINEERING CONSULTANTS, P.A. 303 SOUTH TOPEKA WICHITA, KS 67202 316-262-2691 www.pec1.com	
Designed by	RJS	Job No.	10281
Drawn by	JDT	Date	JAN., 2013
			Sht. 43 of 83