SUMMARY OF QUANTITIES

REMOVAL AND RESETTING OF SIGNS ON PROJECT

	EXISTING PLAN STATION NUMBER	NEW PLAN STATION NUMBER	SIGN TYPE	SIGN SIZE
	K-96 (E. Bd. & W. Bd.)			
	964+74 L	464+74 L	M1-5	24" x 24"
			D10-6	12" x 48"
	464+74 R	464+74 R	M1-5	24" x 24"
			D10-6	12" x 48"
	467+00 L	477+00 L	R2-1	4'-0" x 5'-0"
	471+33 M	471+45 M	E8-1	13'-6" x 8'-6"
	475+39 R	475+39 R	D10-9	18" x 48"
	475+49 L	475+49 L	D10-9	18" x 48"
	477+90 L	485+00 L	M3-4	24" x 12"
			M1-5	24" x 24"
	603+00 M	603+12 M	E8-1	11'-6" x 7'-0"
	RAMP W-NS			
	460+00 R	457+00 R	D3-2	11'-6" x 2'-0"
	460+00 R	460+85 R	R5-1a	36" x 24"
	460+97 L	460+00 L	R5-1a	36" x 24"
*	464+06 R	464+00 R	R5-1	30" x 30"

	EXISTING PLAN STATION NUMBER	NEW PLAN STATION NUMBER	SIGN TYPE	SIGN SIZE
	GREENWICH RD. (N. Bd. & S. Bd.)			
	115+81 R	110+50 R	M2-1	21" x 15"
			M1-5	24" x 24"
*	118+44 M	117+97 M	R4-7	24" x 30"
*			0M1-3	18" x 18"
*	119+18 M	119+70 M	R4-7	24" x 30"
*			0M1-3	18" x 18"
*	120+76 R	120+25 R	R2-1	24" x 30"
	129+62 R	128+85 R	M3-4	24" x 12"
			M1-5	24" x 24"
			M6-1L	21" x 15"
	131+55 L	133+00 L	M3-4	24" x 12"
			M1-5	24" x 24"
			M6-1R	21" x 15"
*	133+22 R	133+22 R	W6-3	36" x 36"
*			R5-1	30" x 30"
*	133+25 M	133+25 M	R4-7	24" x 30"
*			0M1-3	18" x 18"
	133+26 L	134+00 L	D1-2	9'-0" x 2'-0"
*	135+14 R	137+00 R	R3-9B	24" x 36"
	137+00 L	137+00 L	M2-1	21" x 15"
			M1-5	24" x 24"
	26TH ST.			
*	49+64 L	49+64 L	D3	36" x 9"
*			D3	36" x 9"
*	49+48 R	49+47 R	R1-1	30" x 30"

EXISTING PLAN STATION NUMBER	NEW PLAN STATION NUMBER	SIGN TYPE	SIGN SIZE

EXISTING PLAN STATION NUMBER	NEW PLAN STATION NUMBER	SIGN TYPE	SIGN SIZE

* Quantity included in Lump Sum Bid item "Signing (COW)."

Drawn By : cp Plotted : 31-DEC-2013 09:59
File : I:\2009\09521\Standards\09521-TE445.dgn

NO.	DATE	REVISIONS	BY	APP'D

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES FOR REMOVAL AND RESETTING OF SIGNS

~~TE445~~ 7/1/03

FHWA APPROVAL 7/22/2003	APP'D Steven A. Buckley		
DESIGNED D.D.G.	DETAILED K.D.S.	QUANTITIES	TRACED
DESIGN CK. S.A.B.	DETAIL CK. D.D.G.	QUAN. CK.	TRACE CK.