



Douglas Ave.

1525 E. Douglas

1601 E. Douglas

Hydraulic Ave.

Greenwood Ave

MH (no number)  
Abandon Manhole (in pavement)  
  
(manhole is brick and has unsealed 6" pipes  
in & out that are not in use)  
(current pavement is 1/2 brick and 1/2  
concrete / patch with concrete)  
Estimated MH depth = 4.0 ft +-

MH 5547-409  
Replace Manhole Frame  
& Cover (in pavement)  
(in concrete approach)  
Approx MH depth =10.0 ft

21" VCP/CIPP  
  
MH 5547-413  
Abandon Manhole (over CIPP)  
(in pavement) (AC pavement)  
Approx MH depth =10.0 ft  
(est depth over CIPP is 8.6 ft)  
(any structural reinforcement  
over the CIPP shall be  
subsidiary to the abandonment)

No visible structure.  
21" pipe is capped here

Pavement removal and replacement for all  
three manholes on this Site shall be  
subsidiary to the manhole work.

21" VCP

36" SS

27" SS

**SITE 6**



