



GENERAL NOTES

- Mortar used in masonry construction shall contain 8 sacks of cement per cubic yard. Concrete used in manhole bases shall conform to the requirements of concrete for concrete pavement construction as specified in the city standard paving specifications using city concrete cement mix without air entraining admixture. Mortar shall be placed around the manhole rings as shown on the drawings when manholes are constructed in public street pavement. Manholes are located within public street pavement. Manholes constructed where pipe sizes are smaller than 24" shall have an inside diameter of 4". Manholes constructed where pipe sizes are 24" or larger shall have an inside diameter of 5". Completed manhole shall be without leaks and water tight.
- Reinforcing steel shall be installed in the manhole bases and shall consist of no. 4 bars placed on 6" centers in both directions. The manhole base reinforcement shall be placed 6" above the bottom of the manhole base. All costs for furnishing and installing reinforcing steel shall be included in the unit price bid for the manhole.
- The floors of all manholes shall be shaped with flow channels such that the manholes will be self cleaning and free of areas where solids could be deposited as sewage flows through the manhole from all inlet pipes to the outlet pipe. Flow channels shall be formed to match the bottom halves of the inflowing pipes and the outflowing pipe as shown by the drawings. Manhole floors shall have slopes of 3 inches per foot in the areas outside of the flow channels sloped toward the flow channels. Pipes laid through manholes shall have the top half removed to neat lines for the full inside diameter of the manhole. Manhole floors shall then be shaped around the bottom half of the pipe which forms the flow channel.
- Pipes installed within the excavation made for the manhole shall be cradled with concrete to the limits of the manhole excavation. When clay pipe is used, the cradle shall extend to the first joint outside the manhole. The cradle shall be terminated at the pipe joint in a manner which will maintain the flexibility of the joint. Cost of cradle within manhole excavation or to clay pipe joints adjacent to manhole shall be included in the unit price bid for the manhole.
- Manhole cover castings and manhole frame castings shall conform to the requirements as indicated in the standard specifications and as shown in the standard detail drawings.
- The crowns of inflowing pipes shall never be set lower than the crown of the outflowing pipe.
- Standard shallow manholes Type "A" and "B" shall be paid for at the unit price bid per each for the type and diameter indicated. "Standard special shallow manholes Type "A" and "B" shall be paid for at the unit price bid per each for the type indicated. All standard shallow manhole diameters will be 4' unless indicated otherwise.
- All brick used in manhole construction shall meet Grade SW of ASTM C652 or C62-87.




PLAN




SECTION A-A


FLAT CONCRETE SLAB DETAILS




SHALLOW TYPE "B" MANHOLE




SHALLOW TYPE "A" MANHOLE




MASONRY COLLAR DETAIL



SPECIAL SHALLOW TYPE "B" MANHOLE



SPECIAL SHALLOW TYPE "A" MANHOLE



STANDARD/SPECIAL SHALLOW MANHOLES TYPE 'A' & 'B'

PROJECT NUMBER	INDEX CODE
468-83709	744043
DATE	SHEET 3 OF 9
MAR 96	

JIM ARMOUR, P.E.—ACTING CITY ENGINEER
 CITY ENGINEERS, OFFICE
 405 NORTH MAIN STREET
 WICHITA, KANSAS 67201
 (316) 262-4201
 (316) 262-4174 FAX

REV. 1/05/01, MCG

Special Shallow MH Type A & B.DWG

H:\CWL\03120\DWG\SMN\03120B02