



Remove Ex. 24" Stopbar.
connect existing broken 6"
White and Double 4"
solid/Broken Yellow.

Remove Ex. Traffic
Manhole and salvage to
the City of Wichita.

Remove WCR and
construct 10 L.F. Type 1
Curb.

Relocate Ex Signal Pole to
Sta. 189+57.46, 35.80' Lt.

Remove, Clean, and
Palate, Ex. Brick Pavers,
and deliver to the City of
Wichita. Replace with 565
S.F. Asphalt Pavement.

Relocate Ex Signal Pole to
Sta. 189+67.76, 37.57' Rt.

Remove WCR and 37.5 S.F.
4" Sidewalk Pavement.
Construct 10 L.F. Type 1
Curb

Remove Ex. Traffic
Manhole and salvage to
the City of Wichita.
abandon ex. Conduit in
place.

Drawing File: E:\Projects\South Meridian YMCA Signalization\Bae		Project No. 1406-E084 CAPITAL IMPROVEMENT PROJECT	
Design: AZIERE	Drawn: AZIERE	South Meridian YMCA Signalization Relocation Plan	
Approved: AZIERE	Scale: NONE		

Baughman Company, P.A.
315 Ellis St. Wichita, KS 67211 P 316-262-7271 F 316-262-0149
ENGINEERING | SURVEYING | PLANNING | LANDSCAPE ARCHITECTURE