

ANDREA

STATION	AREAS		VOLUMES		CUMULATIVE VOLUMES	
	Square Feet		Cubic Yards		Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
8+52.06	48.27	1.87				
9+19.39	35.24	4.47	104.13	7.91	104.13	7.91
9+38.89	38.20	0.00	26.52	1.62	130.65	9.53
9+53.39	33.54	0.00	19.26	0.00	149.91	9.53
9+67.89	42.15	0.00	20.32	0.00	170.23	9.53
9+87.39	51.33	0.00	33.76	0.00	203.99	9.53
10+00	58.08	0.00	25.55	0.00	229.54	9.53
10+50	48.13	0.00	98.34	0.00	327.88	9.53
11+00	33.92	3.79	75.97	3.51	403.85	13.04
11+02.39	33.57	4.09	2.99	0.35	406.84	13.39
			0.00	0.00	406.84	13.39

ANDREA CT. (NE)

STATION	AREAS		VOLUMES		CUMULATIVE VOLUMES	
	Square Feet		Cubic Yards		Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
0+34	44.38	0.00				
0+50	42.83	0.00	25.84	0.00	25.84	0.00
1+00	41.70	0.00	78.26	0.00	104.10	0.00
1+14.95	39.38	0.06	22.45	0.02	126.55	0.02
1+50	79.25	0.00	77.00	0.04	203.54	0.06
1+64.94	87.10	0.00	46.02	0.00	249.57	0.06
2+00.44	21.00	0.00	71.06	0.00	320.63	0.06
2+14.94	20.53	0.00	11.15	0.00	331.78	0.06
			0.00	0.00	331.78	0.06

ANDREA CT.

STATION	AREAS		VOLUMES		CUMULATIVE VOLUMES	
	Square Feet		Cubic Yards		Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
0+34	39.27	0.00				
0+50	37.31	1.86	22.69	0.55	22.69	0.55
1+00	38.48	3.39	70.17	4.86	92.86	5.41
1+50	39.96	0.04	72.63	3.17	165.49	8.58
2+00	36.43	3.49	70.73	3.26	236.22	11.84
2+65.42	33.23	2.30	84.38	7.02	320.60	18.85
2+84.92	47.34	1.47	29.09	1.36	349.69	20.22
2+99.42	42.68	0.99	24.17	0.66	373.86	20.88
3+13.92	48.48	0.53	24.48	0.41	398.34	21.29
3+33.42	37.04	0.11	30.88	0.23	429.23	21.52
3+50	37.98	0.00	23.03	0.04	452.26	21.56
4+00	40.81	0.00	72.95	0.00	525.21	21.56
4+48.40	41.05	0.05	73.47	0.04	598.68	21.60
			0.00	0.00	598.68	21.60


TARA FALLS CT.

STATION	AREAS		VOLUMES		CUMULATIVE VOLUMES	
	Square Feet		Cubic Yards		Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
0+37	39.23	0.00				
0+50	38.79	0.00	18.78	0.00	18.78	0.00
1+00	38.02	0.00	71.13	0.00	89.91	0.00
1+50	33.84	0.00	66.44	0.00	156.35	0.00
2+00	31.70	1.52	60.68	1.40	217.04	1.40
2+50	27.03	4.60	54.38	5.67	271.42	7.07
3+00	23.04	1.97	46.36	6.08	317.78	13.15
3+50	42.64	0.00	60.82	1.82	378.59	14.98
4+00	40.37	0.00	76.86	0.00	455.46	14.98
4+23.22	39.66	0.00	34.41	0.00	489.87	14.98
4+50	53.71	3.68	46.30	1.82	536.17	16.80
4+73.21	59.98	6.05	48.86	4.18	585.03	20.99
5+08.71	2.00	18.12	40.74	15.89	625.78	36.88
5+23.21	2.26	4.36	1.14	6.03	626.92	42.91
			0.00	0.00	626.92	42.91

ANDREA CT. (NORTH)

STATION	AREAS		VOLUMES		CUMULATIVE VOLUMES	
	Square Feet		Cubic Yards		Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
0+34	39.28	0.00				
0+50	38.00	0.45	22.90	0.13	22.90	0.13
1+00	37.76	0.21	70.15	0.62	93.05	0.75
1+50	44.18	0.00	75.86	0.20	168.91	0.95
2+00	38.24	0.46	76.32	0.43	245.23	1.38
2+50	41.26	0.04	73.61	0.47	318.84	1.85
3+00	40.36	0.31	75.57	0.33	394.41	2.18
3+25	46.11	0.28	40.03	0.27	434.44	2.45
3+50	70.80	13.74	54.12	6.49	488.56	8.94
3+72	70.56	12.09	57.59	10.52	546.15	19.46
4+07.50	13.58	4.89	55.31	11.16	601.46	30.63
4+22	6.51	1.45	5.39	1.70	606.86	32.33
			0.00	0.00	606.86	32.33

TOTAL CUT: 2571 C.Y.
110 C.Y.

Tara Falls Addition, Paving Improvements Earthwork Tables WICHITA, KANSAS			
	Ruggles & Bohm, P.A. Engineering, Surveying, Land Planning		DESIGN KWL DRAWN TEB REVIEW UTILITY
	924 North Main Wichita, Kansas 67203 www.rbkansas.com		(316) 264-8008 (316) 264-4621 fax E-mail: info@rbkansas.com
DRAWING FILE EARTHWORK TABLES	PROJECT NUMBER 472-83848	DATE Oct. 23, 2003	SHEET 31 of 32