

Auburn Hills									
Alignment:	1								
	Cumulative Totals								
Station	Cut (sqft)	L.F. (sqft)	C.F. (sqft)	Cut (cu. yds)	L.F. (cu. yds)	C.F. (cu. yds)	Cut	L.F.	C.F.
0+50	0	255.27	46.55						
1+00	0	201.93	46.55	0	423.33	86.20	0	423.33	86.20
1+03.43	0	196.2	48.55	0	25.29	6.04	0	448.62	92.24
1+28.43	0	177.6	46.56	0	173.06	44.03	0	621.68	136.28
1+50	0	113.39	23.28	0	116.23	27.90	0	737.91	164.17
1+75.43	0	54.13	23.27	0	78.89	21.92	0	816.80	186.10
2+00	5.21	14.23	23.28	2.37	31.10	21.18	2.37	847.91	207.28
2+22.43	10.43	0	24.4	6.5	5.91	19.80	8.87	853.82	227.08
2+50	24.44	0	12.8	17.81	0.00	18.99	26.67	853.82	246.07
3+00	54.57	0	11.74	73.16	0.00	22.72	99.83	853.82	268.80
3+29.07	65.33	0	11.31	64.55	0.00	12.41	164.38	853.82	281.20
3+50	54.47	0	7.41	46.44	0.00	7.26	210.82	853.82	288.46
4+00	18.71	0	26.53	67.76	0.00	31.43	278.58	853.82	319.89
4+50	25.74	0	17.78	41.16	0.00	41.03	319.74	853.82	360.91
4+75.49	21.87	0	20.22	22.47	0.00	17.94	342.21	853.82	378.85
5+00	40.17	0	25.18	28.16	0.00	20.61	370.37	853.82	399.46
5+19.26	34.18	19.18	23.28	26.52	6.84	17.28	396.89	860.66	416.74
5+50	29.36	47.79	23.27	36.17	38.12	26.50	433.05	898.78	443.24
6+00	2.5	54.36	29.96	29.5	94.58	49.29	462.56	993.36	492.53
6+50	1.66	61.67	31.89	3.86	107.44	57.27	466.41	1100.80	549.80
7+00	7.78	27.66	24.26	8.74	82.71	51.99	475.15	1183.51	601.79
7+31.02	35.61	0	17.64	24.92	15.89	24.07	500.08	1199.40	625.86
7+50	64.44	0	5.35	35.16	0.00	8.08	535.24	1199.40	633.94
8+00	159.09	0	0	206.97	0.00	4.95	742.21	1199.40	638.89
8+50	257.9	0	0	386.11	0.00	0.00	1128.32	1199.40	638.89
8+58.37	272.42	0	0	82.19	0.00	0.00	1210.52	1199.40	638.89
9+00	257.1	0	0	408.23	0.00	0.00	1618.74	1199.40	638.89
9+50	187.54	0	0	411.7	0.00	0.00	2030.44	1199.40	638.89
9+78.37	147.37	0	0	175.95	0.00	0.00	2206.39	1199.40	638.89
10+00	125.91	0	0	109.47	0.00	0.00	2315.86	1199.40	638.89
10+27.93	107.49	0	0	120.7	0.00	0.00	2436.56	1199.40	638.89
10+50	100.61	0	0	85.07	0.00	0.00	2521.62	1199.40	638.89
				173.92	0.00	5.70	2695.55	1199.40	644.59

Monterey									
Alignment:	2								
	Cumulative Totals								
Station	Cut (sqft)	L.F. (sqft)	C.F. (sqft)	Cut (cu. yds)	L.F. (cu. yds)	C.F. (cu. yds)	Cut	L.F.	C.F.
0+00	90.42	0	0						
0+50	32.96	0	12.7	114.23	0.00	11.75926	114.23	0.00	11.76
1+00	3.66	0	35.94	33.9	0.00	45.03704	148.13	0.00	56.80
1+09.33	1.16	0	43.27	0.83	0.00	13.68573	148.97	0.00	70.48
1+50	0	54.83	46.46	0.88	41.30	67.57998	149.84	41.30	138.06
2+00	0	82.76	46.55	0	127.40	86.12037	149.84	168.69	224.18
2+31.17	1.77	0	44.64	1.02	47.77	52.63689	150.87	216.46	276.82
2+50	20.18	0	22.4	7.65	0.00	23.3771	158.52	216.46	300.20
3+00	13.78	0	26.86	31.44	0.00	45.61111	189.96	216.46	345.81
3+50	4.62	23.9	32.6	17.04	22.13	55.05556	207	238.59	400.86
3+84.59	0.92	44.2	36.63	3.55	43.62	44.34566	210.55	282.22	445.21
4+00	0.06	58.29	39.77	0.28	29.25	21.8023	210.83	311.46	467.01
4+50	0.28	47.37	40.18	0.32	97.83	74.02778	211.15	409.30	541.04
4+94.30	0	73.41	46.56	0.23	99.08	71.15893	211.38	508.38	612.20
5+00	0	92.02	46.55	0	17.46	9.828278	211.38	525.84	622.03
5+50	0	206.75	46.56	0	276.64	86.21296	211.38	802.48	708.24
5+64.29	0	172.21	46.56	0	100.28	24.64231	211.38	902.77	732.88
6+00	0	115.24	46.72	0	190.09	61.68572	211.38	1092.86	794.57
6+50	3.12	60.5	35.04	2.89	162.72	75.7037	214.28	1255.58	870.27
6+72.15	4.77	57.45	32.51	3.24	48.38	27.70801	217.51	1303.96	897.98
					0.00			1303.96	897.98

Ocala									
Alignment:	3								
	Cumulative Totals								
Station	Cut (sqft)	L.F. (sqft)	C.F. (sqft)	Cut (cu. yds)	L.F. (cu. yds)	C.F. (cu. yds)	Cut	L.F.	C.F.
0+00	0	36.87	43.57						
0+50	4.28	0	36.32	3.96	34.14	73.97	3.96	34.14	73.97
0+84.53	16.12	0	25.19	13.04	0.00	39.33	17	34.14	113.30
1+00	27	0	17.76	12.36	0.00	12.30	29.36	34.14	125.61
1+50	62.73	0	0.16	83.08	0.00	16.59	112.44	34.14	142.20
2+00	101.64	0	0	152.19	0.00	0.15	264.63	34.14	142.35
2+50	124.27	0	0	209.17	0.00	0.00	473.81	34.14	142.35
2+64.37	129.89	0	0	67.63	0.00	0.00	541.44	34.14	142.35
2+80.38	126.35	0	0	75.99	0.00	0.00	617.43	34.14	142.35
3+00	132.91	0	0	94.18	0.00	0.00	711.61	34.14	142.35
3+50	120.61	0	0	234.75	0.00	0.00	946.36	34.14	142.35
3+86.50	84.41	0	1.21	138.58	0.00	0.82	1084.94	34.14	143.17

Auburn Hills Ct.									
Alignment:	4								
	Cumulative Totals								
Station	Cut (sqft)	L.F. (sqft)	C.F. (sqft)	Cut (cu. yds)	L.F. (cu. yds)	C.F. (cu. yds)	Cut	L.F.	C.F.
30	0	54.65	43.41						
15	0	132.82	47.64	0	52.08	25.29	0	52.08	25.29
0+00	0	170.15	50.4	0	84.16	27.23	0	136.23	52.53
0+15	0	141.79	51.08	0	86.65	28.19	0	222.88	80.71
0+30	0	89.81	54.1	0	64.33	29.22	0	287.22	109.93
0+46.86	0	71.45	46.55	0	50.35	31.43	0	337.57	141.36
0+50	0	69.02	46.56	0	8.17	5.41	0	345.73	146.77
1+00	0	45.49	46.54	0	106.03	86.20	0	451.76	232.97
1+50	0	25.5	45.32	0	65.73	85.06	0	517.49	318.03
2+00	1.03	0	43.46	0.95	23.61	82.20	0.95	541.10	400.23
2+50	12.23	0	25.46	12.28	0.00	63.81	13.23	541.10	464.05
3+00	29.66	0	13.77	38.79	0.00	36.32	52.02	541.10	500.37
3+47.77	41.65	0	3.84	63.08	0.00	15.58	115.1	541.10	515.95
3+69.91	160.55	0	0	82.91	0.00	1.57	198.01	541.10	517.52
3+97.03	112.19	0	0	136.98	0.00	0.00	334.99	541.10	517.52
					0.00			541.10	517.52