



TOTAL BILL OF MATERIALS*		
ITEMS	UNITS	TOTAL
PAVEMENT MARKING (6" White)	LF	1459
PAVEMENT MARKING (12" White)	LF	209
PAVEMENT MARKING (24" White)	LF	82
PAVEMENT MARKING (4" Yellow)	LF	12,466
PAVEMENT MARKING (12" Yellow)	LF	158
PAVEMENT MARKING, TURN ARROW (LT) (White)	EA	22
PAVEMENT MARKING, TURN ARROW (RT) (White)	EA	6
PAVEMENT MARKING REMOVAL	LF	150
PAVEMENT MARKING REMOVAL, TURN ARROW	EA	2

*FOR INFORMATION ONLY (Contractor to Bid as Needed)

NOTES:

PAVMENT MARKINGS:

All pavement markings shall be thermoplastic (cold plastic). Pavement markings shall be installed per manufacturer's recommendations and shall meet KDOT's 90M-100-R10 specification (City Standard Specifications). Full Traffic may not be restored (and substantial Project Completion achieved) until all pavement markings are in place. Should construction timing be such that restoration of traffic becomes necessary during temperatures prohibiting the installation of thermoplastic markings, the Contractor shall install and maintain temporary markings until such time that thermoplastic markings may be properly installed. Except for material requirement, temporary pavement markings shall be placed equivalent, in every manner (i.e. dimension, frequency, spacing, etc.), to the permanent marking layout. The cost for temporary pavement markings will not be paid for directly, but shall be considered *SUBSIDIARY* to the bid item for "Pavement Markings".

NOTE:
Remove any Traffic Control Signs and Marking that are Nullified by this New Construction.
(Cost to be Incidental to Project)

NOTE:
All Dimensions Shown are to Centerline of Markings Unless Otherwise Noted.

