



FIRE HYDRANTS REQUIRED

<i>Line No.</i>	<i>Station</i>	<i>Bury Line Elevation</i>	<i>Top of Pipe Elevation</i>	<i>Hydrant Bury Required</i>	<i>Valve Stem Extension Required</i>
1,	3+68.25	1356.31	1352.43	4.5'	
1,	10+32.36	1360.40	1356.02	5.0'	
1,	17+30.30	1366.48	1362.10	5.0'	
2,	10+89.02	1348.50	1344.62	4.5'	
2,	18+21.82	1347.90	1344.00	4.5'	
2,	24+39.73	1351.85	1348.04	4.5'	
2,	31+11.04	1354.12	1350.24	4.5'	
2,	37+67.64	1356.80	1352.41	5.0'	
4,	0+15.93	1346.34	1342.46	4.5'	
4,	6+56.00	1350.03	1345.65	5.0'	
4,	12+73.72	1355.68	1351.89	4.5'	
4,	15+97.30	1358.34	1354.46	4.5'	
4,	19+52.85	1359.04	1354.66	5.0'	
5,	0+17.00	1363.69	1360.29	4.0'	
5,	7+42.02	1367.18	1363.30	4.5'	
5,	13+50.00	1373.20	1369.92	4.5'	
5,	20+13.87	1372.91	1368.53	5.0	
5,	26+79.58	1375.50	1371.15	5.0'	
6,	0+15.21	1368.49	1364.61	4.5'	
6,	6+67.84	1373.64	1369.26	5.0'	
6,	13+40.32	1377.71	1372.83	5.5'	0.5'
6,	19+48.55	1379.73	1375.42	5.0'	
6,	22+83.50	1380.14	1376.34	4.5'	
7,	0+15.74	1353.05	1348.67	5.0'	
7,	6+52.14	1361.36	1356.48	5.5'	0.5'
7,	12+57.27	1364.21	1360.33	4.5'	
7,	19+36.67	1369.26	1364.88	5.0'	
7,	26+02.15	1373.36	1369.48	4.5'	
7,	32+65.32	1375.16	1371.28	4.5'	
8,	0+29.00	1367.60	1364.16	4.5'	
8,	7+50.64	1371.08	1366.20	5.5'	0.5'
9A,	0+57.00	1351.86	1348.05	4.5'	
11,	3+76.03	1377.75	1373.44	5.0'	
11,	9+14.43	1378.30	1374.50	4.5'	

WATER MAIN REPLACEMENT HYDRANT TABLE

	 RUGGLES & BOHM			DATE 04/29/2015
	ENGINEERING SURVEYING LANDSCAPE ARCHITECTURE GOVERNMENT 924 NORTH MAIN WICHITA, KANSAS 67203 P (316) 264-8008 F (316) 264-4021 WWW.RBKANSAS.COM			DESIGN RA / EJG
PROJECT NUMBER 448-90611	RB JOB NO. 4227W	DWG. SCALE NONE	DRAWN RA / DRS	
DRAWING FILE Details [HYDRANT TABLE]			REVIEW 01/07/2015	SHEET 3 OF 40