

EXCAVATION				LOOSE FILL				COMPACTED FILL			
Station	Area	CY	Total	Station	Area	CY	Total	Station	Area	CY	Total
0+90.45	27.49	0.00	0.00	0+90.45	2.18	0.00	0.00	0+90.45	0.04	0.00	0.00
1+00.00	26.74	9.61	9.61	1+00.00	5.22	1.31	1.31	1+00.00	0.86	0.19	0.19
1+50.00	22.94	45.87	55.48	1+50.00	6.05	10.46	11.78	1+50.00	3.74	3.84	4.03
2+00.00	21.85	41.35	96.83	2+00.00	4.75	10.11	21.88	2+00.00	2.62	5.30	9.32
2+50.00	20.05	38.73	135.56	2+50.00	3.98	8.21	30.09	2+50.00	1.20	3.18	12.51
3+00.00	14.98	32.43	167.99	3+00.00	6.53	9.80	39.89	3+00.00	1.96	2.63	15.14
3+50.00	14.51	27.40	195.40	3+50.00	6.15	11.69	51.58	3+50.00	2.36	3.61	18.75
4+03.03	17.51	31.75	227.14	4+03.03	4.98	10.52	62.11	4+03.03	3.29	5.00	23.75
4+33.35	27.08	25.69	252.84	4+33.35	4.43	4.91	67.02	4+33.35	3.06	3.21	26.97
4+63.67	19.29	26.64	279.48	4+63.67	8.07	6.88	73.90	4+63.67	2.57	2.85	29.82
5+00.00	16.43	24.17	303.65	5+00.00	9.66	12.04	85.94	5+00.00	3.34	3.59	33.40
5+54.41	10.74	27.50	331.15	5+54.41	13.17	23.22	109.15	5+54.41	2.80	5.58	38.98
5+84.52	9.64	11.66	342.82	5+84.52	11.04	12.86	122.01	5+84.52	1.09	2.34	41.32
6+13.30	6.12	8.99	351.81	6+13.30	17.53	13.89	135.90	6+13.30	5.86	4.05	45.36
6+50.00	13.35	13.62	365.43	6+50.00	14.90	20.47	156.37	6+50.00	2.42	6.31	51.67
7+00.00	12.63	24.34	389.77	7+00.00	12.04	23.13	179.50	7+00.00	1.51	4.18	55.86
7+50.00	21.48	31.56	421.33	7+50.00	5.78	15.61	195.11	7+50.00	2.00	3.73	59.59
8+00.99	23.98	42.73	464.06	8+00.99	1.27	6.63	201.74	8+00.99	0.42	2.43	62.02

